


# DETAILED DRAWINGS

ENGLISH EDITION  
EFFECTIVE: DECEMBER 2002



 MONTANA DEPARTMENT  
OF TRANSPORTATION

SUPPLEMENTAL TO  
THE STANDARD  
SPECIFICATIONS FOR  
ROAD AND BRIDGE  
CONSTRUCTION



# ***DETAILED DRAWINGS***

## **TABLE OF CONTENTS**

**ENGLISH EDITION  
EFFECTIVE: DECEMBER 2002  
REVISED: JANUARY 2004**

STANDARD SPECIFICATION SECTION AND DRAWING TITLE	DRAWING NUMBER
<b><u>SECTION 101: DEFINITIONS AND TERMS</u></b>	
ABBREVIATIONS .....	101-05
ABBREVIATIONS .....	101-06
ABBREVIATIONS .....	101-07
SYMBOLS .....	101-10
<b><u>SECTION 203: EXCAVATION AND EMBANKMENT</u></b>	
ROADWAY EMBANKMENT AT BRIDGE END .....	203-00
APPROACHES .....	203-05
MAILBOX TURNOUT .....	203-15
DITCH BLOCKS .....	203-20
<b><u>SECTION 208: WATER POLLUTION CONTROL AND STREAM PRESERVATION</u></b>	
SCHEDULE OF BEST MANAGEMENT PRACTICES .....	208-00
INLET/OUTLET PROTECTION .....	208-1A
WATERWAY PROTECTION .....	208-1B
WATER RESOURCE PROTECTION .....	208-1C
PRESERVATION OF EXISTING VEGETATION (SS-2) .....	208-02
HYDRAULIC MULCH (SS-3) .....	208-04
TEMPORARY SEEDING (SS-4) .....	208-06
SOIL BINDERS (SS-5) .....	208-08
STRAW MULCH (SS-6) .....	208-10
GEOTEXTILES, PLASTIC COVERS & EROSION CONT. BLANKETS /MATS (SS-7) .....	208-12A
GEOTEXTILES, PLASTIC COVERS & EROSION CONT. BLANKETS /MATS (SS-7) .....	208-12B
WOOD MULCH (SS-8) .....	208-14
EARTH DIKES /DRAINAGE SWALES & LINED DITCHES (SS-9) .....	208-16
OUTLET PROTECTION /VELOCITY DISSIPATION DEVICES (SS-10) .....	208-18
SLOPE DRAINS (SS-11) .....	208-20
SLOPE ROUGHENING (SS-12) .....	208-22
TERRACED SLOPES (SS-13) .....	208-24
VEGETATED BUFFER (SS-14) .....	208-26
EROSION SEEDING (SS-15) .....	208-28
SILT FENCE (SC-1) .....	208-30
DESILTING BASIN (SC-2) .....	208-32A
DESILTING BASIN (SC-2) .....	208-32B
SEDIMENT TRAP (SC-3) .....	208-34
CHECK DAMS (SC-4) .....	208-36
FIBER ROLLS (SC-5) .....	208-38
GRAVEL BAG BERM (SC-6) .....	208-40
SAND BAG BARRIERS (SC-8) .....	208-42
STRAW BALE BARRIERS (SC-9) .....	208-44

STANDARD SPECIFICATION SECTION AND DRAWING TITLE	DRAWING NUMBER
STORM DRAIN INLET PROTECTION (SC-10) .....	208-46A
STORM DRAIN INLET PROTECTION (SC-10) .....	208-46B
DUGOUT DITCH BASIN (SC-11) .....	208-48
WIND EROSION CONTROL (WE-1) .....	208-50
SNOW ACCUMULATION MANAGEMENT (SN-2) .....	208-52
FREEZE REDUCTION (SN-3) .....	208-54
STABALIZED CONSTRUCTION ENTRANCE /EXIT (TC-1) .....	208-56
ENTRANCE /EXIT TIRE WASH (TC-3) .....	208-58
TEMPORARY STREAM CROSSINGS (NS-4) .....	208-60
<b><u>SECTION 401: COLD MILLING</u></b>	
SHOULDER RUMBLE STRIPS .....	401-02
<b><u>SECTION 552: CONCRETE STRUCTURES</u></b>	
CONCRETE CUTOFF WALLS FOR CULVERTS .....	552-00
CONCRETE, RIPRAP AND BEDDING MATERIAL QUANTITIES FOR SING. AND DBL. CULVERT INSTALLATION .....	552-04
CONCRETE, RIPRAP AND BEDDING MATERIAL QUANTITIES FOR SING. AND DBL. CULVERT INSTALLATION .....	552-06
CONCRETE, RIPRAP AND BEDDING MATERIAL QUANTITIES FOR SING. AND DBL. CULVERT INSTALLATION .....	552-08
<b><u>SECTION 603: CULVERTS, STORM DRAINS, SANITARY SEWERS, STOCKPASSES AND UNDERPASSES</u></b>	
CMP FLARED END TERMINAL SECTION (FETS) .....	603-02
PREFABRICATED RCP FLARED END TERMINAL SECTION (FETS) .....	603-08
PREFABRICATED RCP ARCH FLARED END TERMINAL SECTION (FETS) .....	603-10
RCP ROAD APPROACH CULVERT END TREATMENT (RACET) .....	603-12
CMP ROAD APPROACH CULVERT END TREATMENT (RACET) .....	603-14
PRECAST MEDIAN U-TURN CROSS DRAIN AND CONC. BEVELED END .....	603-17
CSP AND SSPP CULVERT BEDDING .....	603-18
RCP CULVERT BEDDING .....	603-20
WATER TIGHT JOINT FOR REINFORCED CONCRETE PIPE .....	603-22
REINFORCED CONCRETE PIPE JOINT .....	603-24
TYPICAL FIELD CAST CONCRETE CONNECTIONS .....	603-26
EMBANKMENT PROTECTOR .....	603-28
VEHICULAR UNDERPASS AND BACKFILL RETAINER & CUTOFF WALL DETAIL .....	603-30
STEP BEVEL FOR CIRCULAR METAL CULVERT .....	603-32
BEVEL ON ARCH METAL CULVERT .....	603-34
CORRUGATED STEEL PIPE STOCKPASS .....	603-36
<b><u>SECTION 604: MANHOLES, COMBINATION MANHOLES AND INLETS, AND INLETS</u></b>	
MEDIAN INLET COVER .....	604-00
CONCRETE MANHOLE .....	604-02
CURB INLET TYPE II .....	604-03
DROP INLET TYPE IV .....	604-04
TYPE IV DROP INLET WITH SLOTTED DRAIN .....	604-06
TYPE II CURB INLET WITH SLOTTED DRAIN .....	604-08
DROP INLETS .....	604-14



STANDARD SPECIFICATION SECTION AND  
DRAWING TITLE

DRAWING  
NUMBER

SECTION 606: GUARDRAIL AND CONCRETE BARRIER RAIL

METAL GUARDRAIL – WOOD POSTS .....	606-05A
METAL GUARDRAIL – STEEL POSTS .....	606-05B
STIFFENED GUARDRAIL SECTIONS .....	606-07
OPTIONAL TERMINAL SECTION – ET-PLUS .....	606-13A
OPTIONAL TERMINAL SECTION – SKT 350 .....	606-13B
ONE-WAY DEPARTURE TERMINAL SECTION .....	606-18
BRIDGE APPROACH SECTIONS – WOOD POSTS .....	606-24A
BRIDGE APPROACH SECTIONS – STEEL POSTS .....	606-24B
SKEWED BRIDGE APPROACH SECTIONS – WOOD POSTS .....	606-25A
SKEWED BRIDGE APPROACH SECTIONS – STEEL POSTS .....	606-25B
TAPERED CONCRETE CURB DETAIL .....	606-26
TAPERED CONCRETE CURB DETAIL .....	606-27
IMPACT ATTENUATOR – QUADGUARD .....	606-30A
IMPACT ATTENUATOR – TRACC .....	606-30B
IMPACT ATTENUATOR – QUADGUARD ASSEMBLY DETAILS .....	606-31A
IMPACT ATTENUATOR – TRACC ASSEMBLY DETAILS .....	606-31B
CABLE GUARDRAIL .....	606-40
CABLE GUARDRAIL TERMINAL ANCHOR ASSEMBLY .....	606-41
INTERSECTING ROADWAY TERMINAL SECTION .....	606-46
BOX BEAM GUARDRAIL .....	606-50
BOX BEAM ONE-WAY DEPARTURE TERMINAL SECTION .....	606-52
BOX BEAM BRIDGE APPROACH SECTIONS .....	606-53
BOX BEAM ONE-WAY BRIDGE DEPARTURE SECTION .....	606-54
OPTIONAL BOX BEAM TERMINAL SECTION – WY-BET .....	606-55A
OPTIONAL BOX BEAM TERMINAL SECTION – BEAT .....	606-55B
WY-BET BOX BEAM TERMINAL SECTION DETAILS .....	606-56A
BEAT BOX BEAM TERMINAL SECTION DETAILS .....	606-56B
CONCRETE BARRIER RAIL .....	606-60
ALTERNATE CONCRETE BARRIER RAIL .....	606-61
TALL CONCRETE BARRIER RAIL .....	606-64
ALTERNATE TALL CONCRETE BARRIER RAIL .....	606-65
CONCRETE BARRIER RAIL TRANSITION .....	606-66
CONCRETE BARRIER RAIL TERMINAL SECTION (ONE-WAY DEPARTURE) .....	606-68
SCHEDULE OF GUARDRAIL HARDWARE .....	606-80
GUARDRAIL HARDWARE .....	606-82
W-BEAM METAL GUARDRAIL HARDWARE .....	606-84
W-BEAM METAL GUARDRAIL HARDWARE .....	606-88
CABLE GUARDRAIL HARDWARE .....	606-92
CABLE GUARDRAIL HARDWARE .....	606-94
CABLE GUARDRAIL HARDWARE .....	606-95
BOX BEAM GUARDRAIL HARDWARE .....	606-97
BOX BEAM GUARDRAIL HARDWARE .....	606-98

SECTION 607: FENCES

FARM FENCE .....	607-00
INTERSTATE FENCE .....	607-05
FENCING DETAILS .....	607-10

STANDARD SPECIFICATION SECTION AND  
DRAWING TITLE

DRAWING  
NUMBER

FENCING DETAILS .....	607-15
FARM ENTRANCE GATES .....	607-20
CHAIN LINK FENCE .....	607-25
8' WOOD SNOW FENCE W/ANCHOR SYSTEM #1 .....	607-30
12' WOOD SNOW FENCE W/ANCHOR SYSTEM #1 .....	607-35
WOOD SNOW FENCE ANCHOR SYSTEM #3 AND #1 DETAILS .....	607-40
WOOD SNOW FENCE ANCHOR SYSTEM #2 DETAILS .....	607-45

SECTION 608: CONCRETE SIDEWALKS

CONCRETE SIDEWALK .....	608-05
NEW CONSTRUCTION PUBLIC SIDEWALK CURB RAMPS .....	608-15
ALTERATIONS TO EXISTING FACILITIES – PUBLIC SIDEWALK CURB RAMPS .....	608-20
PERPENDICULAR PUBLIC SIDEWALK CURB RAMPS .....	608-25
PARALLEL PUBLIC SIDEWALK CURB RAMPS .....	608-30
DIAGONAL PUBLIC SIDEWALK CURB RAMPS .....	608-35

SECTION 609: CURBS AND GUTTERS

CONCRETE VALLEY GUTTER .....	609-00
MISCELLANEOUS CURBS .....	609-05
MEDIAN CONCRETE CURBS .....	609-10
CONCRETE MEDIAN CAPS .....	609-12

SECTION 610: ROADSIDE RE-VEGETATION

TOPSOIL AND SEEDING .....	610-00
---------------------------	--------

SECTION 611: CATTLE GUARDS

CAST-IN-PLACE CATTLE GUARD .....	611-00
CAST-IN-PLACE CATTLE GUARD REBAR DETAILS .....	611-05
PRECAST CONCRETE BASE FOR CATTLE GUARD – APPROACHES .....	611-10
PRECAST CONCRETE BASE FOR CATTLE GUARD .....	611-15
PRECAST CONCRETE CATTLE GUARD BASE DETAILS .....	611-20

SECTION 613: RIPRAP AND SLOPE AND BANK PROTECTION

CONCRETE EDGE PROTECTION FOR METAL CULVERTS .....	613-06
CONCRETE EDGE PROTECTION FOR CONCRETE CULVERTS .....	613-08
CONCRETE SLOPE PROTECTION .....	613-10
INLET AND OUTLET HEADWALLS FOR RCP AND CMP PIPES .....	613-12
CULVERT RIPRAP .....	613-14
EMBANKMENT PROTECTION .....	613-16
CONCRETE DRAINAGE CHUTE .....	613-18

SECTION 615: IRRIGATION FACILITIES AND HEADWALLS

TRASHGUARD FOR CONCRETE IRRIGATION INLET AND OUTLET TRANSITION STRUCTURES .....	615-02
STANDARD CONCRETE IRRIGATION DIVISION BOXES .....	615-04
CONCRETE IRRIGATION INLET AND OUTLET TRANSITION FOR RCP AND CSP PIPES .....	615-06



STANDARD SPECIFICATION SECTION AND  
DRAWING TITLE

DRAWING  
NUMBER

SECTION 617: TRAFFIC SIGNALS AND LIGHTING

ROAD CLOSURE GATE .....	617-00
ROAD CLOSURE GATE DETAILS .....	617-02
ROAD CLOSURE GATE PIVOT ASSEMBLY .....	617-04
ROAD CLOSURE GATE PIVOT ASSEMBLY DETAILS .....	617-06
FOUR BOLT SLIP BASE .....	617-08
FOUR BOLT SLIP BASE DETAILS .....	617-10

SECTION 618: TRAFFIC CONTROL

BARRICADES AND CHANNELIZING DEVICES .....	618-00
CONSTRUCTION SIGN DETAILS .....	618-01
PORTABLE SIGN SUPPORT ASSEMBLY .....	618-02
TWO-LANE CONSTRUCTION PROJECT .....	618-04
TWO-LANE CONSTRUCTION PROJECT WORK ZONES .....	618-08
TWO-LANE CONSTRUCTION PROJECT SEAL COAT .....	618-10
TWO-LANE CONSTRUCTION PROJECT LANE CLOSURE .....	618-12
TWO-LANE EQUIPMENT ENTRANCES ON LOW VOLUME ROADS .....	618-14
TWO-LANE EQUIPMENT ENTRANCES .....	618-16
TWO-LANE CONSTRUCTION PROJECT DETOUR .....	618-18
FOUR-LANE CONSTRUCTION PROJECT .....	618-20
TEMPORARY ENTRANCE RAMP MEDIAN CROSSING .....	618-21
TEMPORARY EXIT RAMP MEDIAN CROSSING .....	618-22
FOUR-LANE CONSTRUCTION PROJECT WORK ZONES .....	618-24
FOUR-LANE EQUIPMENT ENTRANCES .....	618-27
FOUR-LANE MEDIAN CROSSINGS .....	618-28
TEMPORARY FOUR-LANE TO TWO-LANE MEDIAN CROSSING .....	618-30
TEMPORARY TWO-LANE TO FOUR-LANE MEDIAN CROSSING .....	618-32
SHORT DURATION CREW SIGNING .....	618-34
SHORT-TERM STATIONARY CREW SIGNING .....	618-36
MAINTENANCE GUIDELINE FOR SHORT-TERM TWO-LANE CRACK SEALING WORK ZONE .....	618-M1
MAINTENANCE GUIDELINE FOR SHORT-TERM TWO-LANE CHIP SEAL AND OVERLAY (PILOTED TRAFFIC) .....	618-M2
MAINTENANCE GUIDELINE FOR SHORT-TERM LANE CLOSURE ON INTERSTATE .....	618-M3

SECTION 619: SIGNS, DELINEATORS AND GUIDEPOSTS

SIGN CLEARANCES AND MOUNTING HEIGHTS .....	619-00
TYPICAL RURAL AND URBAN APPROACHES .....	619-02
ALUMINUM SHEET INCREMENT SIGN CONSTRUCTION DETAILS .....	619-04
PLYWOOD SHEET INCREMENT GUIDE SIGN CONSTRUCTION DETAILS .....	619-06
GUIDE SIGN CLEARANCE AND MOUNTING DETAILS .....	619-08
SHEET ALUMINUM OVERLAY .....	619-10
TUBULAR SIGN POST DETAILS .....	619-12
BREAKAWAY AND FOUNDATION DETAILS FOR MULTIPLE GUIDE SIGN SUPPORTS .....	619-13
TYPICAL STEEL POST MOUNTING DETAILS .....	619-16
CANTILEVER TYPE SIGN SUPPORT DETAILS FOR SIDEWALK AREAS .....	619-18
STRUCTURAL STEEL POST SIGN MOUNTING DETAILS .....	619-19

STANDARD SPECIFICATION SECTION AND  
DRAWING TITLE

DRAWING  
NUMBER

TREATED WOOD POLE SIGN MOUNTING AND SUPPORT DETAILS .....	619-20
TREATED WOOD POLE SIGN MOUNTING DETAILS .....	619-21
TREATED WOOD POLE OPTIONAL BACKBRACE .....	619-22
CHEVRON MOUNTING DETAILS .....	619-24
SPECIAL DESIGN ROUTE MARKER PANELS AND SHIELDS .....	619-26
SIGN HINGE DETAILS .....	619-30
MILEPOST DETAILS .....	619-32
DELINEATOR DETAILS .....	619-34
DELINEATOR PLACEMENT DETAILS .....	619-36
OBJECT MARKER DESIGN AND PLACEMENT DETAILS FOR OBSTRUCTIONS ADJACENT TO OR WITHIN HIGHWAYS .....	619-38
FLEXIBLE DELINEATORS .....	619-40
PERMANENT BARRICADE DESIGN DETAILS .....	619-42
INSTALLATION DATE TAGS .....	619-44

SECTION 621: REMOVE, RE-SET AND ADJUST FACILITIES

MANHOLE AND VALVE BOX ADJUSTMENT DETAILS .....	621-00
OPTIONAL MANHOLE AND VALVE BOX ADJUSTMENT DETAILS .....	621-05

MISCELLANEOUS

U-TURN MEDIAN OPENINGS ON CONTROLLED ACCESS HIGHWAYS .....	900-00
MAILBOX DETAIL .....	900-05
OPTIONAL MAILBOX DETAIL .....	900-10





&	AND	CONST. PMT.	CONSTRUCTION PERMIT
@	AT	COR.	CORNER
A. A. D. T.	ANNUAL AVERAGE DAILY TRAFFIC	CORR.	CORRECTED OR CORRUGATION
AASHTO	AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS	COV.	COVER
AB.	ABRUPT	C. P.	CATCH POINT
A. C.	ALUMINUM CAP OR ASPHALT CEMENT	CR.	CRUSHED OR CREEK
ADD. EXC.	ADDITIONAL EXCAVATION	CRS.	COURSE
ADJ.	ADJUSTED	CS	CURVE TO SPIRAL
A. D. T.	AVERAGE DAILY TRAFFIC	C. S. F.	COMBINATION SCALE FACTOR
AGC	ASSOCIATED GENERAL CONTRACTORS OF AMERICA	CSP	CORRUGATED STEEL PIPE
AGG.	AGGREGATE	CSPA	CORRUGATED STEEL PIPE ARCH
AH.	AHEAD	CT.	COURT
ANSI	AMERICAN NATIONAL STANDARDS INSTITUTE	C. T. B.	CEMENT TREATED BASE
APP.	APPROACH	CTR.	CENTER
APPL.	APPLICATION	CTS	CRUSHED TOP SURFACING
APPROX.	APPROXIMATE	CULV.	CULVERT
ARTBA	AMERICAN ROAD AND TRANSPORTATION BUILDERS ASSOCIATION	C. Y.	CUBIC YARD
ASPH.	ASPHALT	D	DEGREE OF CURVATURE OR DISTRIBUTION OF TRAFFIC
ASTM	AMERICAN SOCIETY FOR TESTING & MATERIALS	DBL.	DOUBLE
AVE.	AVENUE	D <sub>c</sub>	DEGREE OF CURVATURE (WITH SPIRALS)
AVG.	AVERAGE	D. D.	DOWN DRAIN
AWS	AMERICAN WELDING SOCIETY	DE	DIFFERENCE IN ELEVATION
AZ.	AZIMUTH	DEFL.	DEFLECTION
		DESC.	DESCRIPTION
BAL.	BALANCE	DEST.	DESTROYED
BBL.	BARREL	DET.	DETOUR OR DETAIL
B. C.	BRASS CAP	DETC.	DETECTOR
B. C. R.	BEGIN CURB RETURN	D. H.	DRILL HOLE
B. E.	BRIDGE END	D. H. V.	DESIGN HOURLY VOLUME
BEG.	BEGIN	D. I.	DROP INLET
BIT.	BITUMINOUS OR BITUMEN	DIA.	DIAMETER
BK.	BACK OR BANK	DIST.	DISTANCE OR DISTRICT
BLDG.	BUILDING	DN.	DOWN
BLK.	BLOCK	DP.	DEEP
B. L. M.	U. S. BUREAU OF LAND MANAGEMENT	DR.	DRAIN OR DRIVE
BLVD.	BOULEVARD	DT.	DITCH
B. M.	BENCH MARK	DTL.	DETAILED
BNDRY.	BOUNDARY	DWG.	DRAWING
BOT.	BOTTOM	DY.	DAYLIGHT
BR.	BRIDGE		
B. R.	BASE OF RAIL	E	EAST OR EXTERNAL DISTANCE
BRG.	BEARING	EB	EASTBOUND
B. S.	BACKSIGHT	E. C. R.	END CURB RETURN
B. S. T.	BITUMINOUS SURFACE TREATMENT	EDM	ELECTRONIC DISTANCE MEASUREMENT
B. W. FE.	BARBED WIRE FENCE	E. G.	EDGE OF GUTTER
		ELEV. OR EL.	ELEVATION
C	CUT	ELONG.	ELONGATED
C/A	CONTROL OF ACCESS	ELY.	EASTERLY
CALC.	CALCULATED	EMB.	EMBANKMENT
CAP	CORRUGATED ALUMINUM PIPE	EMUL.	EMULSIFIED
CATV	CABLE TV	E. O.	EDGE OF OIL
CB.	CURB	E. P.	EDGE OF PAVEMENT
C. B.	CATCH BASIN	EQ.	EQUATION
C. B. W.	CONCRETE BLOCK WALL	E <sub>s</sub>	EXTERNAL DISTANCE (WITH SPIRALS)
C. C.	CLOSING CORNER	E. S.	EDGE OF SHOULDER
CDTN.	CONDITION	ESMT. OR EASE.	EASEMENT
CEM.	CEMENT	ETW	EDGE OF TRAVELED WAY
C&G	CURB & GUTTER	EW.	END WALL
CH.	CHANNEL OR CHAIN	EX.	EXISTING
CH. CH.	CHANNEL CHANGE	EXC.	EXCAVATION
CHD.	CHORD	EXT.	EXTENSION
CHIS. "x"	CHISELED CROSS	EXWY.	EXPRESSWAY
C. I.	CURB INLET		
CIR.	CIRCLE	F	FILL
CL.	CLASS OR CLEARANCE	F. A.	FEDERAL AID
CL-4F, 5F	CHAIN LINK FENCE (W/ HEIGHT)	F. C.	FLOOD CONTROL
C/L OR C	CENTERLINE	FD.	FOUND
CMP	CORRUGATED METAL PIPE		
C. N.	CONCRETE NAIL		
CO.	COUNTY OR COMPANY		
C. O.	CLEAN OUT		
COMP.	COMPACTION		
CONC.	CONCRETE		
COND. (TEL. )	CONDUIT (SPECIFY TYPE)		
CONN.	CONNECTION		
CONST.	CONSTRUCTION		

DETAILED DRAWING

REFERENCE DWG. NO.  
STANDARD SPEC. 101-05  
SECTION 101

ABBREVIATIONS

EFFECTIVE: DECEMBER 2002

 MONTANA DEPARTMENT OF TRANSPORTATION  MONTANA CADD



FDN.	FOUNDATION	LT.	LEFT
FE.	FENCE		
FERT.	FERTILIZER	MATL.	MATERIAL
FETS	FLARED END TERMINAL SECTION	MAX.	MAXIMUM
F. G.	FINISHED GRADE	MC	MEDIUM CURING
F. G. S.	FINISHED GRADE STAKE	MDT	MONTANA DEPARTMENT OF TRANSPORTATION
F. H.	FIRE HYDRANT	MEAS.	MEASURED
FHWA	FEDERAL HIGHWAY ADMINISTRATION	MED.	MEDIAN
FIN.	FINISH	MH.	MANHOLE
FL.	FLUSH	MIN.	MINIMUM, MINERAL OR MINUTE
F. L.	FLOW LINE	MISC.	MISCELLANEOUS
F. O.	FIBER OPTIC CABLE	MKR.	MARKER
F. P.	FENCE POST	M. L.	MAINLINE
FR	FRONTAGE	MNCPL.	MUNICIPAL
FR. RD.	FRONTAGE ROAD	M. O.	MID ORDINATE
F. S.	FORESIGHT	MON.	MONUMENT
FT.	FOOT	MPC	MID-POINT OF CURVE
FTG.	FOOTING	MUTCD	MANUAL FOR UNIFORM TRAFFIC CONTROL DEVICES
FUT.	FUTURE		
FWY.	FREEWAY	M. Y.	MILE YARD
G	GRADING	N	NORTH
GA.	GAGE	NB	NORTHBOUND
GALL.	GALLON	N. C.	NORMAL CROWN
GALV.	GALVANIZED	N. E.	NORTHEAST
GAR.	GARAGE	N. G.	NATURAL GAS
GEOD.	GEODETIC	N. G. S.	NATIONAL GEODETIC SURVEY
G. L.	GAS LINE	NL.	NAIL
G. L. O.	GENERAL LAND OFFICE	NLY.	NORTHERLY
GPS	GLOBAL POSITIONING SYSTEM	NO. OR #	NUMBER
GR.	GRADE	N. W.	NORTHWEST
G. R.	GUARDRAIL	N. W. EL.	NORMAL WATER ELEVATION
GRD	GRID		
GRND.	GROUND	O. OR O/S	OFFSET
GR. SEP.	GRADE SEPARATION	O. C.	ON CENTERS OR OVERHEAD CROSSING
G. S.	GRAVEL SURFACING	O. D.	OUTSIDE DIAMETER
GSP	GALVANIZED STEEL PIPE	O. G.	OLD GROUND OR ORIGINAL GROUND
GTR.	GUTTER	OH.	OVERHANG OR OVERHEAD
G. V.	GAS VALVE	O' PASS	OVERPASS
HDWL.	HEADWALL	P	POWER CABLE OR PIPE
HG.	HEADGATE	P. OR PG.	PAGE
H. I.	HEIGHT OF INSTRUMENT	PAVT.	PAVEMENT
HO.	HOUSE	P. B.	PULL BOX
HOR.	HORIZONTAL	PC	POINT OF CURVE (BEGINNING)
H. P.	HINGE POINT	PCC	POINT OF COMPOUND CURVE OR PORTLAND CEMENT CONCRETE
HT.	HEIGHT		
H&T	HUB & TACK	P. C. S.	PROJECT CONTROL SYSTEM
H. W.	HIGH WATER	P. E.	PRELIMINARY ENGINEERING
HWY.	HIGHWAY	PEN.	PENETRATION
		PERF.	PERFORATED
I	INTERSTATE	PI	POINT OF INTERSECTION
I. C.	INCIDENTAL CONSTRUCTION	PL.	PLACE, PLATE OR PLANT
I. D.	INSIDE DIAMETER	P. L.	PROPERTY LINE
I. E.	INVERT ELEVATION	PLAS.	PLASTIC
INC.	INCORPORATED OR INCREMENT	P. M.	PRINCIPAL MERIDIAN OR PUNCH MARK
INCL.	INCLUDED	P. M. B.	PLANT MIX BASE
INSTR.	INSTRUMENT	P. M. P.	PERFORATED METAL PIPE
INT.	INTERSECTION	PMS	PLANT MIX SURFACING
INTCH.	INTERCHANGE	PMT.	PERMIT
INV.	INVERT	POC	POINT ON CURVE
I. P.	IRON PIN	POL	POINT ON LINE
IRR.	IRRIGATION	POS	POINT ON SPIRAL
I. R. T. S.	INTERSECTING ROADWAY TERMINAL SECTION	POST	POINT ON SEMI-TANGENT
		POT	POINT ON TANGENT
JCT.	JUNCTION	POVC	POINT ON VERTICAL CURVE
J. P.	JOINT USE POLE	PP	POWER POLE
		PP.	PAGES
		PREST.	PRESTRESSED
L	LENGTH OF CURVE OR ANGLE IRON		
LB.	POUND		
L <sub>c</sub>	LENGTH OF CIRCULAR CURVE		
L. C.	LONG CHORD		
L. D.	LOOP DETECTOR		
LENG.	LENGTH OR LENGTHEN		
L. F.	LINEAR FOOT		
LN.	LANE		
L <sub>s</sub>	LENGTH OF SPIRAL		
L. S.	LAND SURVEYOR		

DETAILED DRAWING

REFERENCE DWG. NO.  
STANDARD SPEC. 101-06  
SECTION 101

ABBREVIATIONS

EFFECTIVE: DECEMBER 2002

 MONTANA DEPARTMENT OF TRANSPORTATION  MONTANA CADD



This Frame left blank



PRIM.	PRIMARY	S. W.	SOUTHWEST OR SIDEWALK
PROC.	PROCESSING	S. Y.	SQUARE YARD
PROJ.	PROJECT OR PROJECTED		
PROT.	PROTECT, PROTECTOR OR PROTECTION	T	TOWNSHIP, TANGENT LENGTH OR PERCENT TRUCKS
PT	POINT OF TANGENT (END OF CURVE)		
PT.	POINT	TAN.	TANGENT
PTW	PRESENT TRAVELED WAY	T. B. C.	TOP BACK OF CURB
PVC	POLYVINYL CHLORIDE	T. B. M.	TEMPORARY BENCH MARK
PVT.	PRIVATE	TBR.	TIMBER
PWR.	POWER (LINES)	TEL.	TELEPHONE
		TEL. C.	TELEPHONE CABLE
O	PEAK DISCHARGE (WATER)	TEL.G.	TELEGRAPH
QTY.	QUANTITY	TEL. P.	TELEPHONE POLE
		TEMP.	TEMPERATURE OR TEMPORARY
R	RANGE, RADIUS OR RISE	THK.	THICKNESS
RACET	ROAD APPROACH CULVERT END TREATMENT	TK.	TACK
R <sub>c</sub>	SPIRAL CURVE RADIUS	TOPOG.	TOPOGRAPHIC
RC	RAPID CURING	T. P.	TURNING POINT
RCB	REINFORCED CONCRETE BOX	TR.	TRACT
RCP	REINFORCED CONCRETE PIPE	TRANS.	TRANSMISSION LINE OR TRANSITION
RCPA	REINFORCED CONCRETE PIPE ARCH	TRAV.	TRAVERSE
RD.	ROAD	TRIA.	TRIANGULATION
RDL.	RADIAL	T <sub>s</sub>	LENGTH OF TANGENT (CURVE WITH SPIRALS)
RDWY.	ROADWAY	TS	TANGENT TO SPIRAL
REC.	RECORD	TT	TRANSMISSION TOWER
REF.	REFERENCE	TYP.	TYPICAL
REINF.	REINFORCEMENT		
RET. W.	RETAINING WALL	U	UNIT
RIV.	RIVER	U. G.	UNDERGROUND
R. M.	REFERENCE MONUMENT	UNCL.	UNCLASSIFIED
R. P.	REFERENCE POINT, RADIUS POINT	U' PASS	UNDERPASS
R. R.	RAILROAD	U. S. C. & G. S.	U. S. COAST & GEODETIC SURVEY
RT.	RIGHT OR ROUTE	U. S. C. E.	U. S. CORPS OF ENGINEERS
RTE.	ROUTE	U. S. F. S.	U. S. FOREST SERVICE
R/W	RIGHT OF WAY	U. S. G. S.	U. S. GEOLOGICAL SURVEY
RY.	RAILWAY	U. S. P. L. S.	U. S. PUBLIC LAND SURVEY
S	RATE OF FULL SUPERELEVATION, SLOPE IN FT. PER FT., SPAN OR SOUTH	V	DESIGN SPEED OR VELOCITY
SA.	SATELLITE (FOR TRAVERSE USE)	V. A. B. M.	VERTICAL ANGLE BENCH MARK
SAN. SEW.	SANITARY SEWER	VC	VERTICAL CURVE
SB	SOUTHBOUND	VC CORR.	VERTICAL CURVE OFFSET CORRECTION
SC	SPIRAL TO CURVE OR SLOW CURING	V. C. M.	VERTICAL CONTROL MONUMENT
SCH.	SCHEDULE	V. C. P.	VITRIFIED CLAY PIPE
SDWK.	SIDEWALK	VEH.	VEHICULAR
S. E.	SOUTHEAST	VERT. OR VT.	VERTICAL
SEC.	SECTION, SECOND OR SECONDARY	VIT.	VITRIFIED
SEL.	SELECT	V. P.	VENT PIPE
S. G. OR SUBGR.	SUBGRADE	VPC	VERTICAL POINT OF CURVE
SH.	SHOULDER	VPI	VERTICAL POINT OF INTERSECTION
SHT.	SHEET	VPT	VERTICAL POINT OF TANGENCY
SING.	SINGLE		
SIP.	SIPHON	W	WEST
S. L. D.	SEA LEVEL DATUM	W/	WITH
SLOT. DR.	SLOTTED DRAIN	WB	WESTBOUND
SLP. STK.	SLOPE STAKE	W. C.	WITNESS CORNER
SLY.	SOUTHERLY	W. L.	WATER LINE
S. P.	STAND PIPE OR STATE PLANE	WLY.	WESTERLY
SPEC. PROV.	SPECIAL PROVISION	W/O	WITHOUT
S. P. H. P.	STEEL PIPE, HIGH PRESSURE	W. P.	WING POINT
SPK.	SPIKE	W. S.	WATER SERVICE OR WARPED OR VARIABLE SLOPE
SQ.	SQUARE	WT.	WEIGHT
SS	EMULSIFIED ASPHALT	W. T.	WATER TABLE
SSPP	STRUCTURAL STEEL PLATE PIPE	W. V.	WATER VALVE
SSPPA	STRUCTURAL STEEL PLATE PIPE ARCH	W. W.	WING WALL OR WOVEN WIRE
ST	SPIRAL TO TANGENT		
ST.	STREET	XING.	CROSSING
STA.	STATION	XSEC.	CROSS-SECTION
STD.	STANDARD		
STD. SPEC.	STANDARD SPECIFICATIONS		
STK.	STAKED OR STAKE		
STL.	STEEL		
STM.	STORM DRAIN		
STPD.	STAMPED		
STR.	STRUCTURE OR STRAIGHT		
SUBD.	SUBDIVISION		
SURF.	SURFACE OR SURFACING		
SURV.	SURVEY		

DETAILED DRAWING

REFERENCE DWG. NO.  
STANDARD SPEC. 101-07  
SECTION 101

ABBREVIATIONS

EFFECTIVE: DECEMBER 2002

 MONTANA DEPARTMENT  
OF TRANSPORTATION  MONTANA  
CADD



TITLE SHEET

	PRIMARY ROAD **
	PRIMITIVE ROAD
	PROPOSED ROAD
	GRADED ROAD
	BLADED ROAD
	PRIMITIVE ROAD
	GRAVELED ROAD (CADD *)
	PAVED ROAD
	FEDERAL AID ROUTING (ON EXISTING ROAD)
	FEDERAL AID ROUTING (NON-EXISTING ROAD)
	INTERCHANGE
	STRUCTURE
	FREE FERRY
	TOLL FERRY
	HIGHWAY TUNNEL
	PASS
	RAILROAD
	RESERVATION LINE
	STATE & NATIONAL LINE
	COUNTY LINE
	TOWNSHIP & SECTION LINE
	INTERSTATE
	U. S. HIGHWAY
	STATE HIGHWAY (CADD *)
	CITY OR TOWN
	AIR FIELD
	DAM
	BUILDING OR HOUSE
	BRIDGE

\*\* PRIMARY ROADS ARE 0.08" WIDE. ALL OTHERS ARE 0.05" WIDE.

PROFILE

	FLOWLINE AT $\epsilon$ CULVERT
	FLOWLINE AT $\epsilon$ IRRIGATION SYPHON
	FLOWLINE AT $\epsilon$ CONCRETE BOX CULVERT


CROSS SECTIONS

	POWER POLE (NO. OF WIRES AND VOLTAGE)
	TELEPHONE POLE (NO. OF WIRES)
	TELEGRAPH POLE (NO. OF WIRES)
	GUY POLE
	GUY AND ANCHOR


PLAN

	STATE & NATIONAL LINE
	COUNTY LINE
	CITY OR TOWN BOUNDARIES
	TOWNSHIP LINE
	SECTION LINE (SHOWING CORNER SOLID IF FOUND - OPEN IF NOT FOUND)
	CLOSING CORNER
	MEANDER CORNER
	OWNERSHIP TIE
	PROPERTY CORNER
	EXISTING R/W MONUMENT
	NEW R/W MONUMENT
	PROPERTY LINE
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE
	EXISTING ACCESS
	FULL ACCESS CONTROL
	LIMITED CONTROL
	EXISTING RIGHT-OF-WAY
	HIGHWAY RIGHT-OF-WAY
	RAILROAD RIGHT-OF-WAY
	BASE OR SURVEY LINE
	1/4 CORNER
	R/W
	RR R/W
	1/4 CORNER
	SECTION LINE








SECTION A-A




PLAN VIEW




SECTION B-B

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 203	DWG. NO. 203-00
ROADWAY EMBANKMENT AT BRIDGE END	
EFFECTIVE: AUGUST 1999	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD



\* 25.0' MIN. FOR PRIVATE OR FIELD APP.  
75.0' MIN FOR COUNTY AND MAIN ROADS.


SLOPE FOR DRAINAGE (-3% DESIRABLE,  
+3% ALLOWABLE).



TYPICAL SECTION WITHIN CLEAR ZONE

USE A PIPE AS NECESSARY FOR DRAINAGE.  
INSTALL CULVERTS OUTSIDE THE CLEAR  
ZONE OR PROVIDE END TREATMENT.

⊕ 10:1 SLOPES ARE DESIRABLE  
ON HIGH SPEED FACILITIES  
WHERE PRACTICAL



TYPICAL SECTION BEYOND CLEAR ZONE

BACK SLOPES **	
0' - 5'	4:1
5' - 10'	2:1
OVER 10'	1.5:1

FILL SLOPES **	
0' - 10'	4:1
10' - 20'	2:1
OVER 20'	1.5:1



#### NOTES:

APPROACH GRADE BEYOND LANDING IS NOT TO EXCEED 10% UNLESS  
TRAFFIC VOLUMES AND COST INDICATE SUCH TO BE JUSTIFIABLE.

CONSTRUCT APPROACHES TO FIT LOCAL CONDITIONS, MINIMIZE TRAFFIC  
HAZARDS, AND AFFORD ENTRY AND EXIT OF TRAFFIC TO AND FROM THE  
MAIN ROAD.


SECURE WRITTEN PERMISSION FROM LANDOWNER FOR WORK BEYOND THE  
RIGHT-OF-WAY.

\*\* CRITERIA SHOWN ARE FOR PRIVATE AND FARM FIELD APPROACHES. FOR  
COUNTY AND MAIN ROADS USE ESTABLISHED STANDARDS FOR APPLICABLE  
FUNCTIONAL CLASS.



DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 203	DWG. NO. 203-05
APPROACHES	
EFFECTIVE: DECEMBER 2002	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD





VERTICAL OFFSETS FROM ROADWAY AND GROUND SLOPES  
TO ROUNDING LINES FOR CUTS



BACK SLOPES 2:1 AND STEEPER



BACK SLOPES FLATTER THAN 2:1



VERT. DIST. "E" (FT.)	BACK SLOPES 2:1 AND STEEPER (T = 15')					
	DESCENDING GROUND CUTS					
	0.5M (FT.)					
	0.75:1	1:1	1.25:1	1.5:1	1.75:1	2:1
FLAT	5.0	3.8	3.0	2.5	2.1	1.9
2.0	5.5	4.3	3.5	3.0	2.6	2.4
4.0	6.0	4.8	4.0	3.5	3.1	2.9
6.0	6.5	5.3	4.5	4.0	3.6	3.4
8.0	7.0	5.8	5.0	4.5	4.1	3.9
10.0	7.5	6.3	5.5	5.0	4.6	4.4
12.0	8.0	6.8	6.0	5.5	5.1	4.9
14.0	8.5	7.3	6.5	6.0	5.6	5.4
16.0	9.0	7.8	7.0	6.5	6.1	5.9

VERT. DIST. "E" (FT.)	BACK SLOPES 2:1 AND STEEPER (T = 10')					
	ASCENDING GROUND CUTS					
	0.5M (FT.)					
	0.75:1	1:1	1.25:1	1.5:1	1.75:1	2:1
FLAT	3.3	2.5	2.0	1.7	1.4	1.3
2.0	2.8	2.0	1.5	1.2	0.9	0.8
4.0	2.3	1.5	1.0	0.7	0.4	0.3
6.0	1.8	1.0	0.5	0.2	0.0	0.0
8.0	1.3	0.5	0.0	0.0	-	-
10.0	0.8	0.0	-	-	-	-
12.0	0.3	-	-	-	-	-
14.0	0.0	-	-	-	-	-

VERT. DIST. "E" (FT.)	BACK SLOPES FLATTER THAN 2:1 (T = 10')					
	DESCENDING GROUND CUTS					
	0.5M (FT.)					
	2.5:1	3:1	3.5:1	4:1	5:1	6:1
FLAT	1.0	0.8	0.7	0.6	0.5	0.4
1.0	1.3	1.1	1.0	0.9	0.8	0.7
2.0	1.5	1.3	1.2	1.1	1.0	0.9
3.0	1.8	1.6	1.5	1.4	1.3	1.2
4.0	2.0	1.8	1.7	1.6	1.5	1.4
5.0	2.3	2.1	2.0	1.9	1.8	1.7
6.0	2.5	2.3	2.2	2.1	2.0	1.9
7.0	2.8	2.6	2.5	2.4	2.3	2.2
8.0	3.0	2.8	2.7	2.6	2.5	2.4
9.0	3.3	3.1	3.0	2.9	2.8	2.7
10.0	3.5	3.3	3.2	3.1	3.0	2.9

VERT. DIST. "E" (FT.)	BACK SLOPES FLATTER THAN 2:1 (T = 10')					
	ASCENDING GROUND CUTS					
	0.5M (FT.)					
	2.5:1	3:1	3.5:1	4:1	5:1	6:1
FLAT	1.0	0.8	0.7	0.6	0.5	0.4
1.0	0.8	0.6	0.5	0.4	0.3	0.2
2.0	0.5	0.3	0.2	0.1	0.0	0.0
3.0	0.3	0.0	0.0	0.0	-	-
4.0	0.0	-	-	-	-	-
5.0	-	-	-	-	-	-
6.0	-	-	-	-	-	-
7.0	-	-	-	-	-	-
8.0	-	-	-	-	-	-
9.0	-	-	-	-	-	-
10.0	-	-	-	-	-	-

DETAILED DRAWING  
REFERENCE DWG. NO.  
STANDARD SPEC. 203-10  
SECTION 203

SLOPE ROUNDING

EFFECTIVE: AUGUST 1999

MONTANA DEPARTMENT OF TRANSPORTATION

TURNOUT WITHOUT APPROACH

TURNOUT WITH APPROACH

MAILBOX LOCATION DETAIL

NOTES:

LOCATE NEW INSTALLATIONS, IF POSSIBLE, ON THE FAR RIGHT SIDE OF AN INTERSECTION WITH A PUBLIC ROAD OR PRIVATE DRIVEWAY.

APPROACH QUANTITIES ARE NOT INCLUDED IN TURNOUT QUANTITIES.

USE THIS DETAIL FOR ALL ROADS AND ADT. FOR ADT LESS THAN 400, STEEPER TAPERS ARE ALLOWED IF NEEDED DUE TO LIMITATIONS. SEE THE "AASHTO GUIDE FOR ERECTING MAILBOXES ON HIGHWAYS."

DETAILED DRAWING  
REFERENCE DWG. NO.  
STANDARD SPEC. 203-15  
SECTION 203

MAILBOX TURNOUT

EFFECTIVE: AUGUST 1999


MONTANA DEPARTMENT OF TRANSPORTATION

MAILBOX LOCATION DETAIL


NOTE: THE MINIMUM SPACING BETWEEN MAILBOXES IS EQUAL TO THREE-FOURTHS OF THEIR HEIGHT ABOVE THE GROUND. SEE DTL, DWG. NO. 900-05 AND 900-10 FOR MAILBOX DETAILS.



This Frame left blank



- NOTES:
- ① CONSTRUCT DITCH BLOCKS TO FIT LOCAL CONDITIONS.
  - ② HEIGHTS SHOWN ARE MINIMUMS. SET HEIGHT OF DITCH BLOCKS BASED ON AMOUNT OF ANTICIPATED DRAINAGE.
  - ③ 10:1 SLOPES ARE DESIRABLE ON HIGH SPEED FACILITIES WHERE PRACTICAL.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 203	DWG. NO. 203-20
DITCH BLOCKS	
EFFECTIVE: DECEMBER 2002	
 MONTANA DEPARTMENT OF TRANSPORTATION	
CADD	





SCHEDULE OF BEST MANAGEMENT PRACTICES (BMPs)		
NAME	DESCRIPTION	DTL. DWG. NO. (208-##)
GENERAL BMP's		
IO	INLET/OUTLET PROTECTION	1A
WP	WATERWAY PROTECTION	1B
WR	WATER RESOURCE PROTECTION	1C
TEMPORARY SOIL STABILIZATION BMPs (SS)		
SS-2	PRESERVATION OF EXISTING VEGETATION	02
SS-3	HYDRAULIC MULCH	04
SS-4	TEMPORARY SEEDING	06
SS-5	SOIL BINDERS	08
SS-6	STRAW MULCH	10
SS-7	GEOTEXTILES, PLASTIC COVERS & EROSION CONT. BLANKETS/MATS	12A & 12B
SS-8	WOOD MULCH	14
SS-9	EARTH DIKES/DRAINAGE SWALES & LINED DITCHES	16
SS-10	OUTLET PROTECTION/VELOCITY DISSIPATION DEVICES	18
SS-11	SLOPE DRAINS	20
SS-12	SLOPE ROUGHENING	22
SS-13	TERRACED SLOPES	24
SS-14	VEGETATED BUFFER	26
SS-15	EROSION SEEDING	28
TEMPORARY SEDIMENT CONTROL BMPs (SC)		
SC-1	SILT FENCE	30
SC-2	DESILTING BASIN	32A & 32B
SC-3	SEDIMENT TRAP	34
SC-4	CHECK DAMS	36
SC-5	FIBER ROLLS	38
SC-6	GRAVEL BAG BERM	40
SC-8	SAND BAG BARRIERS	42
SC-9	STRAW BALE BARRIERS	44
SC-10	STORM DRAIN INLET PROTECTION	46A & 46B
SC-11	DUGOUT DITCH BASIN	48
WIND EROSION CONTROL BMPs (WE)		
WE-1	WIND EROSION CONTROL	50
SNOW ACCUMULATION & SNOW MELT BMPs (SN)		
SN-2	SNOW ACCUMULATION MANAGEMENT	52
SN-3	FREEZE REDUCTION	54
TRACKING CONTROL BMPs (TC)		
TC-1	STABILIZED CONSTRUCTION ENTRANCE/EXIT	56
TC-3	ENTRANCE/OUTLET TIRE WASH	58
NON-STORM WATER MANAGEMENT BMPs (NS)		
NS-4	TEMPORARY STREAM CROSSINGS	60

DETAILED DRAWING

REFERENCE DWG. NO.  
STANDARD SPEC. 208-00  
SECTION 208

SCHEDULE OF  
BEST MANAGEMENT PRACTICES

EFFECTIVE: JANUARY 2004

 MONTANA DEPARTMENT  
OF TRANSPORTATION  MONTANA  
CADD

SYMBOL:

I/O

INLET/OUTLET PROTECTION:


INLET/OUTLET PROTECTION (I/O) ARE STRUCTURES ASSOCIATED WITH SEDIMENT REMOVAL AT INLETS AND SEDIMENT REMOVAL AT PIPE OUTLETS. THE PURPOSE OF THIS BMP IS TO ALLOW STORM WATERS OF INTERMITTENT DRAINAGES TO FLOW THROUGH DISTURBED AREAS WITH MINIMAL IMPACT DURING STORM EVENTS AND TO KEEP SEDIMENT FROM LEAVING MOT PROPERTY.

INLET/OUTLET PROTECTION IS USED AT CULVERT INSTALLATIONS THAT DISCHARGE DIRECTLY INTO A WATER RESOURCE OR CULTURAL AND HISTORICAL RESOURCE ADJACENT TO THE RIGHT-OF-WAY LINE. DO NOT USE INLET/OUTLET PROTECTION ON STOCK UNDERPASSES OR APPROACH CULVERTS.

APPROPRIATE BMP FEATURES INCLUDE OUTLET PROTECTION/VELOCITY DISSIPATION DEVICES, SILT FENCE, DESILTING BASIN, SEDIMENT TRAP, CHECK DAMS, FIBER ROLLS, GRAVEL BAG BERM, SAND BAG BARRIER, STRAW BALE BARRIER AND STORM DRAIN INLET PROTECTION. THIS BMP LIST IS NOT COMPREHENSIVE AND DOES NOT SUPERSEDE MOT STANDARD SPECIFICATIONS OR MANDATES AND REQUIREMENTS SPECIFIED BY OTHER AUTHORIZED STATE AND FEDERAL AGENCIES.

INTERMITTENT/EPHEMERAL FLOW  
AND CONSTRUCTION SEASON  
TERMINATION/WINTER SUSPENSION

CULVERT INSTALLATION  
WITH INTERMITTENT FLOW





DETAILED DRAWING

REFERENCE DWG. NO.  
STANDARD SPEC. 208-1A  
SECTION 208

INLET/OUTLET  
PROTECTION

EFFECTIVE: JANUARY 2004

 MONTANA DEPARTMENT  
OF TRANSPORTATION  MONTANA  
CADD




SYMBOL: WP

WATERWAY PROTECTION:

WATERWAY PROTECTION (WP) IS AN EROSION CONTROL FOR CONSTRUCTION ACTIVITIES CROSSINGS WATER RESOURCES. WATERWAY PROTECTION APPLIES TO PERENNIAL STREAM CROSSINGS, WETLANDS, CHANNEL CHANGES, STREAM BANK DISTURBANCES, IRRIGATION SYSTEMS OR OTHER IMPACTS TO WATER RESOURCES FROM BRIDGE CONSTRUCTION OR CULVERT INSTALLATIONS.

APPROPRIATE BMP FEATURES INCLUDE EROSION CONTROL BLANKETS/MATS, SLOPE ROUGHENING, VEGETATIVE BUFFER STRIP, SILT FENCE, CHECK DAMS, FIBER ROLLS, GRAVEL BAG BERM, SAND BAG BARRIER, AND STRAW BALE BARRIER. THIS BMP LIST IS NOT COMPREHENSIVE AND DOES NOT SUPERSEDE MDT STANDARD SPECIFICATIONS OR MANDATES AND REQUIREMENTS SPECIFIED BY OTHER AUTHORIZED STATE AND FEDERAL AGENCIES.

PERENNIAL STREAM CROSSING



BRIDGE/CULVERT INSTALLATION

DETAILED DRAWING	DWG. NO.
REFERENCE STANDARD SPEC. SECTION 208	208-1B

WATERWAY PROTECTION

EFFECTIVE: JANUARY 2004





SYMBOL: WR

WATER RESOURCE PROTECTION:

WATER RESOURCE PROTECTION (WR) IS EROSION CONTROL FOR CONSTRUCTION ACTIVITIES ADJACENT TO WATER RESOURCES. WATER RESOURCE PROTECTION APPLIES TO PERENNIAL STREAMS, WETLANDS, CHANNEL CHANGES, STREAM BANK DISTURBANCES, IRRIGATION SYSTEMS OR OTHER IMPACTS TO WATER RESOURCES FROM ROAD CONSTRUCTION. IT CAN BE USED FOR CRITICAL RESOURCES. THE DESIGNER DENOTES "CRITICAL RESOURCE" ON THE PLANS AND PUTS WATER RESOURCE PROTECTION WITH IT.

APPROPRIATE BMP FEATURES INCLUDE EROSION CONTROL BLANKETS/MATS, SLOPE ROUGHENING, VEGETATIVE BUFFER STRIP, SILT FENCE, CHECK DAMS, FIBER ROLLS, GRAVEL BAG BERM, SAND BAG BARRIER, AND STRAW BALE BARRIER. THIS BMP LIST IS NOT COMPREHENSIVE AND DOES NOT SUPERSEDE MDT STANDARD SPECIFICATIONS OR MANDATES AND REQUIREMENTS SPECIFIED BY OTHER AUTHORIZED STATE AND FEDERAL AGENCIES.



DETAILED DRAWING	DWG. NO.
REFERENCE STANDARD SPEC. SECTION 208	208-1C

WATER RESOURCE PROTECTION

EFFECTIVE: JANUARY 2004





This Frame left blank

SYMBOL: ——— PEV ———


PRESERVATION OF EXISTING VEGETATION SS-2:



PRESERVATION OF EXISTING VEGETATION IS THE IDENTIFICATION AND PROTECTION OF DESIRABLE VEGETATION THAT PROVIDES EROSION AND SEDIMENT CONTROL BENEFITS. PROVIDE PRESERVATION OF EXISTING VEGETATION PRIOR TO COMMENCEMENT OF CLEARING AND GRUBBING OPERATIONS OR OTHER SOIL DISTURBING ACTIVITIES. MARK THE AREA AS DESIGNATED ON THE CONSTRUCTION PLANS USING TEMPORARY FENCING MADE OF ORANGE POLYPROPYLENE THAT IS STABILIZED AGAINST ULTRAVIOLET LIGHT. AFFIX FENCING TO METAL "T" POST USING 11 GAGE WIRE. PLACE FENCING AN ADEQUATE DISTANCE FROM TREES AND BUSHES TO PREVENT ROOT AND IRRIGATION SYSTEM DAMAGE.

UPON WRITTEN APPROVAL BY THE ENGINEER, THE CONTRACTOR MAY BE ALLOWED TO FLAG OR VERBALLY DESIGNATE AREAS OF EXISTING VEGETATIVE PRESERVATION.

PRESERVATION OF EXISTING VEGETATION MAY BE USED IN CONJUNCTION WITH VEGETATIVE BUFFER (SS-14), WIND EROSION CONTROL (WE-1) AND SNOW ACCUMULATION (SN-1).

FOLLOW CLEAR ZONE REQUIREMENTS FOR ALL FENCING PLACED WITHIN THE CLEAR ZONES.



DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	208-02
SECTION 208	
PRESERVATION OF EXISTING VEGETATION (SS-2)	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD



SYMBOL:        ———— HM ————

HYDRAULIC MULCH SS-3:

HYDRAULIC MULCH CONSISTS OF APPLYING A MIXTURE OF SMALL PIECES OF CELLULOSE FIBERS WHICH CAN BE MADE FROM SHREDDED WOOD FIBERS OR RECYCLED PAPER AND A STABILIZING EMULSION AND TACKIFIER (SUBJECT TO ENGINEERS DISCRETION) USING HYDRO-MULCHING EQUIPMENT. HYDRAULIC MULCH IS APPLIED TO DISTURBED AREAS REQUIRING TEMPORARY PROTECTION UNTIL PERMANENT VEGETATION IS ESTABLISHED OR DISTURBED AREAS THAT MUST BE RE-DISTURBED FOLLOWING AN EXTENDED PERIOD OF INACTIVITY.


APPLY HYDRAULIC MULCH A MINIMUM OF 24 HOURS PRIOR TO A STORM EVENT TO ALLOW FOR ADEQUATE DRYING.

HYDRAULIC MULCH SELECTION MUST MEET MDT SPECIFICATIONS AND BE APPROVED BY THE ENGINEER PRIOR TO PLACEMENT. ROUGHEN EXISTING EMBANKMENT FOLLOWING GUIDELINES SPECIFIED IN BMP SS-12. WHEN EITHER TEMPORARY SEEDING OR PERMANENT SEEDING IS COMBINED WITH THE HYDRAULIC MULCH BMP, COMPLETE SEEDING OPERATIONS PRIOR TO HYDRAULIC MULCHING OPERATIONS. REFER TO BMPs SS-4 AND SS-5 FOR SEEDING REQUIREMENTS. REMOVE ANY OVER SPRAY FROM ROADWAYS OR SIDEWALKS IMMEDIATELY FOLLOWING APPLICATION.

REAPPLY HYDRAULIC MULCH TO ANY DISTURBED AREAS FOLLOWING A RAIN EVENT OR RESULTING FROM CONSTRUCTION ACTIVITIES.



RECYCLED PAPER MULCH SHOULD CONTAIN 100% POST CONSUMED PAPER.

REFER TO BMP SS-5 (SOIL BINDER) FOR TACKIFIER REQUIREMENTS. ADD ENVIRONMENTALLY SAFE GREEN DYE AS A VISUAL AID DURING APPLICATION.



HYDRAULIC MULCH		
PRODUCT	MATERIAL	APPLICATION RATE *
PAPER-BASED HYDRAULIC MULCH	PAPER	1000 LB./ACRE (MIN)
WOOD-BASED HYDRAULIC MULCH	WOOD OR WOOD & PAPER	1000 LB./ACRE (MIN)

\* APPLICATION RATES VARY WITH SLOPE & MUST BE APPROVED BY THE ENGINEER

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 208	DWG. NO. 208-04
HYDRAULIC MULCH (SS-3)	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION 	

SYMBOL:        ———— TS ————

TEMPORARY SEEDING SS-4:

TEMPORARY SEEDING IS THE ESTABLISHMENT OF A TEMPORARY VEGETATIVE COVER BY SEEDING WITH CEREAL BARLEY. USE TEMPORARY SEEDING ON AREAS 3:1 OR FLATTER THAT WILL BE EXPOSED FOR LONGER THAN 14 DAYS AND THAT WILL UNDERGO FURTHER DISTURBANCE, EXCLUDE ROCK SLOPES THAT CANNOT BE EXCAVATED BY RIPPING.


SEEDING DATES AND APPLICATION RATES ARE AS FOLLOWS:

APR. 1 TO JUN. 30: CEREAL BARLEY AT 12 LB./ACRE  
JUL. 1 TO AUG. 31: TEMPORARY SEEDING NOT RECOMMENDED  
SEP. 1 TO NOV. 15: CEREAL BARLEY AT 12 LB./ACRE



DO NOT TEMPORARY SEED FROM SEP. 1 TO NOV. 15 IF THE AREA IS TO BE PERMANENTLY SEEDED THAT FALL.

CONTACT THE MDT AGRONOMIST, THROUGH THE ENGINEER, PRIOR TO USING SUBSTITUTIONS OR PLACING TEMPORARY SEEDING OUTSIDE THESE DATES. DRILL SEED SLOPES OF 3:1 OR FLATTER. FOR SLOPES STEEPER THAN 3:1, REFER TO EROSION SEEDING.

ANY TEMPORARY SEEDING EFFORTS THAT DO NOT PROVIDE ADEQUATE COVER MUST BE RE SEEDED AS REQUIRED BY THE ENGINEER.



SLOPES 3:1 OR FLATTER

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 208	DWG. NO. 208-06
TEMPORARY SEEDING (SS-4)	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION 	



SYMBOL: SB


SOIL BINDERS SS-5:

SOIL BINDERS CONSIST OF APPLYING AND MAINTAINING POLYMERIC OR LIGNIN SULFONATE SOIL STABILIZERS OR EMULSIONS. SOIL BINDERS ARE MATERIALS APPLIED TO THE SOIL SURFACE TO TEMPORARILY PREVENT WATER-INDUCED EROSION OF EXPOSED SOILS ON CONSTRUCTION SITES. SOIL BINDERS TYPICALLY ALSO PROVIDE DUST, WIND AND SOIL STABILIZATION BENEFITS. BECAUSE SOIL BINDERS CAN OFTEN BE INCORPORATED INTO THE WORK, THEY MAY BE A GOOD CHOICE FOR AREAS WHERE GRADING ACTIVITIES MAY SOON RESUME.

DUE TO THE TEMPORARY NATURE OF SOIL BINDERS, REAPPLICATION MAY BE REQUIRED OVER AREAS WITH PEDESTRIAN AND VEHICLE TRAFFIC.

SOIL BINDER TYPE AND APPLICATION PROCEDURES REQUIRE THE ENGINEER'S APPROVAL PRIOR TO PLACEMENT. APPLY PER MANUFACTURES SPECIFICATIONS.

REAPPLY SOIL BINDERS, AS SPECIFIED BY THE ENGINEER, IN HIGH TRAFFIC AREAS AND FOLLOWING RAIN EVENTS TO ENSURE AN ADEQUATELY MAINTAINED SURFACE.



PROPERTIES OF SOIL BINDERS FOR EROSION CONTROL				
CHEMICALS	COPOLYMER	LIGNIN SULFONATE	PSYLLIUM	GUAR
COMMENTS	FORMS SEMIPERMEABLE TRANSPARENT CRUST. RESISTS ULTRAVIOLET RADIATION & MOISTURE INDUCED BREAKDOWN.	PAPER INDUSTRY WASTE PRODUCT. ACTS AS DISPERSING AGENT. BEST IN DRY CLIMATES. CAN BE SLIPPERY.	EFFECTIVE ON DRY, HARD SOILS. FORMS A CRUST.	EFFECTIVE ON DRY, HARD SOILS. FORMS A CRUST.
RELATIVE COST	HIGH	MODERATE	LOW	LOW
ENVIRONMENTAL HAZARD	LOW	LOW	LOW	LOW
PENETRATION	MODERATE	MODERATE	HIGH	HIGH
EVAPORATION	MODERATE	MODERATE	MODERATE	MODERATE
LEACHING RESISTANCE	LOW	HIGH	HIGH	HIGH
ABRASION RESISTANCE	HIGH	LOW	MODERATE	MODERATE
LONGEVITY	1 TO 2 YEARS	6 MONTHS TO 1 YEAR	3 TO 6 MONTHS	3 TO 6 MONTHS
MINIMUM CURING TIME BEFORE RAIN	24 HOURS	24 HOURS	24 HOURS	24 HOURS
COMPATIBILITY WITH EXISTING VEGETATION	GOOD	POOR	POOR	POOR
MODE OF DEGRADATION	CHEMICALLY DEGRADABLE	BIOLOGICALLY/PHYSICALLY/CHEMICALLY	BIOLOGICALLY DEGRADABLE	BIOLOGICALLY DEGRADABLE
LABOR INTENSIVE	NO	NO	NO	NO
SPECIALIZED APPL. EQUIPMENT	YES	YES	YES	YES
LIQUID/POWDER	LIQUID	POWDER	POWDER	POWDER
SURFACE CRUSTING	YES	YES, BUT DISSOLVED ON REWETTING	YES, BUT DISSOLVED ON REWETTING	YES, BUT DISSOLVED ON REWETTING
CLEAN-UP	SOLVENTS	SOLVENTS	WATER	WATER
EROSION CONTROL APPLICATION RATE	APPLY 85-105 GAL./ACRE	APPLY 600-700 GAL./ACRE	APPLY 150 LB./ACRE WITH 500-2000 LB./ACRE FIBER MULCH	APPLY 100-200 LB./ACRE WITH 500-2000 LB./ACRE FIBER MULCH
DUST CONTROL APPLICATION RATE	APPLY 30-55 GAL./ACRE	LOOSEN SURFACE 1-2 INCHES. NEED 4-8% FINES. APPLY 50-200 GAL./ACRE	APPLY 150 LB./ACRE	APPLY 40-60 LB./ACRE

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 208	DWG. NO. 208-08
SOIL BINDERS (SS-5)	
EFFECTIVE: JANUARY 2004	
MONTANA DEPARTMENT OF TRANSPORTATION	

SYMBOL: SM

STRAW MULCH SS-6:


STRAW MULCH CONSISTS OF PLACING A UNIFORM LAYER OF STRAW AND ANCHORING IT INTO THE SOIL WITH A STUDDED ROLLER OR DISK OR BINDING THE STRAW TOGETHER WITH AN ENGINEER APPROVED TACKIFIER.

USE STRAW MULCH FOR SOIL STABILIZATION AS A TEMPORARY SURFACE COVER ON DISTURBED AREAS UNTIL SOILS CAN BE PREPARED OR RE-VEGETATION/PERMANENT VEGETATION IS ESTABLISHED. STRAW MULCH IS COMMONLY USED IN COMBINATION WITH TEMPORARY SEEDING, BMPs SS-4 & SS-15, AND/OR PERMANENT SEEDING TO ENHANCE PLANT ESTABLISHMENT.


ALL STRAW MULCH IS REQUIRED TO BE CERTIFIED WEED FREE AND DERIVED FROM WHEAT, BARLEY OR RICE. ENGINEERS APPROVAL IS REQUIRED PRIOR TO ANY PLACEMENT OF STRAW MULCH.

STRAW MULCH CAN BE APPLIED BY HAND OR BLOWN UNDER LOW WIND CONDITIONS. OBTAIN ENGINEERS APPROVAL FOR PLACEMENT METHODS PRIOR TO PLACEMENT. EVENLY DISTRIBUTE STRAW MULCH AT A MINIMUM LOOSE RATE OF 4000 LB./ACRE. IMMEDIATELY FOLLOWING PLACEMENT, CRIMP OR APPLY TACKIFIERS TO RETAIN MULCH. CRIMP USING DISKS OR A PUNCH-TYPE ROLLER. IF TACKIFIERS ARE USED, FOLLOW GUIDELINES PROVIDED IN BMP SS-5. WHEN EITHER TEMPORARY OR PERMANENT SEEDING IS COMBINED WITH THE STRAW MULCH BMP, COMPLETE SEEDING OPERATIONS PRIOR TO STRAW MULCH PLACEMENT. REFER TO BMPs SS-4 AND SS-15 FOR SEEDING GUIDELINES.

REAPPLICATION OF STRAW MULCH AND TACKIFIER MAY BE REQUIRED BY THE ENGINEER TO MAINTAIN EFFECTIVE SOIL STABILIZATION OVER DISTURBED AREAS AND SLOPES.



STRAW BLOWER



STRAW CRIMPING

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 208	DWG. NO. 208-10
STRAW MULCH (SS-6)	
EFFECTIVE: JANUARY 2004	
MONTANA DEPARTMENT OF TRANSPORTATION	



SYMBOL: ——— EC ———



GEOTEXTILES, PLASTIC COVERS & EROSION CONTROL BLANKETS/MATS SS-7:



GEOTEXTILES, PLASTIC COVERS, AND EROSION CONTROL BLANKETS/MATS ARE USED TO STABILIZE DISTURBED SOIL AREAS AND PROTECT SOILS FROM EROSION BY WIND AND WATER. THESE PRODUCTS CAN BE USED ON STEEP SLOPES, SLOPES WITH HIGH EROSION HAZARDS, SLOPES WHERE MULCHES CAN NOT BE ANCHORED, UNPROTECTED CHANNELS AND HIGH FLOW CHANNELS.


INSTALL GEOTEXTILES AND EROSION CONTROL BLANKETS/MATS IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS AND MDT STANDARD SPECIFICATIONS SECTION 622.

PROVIDE GEOTEXTILE MATERIALS MEETING MDT STANDARD SPECIFICATIONS SECTION 713.


LIMIT USE OF PLASTIC COVERS TO COVERING STOCKPILES, OR VERY SMALL GRADED AREAS FOR SHORT PERIODS OF TIME (SUCH AS THROUGH ONE IMMINENT STORM EVENT) UNTIL ALTERNATIVE MEASURES MAY BE INSTALLED. PLASTIC COVERS ARE REQUIRED TO BE POLYETHYLENE SHEETING HAVING A MINIMUM THICKNESS OF 6 mil. ANCHOR PLASTIC COVERS WITH SANDBAGS PLACED NO MORE THAN 10 FT. APART AND BY KEYING INTO THE TOP OF SLOPE TO PREVENT INFILTRATION OF SURFACE WATERS UNDER THE PLASTIC. TAPE OR WEIGHT DOWN THE ENTIRE LENGTH OF ALL SEAMS WITH AT LEAST A 1 FT. TO 2 FT. OVERLAP.




DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	208-12A
SECTION 208	
GEOTEXTILES, PLASTIC COVERS & EROSION CONT. BLANKETS/MATS (SS-7) (SHEET 1)	
EFFECTIVE: JANUARY 2004	
	MONTANA DEPARTMENT OF TRANSPORTATION
	MONTANA CADD




INITIAL CHANNEL ANCHOR TRENCH




TERMINAL SLOPE & CHANNEL ANCHOR TRENCH





TYPICAL CHANNEL DETAIL - ISOMETRIC VIEW



INTERMITTENT CHECK SLOT



LONGITUDINAL ANCHOR TRENCH

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	208-12B
SECTION 208	
GEOTEXTILES, PLASTIC COVERS & EROSION CONT. BLANKETS/MATS (SS-7) (SHEET 2)	
EFFECTIVE: JANUARY 2004	
	MONTANA DEPARTMENT OF TRANSPORTATION
	MONTANA CADD



---

WM

---


WOOD MULCH SS-8:

WOOD MULCHING CONSISTS OF APPLYING A MIXTURE OF SHREDED WOOD MULCH, BARK, OR COMPOST. WOOD MULCH IS MOSTLY APPLICABLE TO LANDSCAPE PROJECTS. WOOD MULCHING REDUCES EROSION BY PROTECTING BARE SOIL RAINFALL IMPACT, INCREASING INFILTRATION, AND REDUCING RUNOFF. IT DOES NOT USE WOOD MULCH WHERE CONCENTRATED RUNOFF FLOWS MAY EXIST.

OBTAIN ENGINEERS APPROVAL PRIOR TO PLACEMENT TO VERIFY MULCH CONTAINS SHREDDED WOOD, BARK AND COMPOST THAT IS WEED FREE. PRIOR TO PLACEMENT, ROUGHEN ALL SURFACES IN ACCORDANCE WITH BMP SS-12. FOLLOWING SLOPE ROUGHENING, EVENLY DISTRIBUTE MULCH AT A MINIMUM DEPTH OF 3". WHEN EITHER TEMPORARY OR PERMANENT SEEDING IS COMBINED WITH THE WOOD MULCH BMP, COMPLETE SEEDING OPERATIONS PRIOR TO WOOD MULCH PLACEMENT. REFER TO BMPs SS-4 AND SS-15 FOR SEEDING REQUIREMENTS.

AVOID MULCH PLACEMENT ONTO THE TRAVELED WAY, SIDEWALKS, LINED DRAINAGE CHANNELS, AND EXISTING VEGETATION.

MULCH CAN BE APPLIED BY HAND OR BY PNEUMATIC METHODS.



REFERENCE STANDARD SPEC. SECTION 208	DETAILED DRAWING	DWG. NO. 208-14
--	------------------	--------------------

WOOD MULCH  
(SS-8)


**MONTANA DEPARTMENT OF TRANSPORTATION**  

**MONTANA CADD**  
**EFFECTIVE: JANUARY 2004**

SYMBOL: \_\_\_\_\_ ED \_\_\_\_\_

EARTH DIKES/DRAINAGE SWALES &amp; LINED DITCHES SS-9:


EARTH DIKES, DRAINAGE SWALES AND LINED DITCHES ARE STRUCTURES THAT INTERCEPT, DIVERT, AND CONVEY SURFACE RUN-ON, GENERALLY SHEET FLOW, TO PREVENT EROSION. THESE DEVICES MAY BE IMPLEMENTED ON A PROJECT-BY-PROJECT BASIS WITH OTHER BMPs WHEN DETERMINED NECESSARY AND FEASIBLE BY THE ENGINEER. DIKES, SWALES AND DITCHES ARE CONVEYANCE MEASURES AND ARE NOT INTENDED TO TRAP SEDIMENT. SEDIMENT CONTROL BMPs CAN BE USED IN CONJUNCTION WITH THESE CONVEYANCE DEVICES.

WHEN POSSIBLE, INSTALL AND UTILIZE DIKES, SWALES AND DITCHES EARLY IN THE CONSTRUCTION PHASE. CONSTRUCT SWALES ALONG THE TOP AND BOTTOM OF CUT AND FILL SLOPES, AS SPECIFIED IN THE PLANS OR AS DESIGNATED BY THE ENGINEER. "V" BOTTOM DITCHES CAN BE USED FOR SWALE CONSTRUCTION FOLLOWING ENGINEERS APPROVAL. USE SEDIMENT CONTROL DEVICES FOR RUNOFF THAT IS DIVERTED FROM DISTURBED AREAS. CONVEY FLOWS FROM UNDISTURBED AREAS INTO A STABILIZED AREA AT NON-EROSIVE VELOCITIES. DO NOT PLACE DIKES, SWALES, AND DITCHES IN A MANNER THAT ALLOWS HIGHWAY RUNOFF TO ENTER ONTO OTHER PROPERTY'S RIGHT-OF-WAY.


USE LINED DITCHES FOR AREAS OF HIGH FLOW VELOCITIES FOLLOWING THE GUIDELINES SPECIFIED IN SS-7 (GEOTEXTILES, PLASTIC COVERS & EROSION CONTROL BLANKETS/MATS) AND/OR SS-11 (SLOPE DRAINS). SEED ALL UNLINED PORTIONS OF DITCHES, DIKES AND SWALES THAT WILL BE IN USE FOR MORE THEN 14 DAYS IN ACCORDANCE WITH SS-15 (EROSION SEEDING)

INSPECT DIKES, SWALES, AND DITCHES AFTER RAINFALL EVENTS. REMOVE DEBRIS AND SEDIMENT, AND REPAIR LININGS AND EMBANKMENTS AS NEEDED OR AS SPECIFIED BY THE ENGINEER.


REMOVAL ALL DIKES, SWALES AND LINED DITCHES FROM THE CLEAR ZONES EXPEDIENTLY  
UPON COMPLETION OF CONSTRUCTION ACTIVITIES.





### TYPICAL DRAINAGE SWALE




TYPICAL EARTH DIKE



TYPICAL TRAPEZOIDAL DITCH

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 208	DWG. NO. 208-16
EARTH DIKES/DRAINAGE SWALES & LINED DITCHES (SS-9)	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION	
 MONTANA CADD	




SYMBOL: 


OUTLET PROTECTION/VELOCITY DISSIPATION DEVICES SS-10:

OUTLET PROTECTION AND VELOCITY DISSIPATION DEVICES ARE PLACED AT PIPE OUTLETS TO PREVENT SCOUR AND REDUCE THE VELOCITY AND/OR ENERGY OF EXITING STORM WATER FLOWS. THESE DEVICES CAN BE USED AT THE OUTLETS OF PIPES, DRAINS, CULVERTS, SLOPE DRAINS, DIVERSION DITCHES, SWALES, CONDUITS OR CHANNELS AND SHOULD BE IMPLEMENTED ON A PROJECT-BY-PROJECT BASIS WITH OTHER BMPs WHEN DETERMINED NECESSARY BY THE ENGINEER.


FOLLOW GUIDELINES BELOW FOR SIZING OUTLET PROTECTION AND VELOCITY DISSIPATION DEVICES. FOLLOWING ENGINEER'S APPROVAL, OTHER MATERIALS MAY BE SUBSTITUTED FOR RIPRAP. GEOTEXTILE PLACEMENT MAY BE ELIMINATED FOLLOWING ENGINEERS APPROVAL. PLACE TYPE 1 OR TYPE 2 BANK PROTECTION AT PIPE OUTLET. FOR PIPE DIAMETERS LARGER THAN 24" AND/OR HIGH FLOWS, THE APPLICATION IS NOT CONSIDERED TEMPORARY AND A MONTANA REGISTERED ENGINEER'S DESIGN IS REQUIRED.




PLAN VIEW - CHANNELIZED FLOW  
(OUTFALL TO CHANNEL OR DITCH)



PLAN VIEW - UNCHANNELIZED FLOW  
(OUTFALL TO UNCONFINED SURFACE-OVERLAND FLOW)



PROFILE VIEW

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	208-18
SECTION 208	
OUTLET PROTECTION/VELOCITY DISSIPATION DEVICES (SS-10)	
EFFECTIVE: JANUARY 2004	
	

SYMBOL: \_\_\_\_\_ TSD \_\_\_\_\_

SLOPE DRAINS SS-11

A SLOPE DRAIN IS A PIPE OR LINED CHANNEL USED TO INTERCEPT AND CONVEY SURFACE RUNOFF OR GROUNDWATER INTO A STABILIZED WATERCOURSE, TRAPPING DEVICE, OR STABILIZED AREA. THIS DEVICE MAY BE USED AT CONSTRUCTION SITES WHERE SLOPES MAY BE ERODED BY SURFACE RUNOFF.


DO NOT EXCEED A DRAINAGE AREA OF 10 ACRES PER SLOPE DRAIN PIPE. FOR AREAS LARGER THAN 10 ACRES USE ROCK LINED CHANNELS. DO NOT PLACE SLOPE DRAINS ON SLOPES THAT EXCEED 2:1 SLOPES. INCORPORATE BMP SS-9 (EARTH DIKES/DRAINAGE SWALES & LINED DITCHES) TO AID IN FLOW DIVERSION.

INSTALL SLOPE DRAINS AS FOLLOWS:


- INSTALL DRAINS PERPENDICULAR TO SLOPE
- COMPACT SOIL AROUND INLET, OUTLET AND LENGTH OF STRUCTURE
- SECURELY ANCHOR SLOPE DRAINS INTO SOIL
- ENSURE CONNECTIONS ARE WATER TIGHT
- PROTECT INLET AND OUTLET WITH BMP SS-10 (OUTLET PROTECTION & VELOCITY DISSIPATION)

ALL MATERIALS REQUIRE ENGINEER'S APPROVAL PRIOR TO PLACEMENT.


PIPE SLOPE DRAIN






RIPRAP SLOPE DRAIN




DITCH LINER: SYNTHETIC EROSION CONTROL AND REVEGETATION MAT



SLOPE DRAIN INLETS



DETAILED DRAWING	DWG. NO.
REFERENCE	208-20
STANDARD SPEC.	
SECTION 208	
SLOPE DRAINS (SS-11)	
EFFECTIVE: JANUARY 2004	
	




SYMBOL:      ——— SR ———


SLOPE ROUGHENING SS-12:



SLOPE ROUGHENING IS A VERY ROUGH SOIL SURFACE ON SLOPES RESULTING FROM CONSTRUCTION ACTIVITIES OR THE SYSTEMATIC ROUGHENING USING HEAVY EQUIPMENT TO CREATE RIDGES OR FURROWS PERPENDICULAR TO THE SLOPE. THE RIDGES OR FURROWS ARE TO BE EQUAL TO OR GREATER THAN 2" IN HEIGHT AND NO FURTHER THAN TWICE THE HEIGHT OF THE RIDGE OR FURROW APART. SLOPE ROUGHENING IS A GOOD FIRST LINE OF DEFENSE TO CONTROL EROSION AND SEDIMENT RUNOFF. DEGREE OF SLOPE ROUGHENING IS DEPENDENT ON THE GRADES AND PROXIMITY TO WATER RESOURCES.

ALL SLOPES STEEPER THAN 3:1 AND GREATER THAN 5 VERTICAL FEET REQUIRE SLOPE ROUGHENING, EXCLUDING ROCK SLOPES THAT CANNOT BE EXCAVATED BY RIPPING. ROUGHEN DISTURBED SLOPES OR LEAVE IN A ROUGHENED CONDITION. APPROPRIATE SUPPLEMENTS INCLUDE SOIL STABILIZATION BMPs SUCH AS TEMPORARY SEEDING OR EROSION SEEDING. WHEN FILL SLOPES ARE WITHIN 50 FT. OF SURFACE WATER, EARTH DIKES/DRAINAGE SWALES & LINED DITCHES (SS-9) AND/OR A SEDIMENT CONTROL BMP ARE REQUIRED.



ROUGHEN SLOPES  
WITH HEAVY EQUIPMENT  
OR LEAVE IN ROUGHENED  
CONDITION





DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	208-22
SECTION 208	
SLOPE ROUGHENING (SS-12)	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD



SYMBOL:      ——— GT ———

TERRACED SLOPES SS-13:

TERRACED SLOPES ARE MADE OF EITHER EARTHEN EMBANKMENTS OR RIDGE AND CHANNEL SYSTEMS THAT ARE PROPORTIONALLY SPACED AND ARE CONSTRUCTED WITH AN ADEQUATE GRADE. TERRACES REDUCE DAMAGE FROM EROSION BY COLLECTING AND REDISTRIBUTING SURFACE RUNOFF TO STABLE OUTLETS AT SLOWER VELOCITIES AND BY INCREASING THE DISTANCE OF OVERLAND RUNOFF FLOW. THIS BMP IS USUALLY LIMITED TO USE ON LONG STEEP SLOPES WITH A WATER EROSION PROBLEM, OR WHERE IT IS ANTICIPATED THAT WATER EROSION WILL BE A PROBLEM. TERRACED SLOPES ARE NOT APPROPRIATE FOR USE ON SANDY, STONY, OR SHALLOW SOILS.

DESIGN TERRACED SLOPES WITH ADEQUATE AND APPROPRIATE OUTLETS. ENGINEER'S APPROVAL IS REQUIRED PRIOR TO MODIFICATIONS OF SPECIFIED TERRACED SLOPES.



DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	208-24
SECTION 208	
TERRACED SLOPES (SS-13)	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD




SYMBOL: \_\_\_\_\_ VBS \_\_\_\_\_

VEGETATED BUFFER SS-14:

VEGETATED BUFFER IS AN UNDISTURBED AREA OR STRIP OF ESTABLISHED VEGETATION. A VEGETATED BUFFER PROVIDES A LIVING SEDIMENT FILTER TO REDUCE RUNOFF VELOCITIES AND ALLOW CAPTURE AND SETTLING OF COARSE-GRAINED SEDIMENT. VEGETATED BUFFERS REDUCE OR PREVENT SEDIMENTATION FROM LEAVING THE RIGHT-OF-WAY.

IDENTIFY EXISTING VEGETATED BUFFERS BEFORE CONSTRUCTION OCCURS AND MARK AREA PER SS-2 (PRESERVATION OF EXISTING VEGETATION) OR WITH SC-1 (SILT FENCE). ESTABLISHED VEGETATED BUFFERS SHOULD INCLUDE GRASSES AND SHRUBS. IRRIGATION, FERTILIZATION AND WEED AND PEST CONTROL MAY BE REQUIRED IN ORDER TO ESTABLISH AND MAINTAIN AN EFFECTIVE VEGETATED BUFFER. KEEP EQUIPMENT AND FILL MATERIAL OFF OF VEGETATED BUFFERS. ALWAYS CONSIDER VEGETATED BUFFER BUFFERS WHEN WATER RESOURCES ARE ADJACENT TO OR NEAR DISTURBANCES AND REQUIRE PROTECTION. THE MINIMUM WIDTH REQUIREMENT FOR A WELL-ESTABLISHED VEGETATED BUFFER WITH A SLOPE OF 3:1 OR FLATTER IS 50 FT. THE MINIMUM WIDTH REQUIREMENT FOR A WELL-ESTABLISHED VEGETATED BUFFER WITH A SLOPE STEEPER THAN 3:1 IS 100 FT. WIDTH OF THE VEGETATED BUFFER MAY BE ADJUSTED ON A PROJECT-BY-PROJECT BASIS WITH APPROVAL BY THE ENGINEER. APPROPRIATE SUPPLEMENTS INCLUDE CHECK DAMS, SILT FENCES AND OTHER SEDIMENT CONTROL BARRIERS.




DETAILED DRAWING

REFERENCE STANDARD SPEC. SECTION 208

DWG. NO. 208-26

VEGETATED BUFFER (SS-14)

EFFECTIVE: JANUARY 2004

MONTANA DEPARTMENT OF TRANSPORTATION


SYMBOL: \_\_\_\_\_ ES \_\_\_\_\_

EROSION SEEDING BMP SS-15:

EROSION SEEDING IS THE IMMEDIATE SEEDING OF FRESHLY EXPOSED SLOPES. USE EROSION SEEDING ON CUT AND FILL SLOPES STEEPER THAN 3:1 THAT ARE NOT SUBJECT TO FURTHER DISTURBANCE. EXCLUDE ROCK SLOPES THAT CANNOT BE EXCAVATED BY RIPPING. SEEDING DOES NOT REPLACE OR SUBSTITUTE FOR FINAL SEEDING ACTIVITIES SPECIFIED IN THE SEEDING SPECIAL PROVISION.

SEED COMPLETED SECTIONS DAILY, REGARDLESS OF THE TIME OF YEAR. ACCOMPLISH SEEDING BY MANUAL BROADCASTING WITH A SHOULDER-HARNESSED SPREADER SEEDER WITH NO MULCH OR FERTILIZER APPLIED. TRACK AREAS FOLLOWING SEEDING IN ACCORDANCE TO BMP SS-12. SLOPE ROUGHENING HYDROSEEDING ONLY BE USED IS APPROVED BY THE MOT AGRONOMIST THROUGH THE ENGINEER. STORE THE RECOMMENDED SEED MIX ON-SITE PRIOR TO INITIATION OF SLOPE EXCAVATION. IF ONE OR MORE SPECIES IS UNAVAILABLE, CONTACT THE MOT AGRONOMIST THROUGH THE ENGINEER. FOR THE SUBSTITUTE, ROCK AREAS THAT CANNOT BE RIPPED WILL BE EVALUATED ON A PROJECT-BY-PROJECT BASIS FOR THE NEED OF EROSION SEEDING. THESE AREAS WILL RECEIVE EROSION SEEDING FOLLOWING THE ENGINEER'S APPROVAL. THE SEED MIX AND RATE OF APPLICATION ARE AS FOLLOWS:

DISTRICT	SPECIES	LB./ACRE PLS
1 (MISSOULA)	CANADA WILDRYE	3
	SECAR BLUEBUNCH WHEATGRASS	5
	CRITANA THICKSPIKE WHEATGRASS	5
	COVAR SHEEP FESCUE	2
	CEREAL BARLEY	5
2, 3, 5 (BUTTE, GREAT FALLS, BILLINGS)	CANADA WILDRYE	3
	SECAR BLUEBUNCH WHEATGRASS	5
	SODAR STREAMBANK WHEATGRASS	5
	COVAR SHEEP FESCUE	2
	CEREAL BARLEY	5
4 (GLENDIVE)	CANADA WILDRYE	3
	SECAR BLUEBUNCH WHEATGRASS	5
	ROSANA WESTERN WHEATGRASS	5
	LODORM GREEN NEEDLEGRASS	3
	CEREAL BARLEY	5




DETAILED DRAWING

REFERENCE STANDARD SPEC. SECTION 208

DWG. NO. 208-28

EROSION SEEDING (SS-15)

EFFECTIVE: JANUARY 2004

MONTANA DEPARTMENT OF TRANSPORTATION



SYMBOL: \_\_\_\_\_ SF \_\_\_\_\_


SILT FENCE SC-1:

SILT FENCE IS A SINGLE OR SERIES OF FILTER FABRIC SEDIMENT BARRIER STRETCHED AND ATTACHED TO SUPPORTING POSTS. THE FENCE BOTTOM IS ENTRENCHED.


SILT FENCES ARE USED FOR SHEET FLOWS TO ASSIST IN SEDIMENT CONTROL BY RETAINING SOME OF THE ERODED SOIL PARTICLES AND SLOWING THE RUNOFF VELOCITY TO ALLOW PARTICLE SETTLING. APPLICATIONS INCLUDE WATER RESOURCE PROTECTION, INLET PROTECTION, BANK PROTECTION, AND TOE OF SLOPE PROTECTION. INSTALL SILT FENCES PRIOR TO DISTURBING AREAS REQUIRING THIS BMP OR AS SLOPE GRADES ARE ACHIEVED. MAXIMUM CUT OR FILL SLOPE FOR A SILT FENCE IS 2:1. FOLLOW MDT STANDARD SPECIFICATION 622 FOR SILT FENCE MATERIALS AND INSTALLATION.

THERE ARE TWO TYPE OF SILT FENCE INSTALLATIONS:


- UNSTABILIZED - SILT FENCE SUPPORTED WITH EITHER WOOD OR METAL FENCE POSTS.
- STABILIZED - SILT FENCE SUPPORTED WITH METAL POSTS AND WITH WOVEN WIRE BACKING.



JOINING SECTION DETAIL



SILT FENCE - PLAN VIEW



SILT FENCE - CROSS SECTION

\* FOR CLEAR ZONE APPLICATIONS USE  
MAX. POST LENGTH OF 60" WITH  
A MAX. BURIAL DEPTH OF 18".

DETAILED DRAWING	DWG. NO.
REFERENCE STANDARD SPEC. SECTION 208	208-30

SILT FENCE  
(SC-1)

EFFECTIVE: JANUARY 2004



SYMBOL: \_\_\_\_\_ DB \_\_\_\_\_

DESILTING BASIN SC-2:


A DESILTING BASIN IS A TEMPORARY BASIN FORMED BY EXCAVATION AND/OR CONSTRUCTING AN EMBANKMENT SO THAT SEDIMENT-LADEN RUNOFF IS TEMPORARILY DETAINED UNDER SLOW FLOWING CONDITIONS, ALLOWING SEDIMENT TO SETTLE OUT BEFORE THE RUNOFF IS DISCHARGED.

USE DESILTING BASINS FOR DISTURBED AREAS BETWEEN 5 ACRES AND 10 ACRES WHERE SEDIMENT-LADEN WATER MAY ENTER THE DRAINAGE SYSTEM OR WATERCOURSE.


DO NOT USE DESILTING BASINS FOR DRAINAGE AREAS GREATER THEN 75 ACRES AND DO NOT LOCATE BASINS WITHIN LIVE STREAMS.

SIZE DESILTING BASINS SUCH THAT THERE IS 50 C.Y. PER ACRE OF CONTRIBUTING AREA. LENGTH MUST BE EQUAL OR LARGER THAN TWICE THE WIDTH, DEPTH MUST BE BETWEEN 3 FT. AND 5 FT. ANY BASIN MEETING THE DEFINITION OF A "HIGH HAZARD DAM" MUST BE DESIGNED BY A PROFESSIONAL CIVIL ENGINEER REGISTERED IN THE STATE OF MONTANA. BASINS LARGER THAN 1300 C.Y. MUST ALSO BE DESIGNED BY A PROFESSIONAL CIVIL ENGINEER REGISTERED IN THE STATE OF MONTANA.


PLACE ROCK, VEGETATION, GEOTEXTILE OR BLANKETS TO PROTECT THE BASIN INLET AND SLOPES AGAINST EROSION. SURROUND DESILTING BASINS WITH CHAIN LINK FENCE WHEN DESIGNED IN RESIDENTIAL/COMMERCIAL AREAS OR AS DIRECTED BY THE ENGINEER.



TYPICAL DESILTING BASIN - TOP VIEW




TYPICAL DESILTING BASIN - EMERGENCY SPILLWAY CROSS SECTION



TYPICAL DESILTING BASIN - OUTLET #1


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 208	DWG. NO. 208-32A
DESILTING BASIN (SC-2) (SHEET 1)	
EFFECTIVE: JANUARY 2004	







NOTE:  
THIS OUTLET PROVIDES NO  
DRAINING OF PERMANANT POOL

TYPICAL DESILTING BASIN - OUTLET #2



NOTE:  
THIS OUTLET PROVIDES  
COMPLETE DRAINING OF POOL

TYPICAL DESILTING BASIN - OUTLET #3

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	208-32B
SECTION 208	
DESILTING BASIN (SC-2) (SHEET 2)	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION  MONTANA CADD	

SYMBOL: ———— ST ————

#### SEDIMENT TRAP SC-3:

A SEDIMENT TRAP IS A TEMPORARY BASIN WITH A CONTROLLED RELEASE STRUCTURE, FORMED BY EXCAVATING OR CONSTRUCTION OF AN EARTHEN EMBANKMENT ACROSS A WATERWAY OR LOW DRAINAGE AREA.


USE SEDIMENT TRAPS WHEN DISTURBED AREAS ARE LESS THAN 5 ACRES. THIS BMP CAN BE USED TO PROVIDE ADDITIONAL PROTECTION FOR A WATER BODY OR FOR REDUCING SEDIMENT BEFORE IT ENTERS A DRAINAGE SYSTEM.

SEDIMENT BASINS ARE NOT APPROPRIATE FOR DRAINAGE AREAS LARGER THAN 5 ACRES AND ONLY REMOVE LARGE TO MEDIUM SIZED PARTICLES. DO NOT USE SEDIMENT TRAPS IN LIVE STREAMS.


A MINIMUM SETTLING ZONE OF 70 C.Y. PER ACRE AND A MINIMUM SEDIMENT ZONE OF 35 C.Y. PER ACRE IS REQUIRED FOR EACH SEDIMENT TRAP. ANY TRAP MEETING THE DEFINITION OF A "HIGH HAZARD DAM" MUST BE DESIGNED BY A PROFESSIONAL CIVIL ENGINEER LICENSED IN THE STATE OF MONTANA. ALL TRAPS LARGER THAN 1300 C.Y. REQUIRE A DESIGN BY A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF MONTANA.

PLACE ROCK, VEGETATION, GEOTEXTILE OR BLANKETS TO PROTECT THE TRAP'S INLET, OUTLET AND SLOPES AGAINST EROSION. ENCLOSE THE SEDIMENT TRAP WITH CHAIN LINK FENCE WHEN PLACED IN RESIDENTIAL/COMMERCIAL AREAS OR AS DIRECTED BY THE ENGINEER.



REFER TO BMP SC-2 FOR RISER PIPE CONFIGURATIONS AND OVERFLOW SPILLWAY DESIGNS.



TYPICAL SEDIMENT TRAP WITH SPILLWAY TYPE OUTFALL



TYPICAL SEDIMENT TRAP WITH RISER PIPE TYPE OUTFALL

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	208-34
SECTION 208	
SEDIMENT TRAP (SC-3)	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION  MONTANA CADD	



SYMBOL: \_\_\_\_\_ CD \_\_\_\_\_

CHECK DAMS SC-4:

A CHECK DAM IS A SMALL DEVICE CONSTRUCTED OF GRAVEL, SANDBAGS, OR FIBER ROLLS, PLACED ACROSS A NATURAL OR MAN-MADE CHANNEL OR DRAINAGE DITCH. CHECK DAMS REDUCE SCOUR AND CHANNEL EROSION BY REDUCING FLOW VELOCITIES AND ENCOURAGING SEDIMENT DROP-OUT.

CHECK DAMS MAY BE INSTALLED IN SMALL CHANNELS WITH DRAINAGE AREAS OF 10 ACRES OR LESS AND/OR STEEP CHANNELS WHERE STORM WATER RUNOFF VELOCITIES EXCEED 5 FT./S. THE MAXIMUM HEIGHT FOR CHECK DAMS WITHIN THE CLEAR ZONE IS 6".

CHECK DAMS CANNOT BE USED IN LIVE STREAMS OR FOR DRAINAGE AREAS LARGER THAN 10 ACRES. IN ADDITION, CHECK DAMS CANNOT BE CONSTRUCTED FROM SILT FENCE.


PLACE CHECK DAMS AT A DISTANCE THAT WILL ALLOW SMALL POOLS TO BE FORMED BEHIND EACH DAM. INSTALL THE FIRST CHECK DAM APPROXIMATELY 15 FT. FROM THE OUTFALL DEVICE. PLACE MULTIPLE CHECK DAMS SUCH THAT BACKWATER FROM THE DOWNSTREAM DAM WILL REACH THE TOE OF THE UPSTREAM DAM. ROCK MAY BE PLACED BY HAND OR BY MECHANICAL METHOD TO ACHIEVE COMPLETE DITCH OR SWALE COVERAGE.


CHECK DAMS CONSTRUCTED FROM GRAVEL MUST BE 100% PASSING THE 2" SCREEN AND 10% MAXIMUM PASSING THE NO. 4 SIEVE. DAM MATERIAL MAY BE PITRUN OR CRUSHED AGGREGATE. REFER TO BMPs SC-5 AND SC-8 FOR USE OF FIBER ROLLS AND SAND BAGS AS CHECK DAMS. REMOVE SEDIMENT FROM BEHIND THE DAM WHEN IT ACCUMULATES TO ONE-HALF THE ORIGINAL HEIGHT UNLESS ITS DRAINAGE AREA HAS BEEN STABILIZED.

DISTANCES BETWEEN CHECK DAMS ARE AS FOLLOWS:

- FROM 1% TO 3% PLACE CHECK DAMS AT 300 FT. SPACING
- FROM 3% TO 4% PLACE CHECK DAMS AT 200 FT. SPACING
- FROM 4% + PLACE CHECK DAMS AT 100 FT. SPACING

CHECK DAM SPACING MAY BE ADJUSTED ON A PROJECT-BY-PROJECT BASIS BY THE ENGINEER. DO NOT USE CHECK DAMS ON 1-2% GRADES UNLESS DETERMINED NECESSARY BY THE ENGINEER.



DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 208	DWG. NO. 208-36
CHECK DAMS (SC-4)	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION CADD	


SYMBOL: \_\_\_\_\_ FR \_\_\_\_\_


FIBER ROLLS SC-5:

A FIBER ROLL CONSISTS OF EROSION CONTROL BLANKET MATERIAL THAT IS PREFABRICATED, OR ROLLED AND BOUND IN THE FIELD INTO A TIGHT TUBULAR ROLL, AND PLACED ON THE FACE OF SLOPES AT REGULAR INTERVALS TO INTERCEPT RUNOFF, REDUCE ITS FLOW VELOCITY, RELEASE THE RUNOFF AS SHEET FLOW, AND PROVIDE SOME REMOVAL OF SEDIMENT FROM THE RUNOFF.

FIBER ROLLS MAY BE USED ALONG THE TOP, FACE, AND AT GRADE BREAKS OF EXPOSED AND ERODIBLE SLOPES TO SHORTEN SLOPE LENGTH AND SPREAD RUNOFF AS SHEET FLOW. ROLLS MAY BE USED AS CHECK DAMS IF APPROVED BY THE ENGINEER. FOR USE AS CHECK DAMS, PLACE FIBER ROLLS AT 50 FT. MAXIMUM SPACING OR AS APPROVED BY THE ENGINEER.

ALTHOUGH FIBER ROLLS PROVIDE SOME SEDIMENT REMOVAL, FIBER ROLLS ARE NOT TO BE USED IN PLACE OF A LINEAR SEDIMENT BARRIER (I.E., SILT FENCE, SANDBAG BARRIER, OR STRAW BALE BARRIER).



DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 208	DWG. NO. 208-38
FIBER ROLLS (SC-5)	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION CADD	



SYMBOL:        GBB

GRAVEL BAG BERM SC-6:

A GRAVEL BAG BERM CONSISTS OF A SINGLE ROW OF GRAVEL BAGS THAT ARE INSTALLED END-TO-END TO FORM A BARRIER ACROSS A SLOPE TO INTERCEPT RUNOFF, REDUCE RUNOFF VELOCITY, RELEASE RUNOFF AS SHEET FLOW, AND PROVIDE SOME SEDIMENT REMOVAL. GRAVEL BAG BERMS CAN BE USED ALONG THE FACE AND AT GRADE BREAKS OF EXPOSED AND ERODIBLE SLOPES TO SHORTEN SLOPE LENGTHS AND SPREAD RUNOFF AS SHEET FLOW.

THESE DEVICES ARE NOT TO BE USED IN PLACE OF A LINEAR SEDIMENT BARRIER (I.E., SILT FENCE, SANDBAG BARRIERS, OR STRAW BALE BARRIERS).

USE WOVEN POLYPROPYLENE, POLYETHYLENE, OR POLYAMIDE FABRIC OR BURLAP MATERIAL FOR BAGS. BAG MATERIAL IS REQUIRED TO HAVE A MINIMUM UNIT WEIGHT OF 0.25 LB./S.Y. MULLEN BURST STRENGTH EXCEEDING 300 PSI AND AN ULTRAVIOLET STABILIZATION EXCEEDING 70%.


USE GRAVEL BAGS HAVING A LENGTH OF 1'-6", WIDTH OF 12", THICKNESS OF 3", AND A MASS OF APPROXIMATELY 35 LB. ALTERNATIVE BAG SIZES REQUIRE ENGINEERS APPROVAL PRIOR TO USE.



FILL GRAVEL BAGS APPROXIMATELY 75% FULL WITH GRAVEL CONSISTING OF 100% PASSING THE 3/4" SCREEN AND 10% MAXIMUM PASSING THE NO. 4 SIEVE. FILL MATERIAL MAY BE PITRUN OR CRUSHED AGGREGATE. FILL MATERIAL IS SUBJECT TO APPROVAL BY THE ENGINEER.

TIGHTLY PLACE GRAVEL BAGS TO MINIMIZE GAPS BETWEEN BAGS. BAGS MAY BE STAGGERED ON A PROJECT-BY PROJECT BASIS AS APPROVED BY THE ENGINEER.

PLACE GRAVEL BAG BERMS AT 8 FT. TO 20 FT. SPACING ALONG THE SLOPE. FOR ABNORMALLY STEEP OR SHALLOW SLOPES FOLLOW ENGINEERS GUIDELINES.

ALL BAGS PLACED WITHIN THE CLEAR ZONE REQUIRE MEASURES TO PROTECT GRAVEL FROM FREEZING. ALL FREEZE REDUCTION METHODS REQUIRE ENGINEERS APPROVAL PRIOR TO IMPLEMENTATION.



DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	208-40
SECTION 208	
GRAVEL BAG BERM (SC-6)	
EFFECTIVE: JANUARY 2004	
	MONTANA DEPARTMENT OF TRANSPORTATION
	MONTANA CADD

SYMBOL:        SAND-B

SAND BAG BARRIERS SC-8:

A SANDBAG BARRIER IS A TEMPORARY LINEAR SEDIMENTATION BARRIER CONSISTING OF STACKED SANDBAGS, DESIGNED TO INTERCEPT AND SLOW THE FLOW OF SEDIMENT-LADEN SHEET FLOW RUNOFF. SANDBAGS CAN ALSO BE USED WHERE FLOWS ARE MODERATELY CONCENTRATED, SUCH AS DITCHES, SWALES, AND STORM DRAIN INLETS TO DIVERT AND/OR DETAIN FLOWS.

LIMIT THE USE OF SANDBAG BARRIERS TO DRAINAGE AREAS OF 5 ACRES OR SMALLER. DUE TO THE BAG MATERIAL, SANDBAG BARRIERS HAVE A TENDENCY TO FAIL OVER LONG-TERM PROJECTS.

USE WOVEN POLYPROPYLENE, POLYETHYLENE, OR POLYAMIDE FABRIC OR BURLAP MATERIAL FOR BAGS. BAG MATERIAL IS REQUIRED TO HAVE A MINIMUM UNIT WEIGHT OF 0.25 LB./S.Y., A MULLEN BURST STRENGTH EXCEEDING 300 PSI AND AN ULTRAVIOLET STABILIZATION EXCEEDING 70%.




USE SANDBAGS HAVING A LENGTH OF 1'-6", WIDTH OF 12", THICKNESS OF 3", AND A MASS OF APPROXIMATELY 35 LB. ALTERNATIVE BAG SIZES MAY REQUIRE ENGINEER'S APPROVAL PRIOR TO USE.



FILL SANDBAGS WITH SAND CONSISTING OF 100% PASSING THE NO. 4 SIEVE, 50% PASSING THE NO. 10 SIEVE, AND 20% MAXIMUM PASSING THE NO. 200 SIEVE. FILL MATERIAL IS SUBJECT TO APPROVAL BY THE ENGINEER.

WHEN INSTALLING SANDBAG BARRIERS AS LINEAR CONTROL, PLACE BAGS ALONG A LEVEL CONTOUR. UPON ENDING THE SANDBAG RUN, PLACE THE LAST BAGS TO ANGLE UP THE SLOPE SO THAT FLOWS DO NOT ESCAPE AROUND THE END.

WHEN SANDBAG BARRIERS ARE PLACED IN CONCENTRATED FLOWS, STACK SANDBAGS TO HEIGHT USING A PYRAMID APPROACH WITH THE UPPER SANDBAGS OVERLAPPING THE LOWER ROW. THIS APPLICATION MAY NOT BE USED WITHIN THE CLEAR ZONE UNLESS OVERALL HEIGHT IS 6" OR LESS.

ALL BAGS PLACED WITHIN THE CLEAR ZONE REQUIRE MEASURES TO PROTECT SAND FROM FREEZING. ALL FREEZE REDUCTION METHODS REQUIRE ENGINEERS APPROVAL PRIOR TO IMPLEMENTATION.



REFERENCE	DWG. NO.
STANDARD SPEC.	208-42
SECTION 208	
SAND BAG BARRIERS (SC-8)	
EFFECTIVE: JANUARY 2004	
	MONTANA DEPARTMENT OF TRANSPORTATION
	MONTANA CADD



SYMBOL: \_\_\_\_\_ STRAW-B \_\_\_\_\_

STRAW BALE BARRIERS SC-9:

STRAW BALE BARRIERS ARE A SEDIMENT BARRIER CONSISTING OF ENTRENCHED, OVERLAPPING AND ANCHORED STRAW BALES THAT REDUCE RUNOFF VELOCITIES AND RETAIN SEDIMENT. DO NOT USE STRAW BALE BARRIERS INSIDE THE CLEAR ZONE. STRAW BALES MUST BE CERTIFIED WEED-FREE.




STRAW BALE BARRIERS ARE USED FOR SHEET OR CONCENTRATED FLOWS TO REDUCE RUNOFF VELOCITY, PROMOTE SEDIMENT RETENTION AND ALLOW SETTLING. DO NOT USE STRAW BALES IN HIGH FLOWS SUCH AS CHANNELS OR LIVE STREAMS. IN ADDITION, STRAW BALES CAN NOT BE USED ON SURFACE WHICH DO NOT ALLOW FOR ENTRENCHMENT.

MINIMUM STRAW BALES SIZE REQUIREMENTS ARE A WIDTH OF 1'-2", HEIGHT OF 1'-6", LENGTH OF 3 FT. AND A MASS OF 50 LB. USE STEEL WIRE (16 GAGE MIN.), NYLON OR POLYPROPYLENE STRING (1/16" MIN. DIAMETER) TO BIND BALES. MINIMUM BREAKING STRENGTH OF BINDING MATERIAL IS 80 LB. USE 2" BY 2" (NOMINAL) BY 3 FT. LONG WOODEN STAKES. DO NOT USE METAL STAKES.

INSTALL STRAW BALES ALONG A LEVEL CONTOUR, WITH THE LAST BALE TURNED UP SLOPE. PLACE BALES IN A 4" DEEP TRENCH, TIGHTLY ABOUT ADJACENT BALES, AND STAKE USING A MINIMUM OF TWO STAKES PER BALE. IF SLOPES EXCEED 10:1 THE LENGTH OF SLOPE UP STREAM OF THE BARRIER MUST BE LESS THAN 50 FT. OFFSET BALES AT LEAST 3 FT. FROM THE TOE OF SLOPES. IF SITE CONDITIONS DO NOT ALLOW FOR OFFSET, BALES MAY BE PLACED AT TOE.

FOLLOW GUIDELINES IN BMP SC-4 IF BALES ARE USED AS CHECK DAMS.

REPAIR OR REPLACE DAMAGED, UNDER-CUT OR END RUN BALES. REMOVE SEDIMENT BUILDUP FROM BALES ONCE IT REACHES A HEIGHT OF 1/3 THE BALE HEIGHT.



DETAILED DRAWING  
REFERENCE STANDARD SPEC.  
SECTION 208

DWG. NO.  
208-44

STRAW BALE BARRIERS  
(SC-9)

EFFECTIVE: JANUARY 2004




SYMBOL: (SDP)

STORM DRAIN INLET PROTECTION SC-10:


STORM DRAIN INLET PROTECTION IS USED AT STORM DRAIN INLETS THAT ARE SUBJECT TO RUNOFF FROM CONSTRUCTION ACTIVITIES. THESE DEVICES DRAIN AND/OR FILTER SEDIMENT-LADEN RUNOFF AND ALLOW SEDIMENT TO SETTLE PRIOR TO DISCHARGE OF STORM WATER INTO STORM WATER DRAINAGE SYSTEMS OR WATERCOURSES.

USE STORM DRAIN INLET PROTECTION WHEN PONDING WILL NOT ENCROACH INTO HIGHWAY AND FOR DRAINAGE AREAS OF 1 ACRE OR LESS. FOR FLOWS LESS THAN 0.5 CFS SILT FENCE OR STRAW BALES MAY BE USED. WHEN FLOWS EXCEED 0.5 CFS USE SANDBAG BARRIERS OR GRAVEL CHECK DAMS. FOLLOW SILT FENCE (SC-1), STRAW BALE BARRIERS (SC-9), SANDBAG BARRIERS (SC-8) AND CHECK DAMS (SC-4) FOR INSTALLATION REQUIREMENTS FOR EACH TYPE OF MATERIAL.


STRAW BALES, SAND BAGS, AND GRAVEL BERMS MAY BE USED WITHIN THE CLEAR ZONE UPON ENGINEERS APPROVAL. EXPEDIENTLY REMOVE ALL STRAW BALES, SAND BAGS, AND GRAVEL BERMS FROM THE CLEAR ZONE UPON COMPLETION OF CONSTRUCTION ACTIVITIES.




SILT FENCE - PLAN VIEW




SILT FENCE - PROFILE VIEW



STRAW BALE BARRIER - PLAN VIEW



STRAW BALE BARRIER - PROFILE VIEW



EXAMPLE ISOMETRIC VIEW

DETAILED DRAWING  
REFERENCE STANDARD SPEC.  
SECTION 208


DWG. NO.  
208-46A

STORM DRAIN INLET  
PROTECTION  
(SC-10) (SHEET 1)


EFFECTIVE: JANUARY 2004









SANDBAG BARRIER - PLAN VIEW




GRAVEL CHECK DAM - PLAN VIEW



SANDBAG BARRIER - PROFILE VIEW



GRAVEL CHECK DAM - PROFILE VIEW

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 208	DWG. NO. 208-46B
STORM DRAIN INLET PROTECTION (SC-10) (SHEET 2)	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION CADD	

SYMBOL: \_\_\_\_\_ DDB \_\_\_\_\_



DUGOUT DITCH BASIN SC-11:


DUGOUT DITCH BASINS CONSIST OF ONE OR A SERIES OF SMALL DUGOUT BASINS USED FOR CONCENTRATED FLOWS TO REDUCE RUNOFF VELOCITY, PROMOTE SEDIMENT RETENTION AND ALLOW SETTLING. THE MAXIMUM HEIGHT FOR DUGOUT DITCH BASINS USED INSIDE THE CLEAR ZONE IS 6".

DUGOUT DITCH BASINS ARE USED FOR LONGITUDINAL SLOPE STEEPNESS (GRADE) SEDIMENT RETENTION. APPLICATIONS INCLUDE DITCH SEDIMENT TRAPS, INTERCEPTOR DITCHES AND TOE OF SLOPE PROTECTION. USE IS DEPENDENT ON SOIL TYPE.

- FROM 2% TO 3% PLACE DUGOUT DITCH BASINS AT 300 FT. SPACING
- FROM 3% TO 4% PLACE DUGOUT DITCH BASINS AT 150 FT. SPACING
- FROM 4% + PLACE DUGOUT DITCH BASINS AT 50 FT. SPACING

DUGOUT DITCH BASIN SPACING CAN BE ADJUSTED ON A PROJECT-BY-PROJECT BASIS FOLLOWING ENGINEERS APPROVAL.



DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 208	DWG. NO. 208-48
DUGOUT DITCH BASIN (SC-11)	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION CADD	



WIND EROSION CONTROL WE-1:

WIND EROSION CONTROL CONSISTS OF APPLYING WATER OR OTHER DUST SUPPRESSANTS, ROUGHENING SURFACES OR INSTALLING WIND BARRIERS TO PREVENT WIND EROSION BY PROTECTING SOIL SURFACES OR BY REDUCING WIND VELOCITIES.

WATER SPRAYING:

APPLY BY MEANS OF PRESSURE-TYPE DISTRIBUTORS OR PIPELINES EQUIPPED WITH A SPRAY SYSTEM OR HOSES AND NOZZLES THAT MAY ENSURE EVEN DISTRIBUTION. DO NOT USE EXCESSIVE AMOUNTS OF WATER FOR DUST SUPPRESSION THAT MAY CAUSE SOILS TO BECOME SATURATED AND CREATE OTHER PROBLEMS SUCH AS EXCESS RUNOFF, MUD/DIRT TRACKING OR ICING IN THE WINTER MONTHS. EQUIP ALL DISTRIBUTION SYSTEMS WITH A POSITIVE MEANS OF SHUTOFF. UNLESS WATER IS APPLIED BY MEANS OF PIPELINES, AT LEAST ONE MOBILE IS REQUIRED TO BE AVAILABLE AT ALL TIMES ON THE CONSTRUCTION SITE TO APPLY WATER OR DUST SUPPRESSANTS. IF RECLAIMED WASTEWATER IS USED, THE SOURCES AND DISCHARGE MUST MEET MONTANA DEO WATER RECLAMATION CRITERIA. DO NOT USE NON-POTABLE WATER IN TANKS OR DRAIN PIPES THAT MAY BE USED TO CONVEY POTABLE WATER. DO NOT CONNECT BETWEEN POTABLE AND NON-POTABLE SUPPLIES. MARK ALL NON-POTABLE TANKS, PIPES AND OTHER CONVEYANCES AS "NON-POTABLE WATER - DO NOT DRINK".

DUST SUPPRESSANTS:

MATERIALS APPLIED AS TEMPORARY SOIL STABILIZERS AND SOIL BINDERS MAY ALSO PROVIDE WIND EROSION CONTROL BENEFITS. APPLY THESE MATERIALS PER MANUFACTURE'S SPECIFICATIONS IN ACCORDANCE WITH ALL FEDERAL, STATE AND LOCAL REGULATIONS. SEE SS-5 SOIL BINDERS.

CALCIUM CHLORIDE OR OTHER DUST SUPPRESSANTS USED ON ROADWAYS THAT ARE NOT LISTED IN SS-5 MUST MEET MDT SPECIFICATIONS AND/OR BE APPROVED BY THE ENGINEER PRIOR TO USE.


SLOPE ROUGHENING:

REFER TO SLOPE ROUGHENING TECHNIQUES DISCUSSED IN SS-12 SLOPE ROUGHENING.

WIND BARRIERS:

WIND BARRIERS PROVIDE AN AREA OF REDUCED WIND VELOCITY WHICH ALLOWS SETTLING OF LARGE SEDIMENT PARTICLES. MAXIMUM REDUCTION OF WIND VELOCITIES OCCUR IMMEDIATELY DOWNWIND OF THE WIND BARRIER, GRADUALLY DECREASING FURTHER DOWNWIND.

USE TEMPORARY WIND FENCING AS WIND BARRIERS ON CONSTRUCTION SITES. BOARD FENCING, EARTHEN BANKS, STRAW ROWS, ROCK WALLS, OR OTHER TEMPORARY WIND BARRIERS MAY BE UTILIZED AS APPROVED BY THE ENGINEER. WIND FENCING CAUSES WIND VELOCITY TO SLOW DOWN FOR APPROXIMATELY 40-50 TIMES THE FENCE HEIGHT, HOWEVER THE WIND FENCING IS ONLY EFFECTIVE FOR WIND BREAKING FOR APPROXIMATELY 10-25 TIMES THE HEIGHT OF THE FENCE. WIND FENCE IS REQUIRED TO BE A PREFABRICATED COMMERCIAL PRODUCT MADE OF WOVEN POLYETHYLENE AND ULTRAVIOLET RESISTANT MATERIAL WITH A POROSITY OF 50% MINIMUM. WIND FENCING IS MOST PROTECTIVE IN A DIRECTION THAT IS PERPENDICULAR TO THE WIND DIRECTION. FOR WIND PROTECTION OF STOCKPILES, PLACE WIND FENCING APPROXIMATELY 3 PILE HEIGHTS UPWIND OF THE STOCKPILE BASE.




SNOW ACCUMULATION MANAGEMENT (SN-2):

SNOW ACCUMULATION BARRIERS PROVIDE AN AREA OF REDUCED WIND VELOCITY WHICH ALLOWS SETTLING OF SNOW. MAXIMUM REDUCTION OF WIND VELOCITIES OCCUR IMMEDIATELY DOWNWIND OF THE SNOW BARRIER, GRADUALLY DECREASING FURTHER DOWNWIND.

SNOW FENCING IS ONLY EFFECTIVE FOR DRIFT CONTROL FOR APPROXIMATELY 15-20 TIMES THE HEIGHT OF THE FENCE. SNOW FENCE IS REQUIRED TO BE A PREFABRICATED COMMERCIAL PRODUCT MADE OF WOVEN POLYETHYLENE AND ULTRAVIOLET RESISTANT MATERIAL WITH A POROSITY OF 40-60%. SNOW FENCING IS MOST PROTECTIVE IN A DIRECTION THAT IS PERPENDICULAR TO THE WIND DIRECTION. SEVERAL PARALLEL FENCES CAN BE USED IN AREAS OF HIGH SNOW ACCUMULATION OR HIGH WIND CONDITIONS. SECURE FENCING TO APPROVED POSTS WITH FOLLOWING MANUFACTURE RECOMMENDATIONS.

MAINTAIN SNOW FENCING AS NEEDED OR AS SPECIFIED BY THE ENGINEER. REMOVE SNOW ACCUMULATIONS FROM FENCING ONCE LEVELS HAVE REACHED THE BOTTOM OF THE FENCE.











FREEZE REDUCTION SN-3:

FREEZE REDUCTION BMPs ARE USED TO ENSURE THAT CRITICAL CULVERTS DO NOT FREEZE DURING THE WINTER MONTHS. USE HEAT TRACE IN CULVERTS TO PREVENT FREEZING. IN ENGINEER APPROVED CONDITIONS A DOUBLE CULVERT SYSTEM MAY BE USED. WITH THIS SYSTEM IF ONE CULVERT FREEZES A SECOND, HIGHER OR LOWER, CULVERT WILL CONTAIN RUNOFF.

ALL ELECTRICAL WORK TO BE COMPLETED BY A LICENSED ELECTRICIAN IN ACCORDANCE WITH NATIONAL ELECTRICAL CODES AND MDT STANDARD SPECIFICATIONS. HEAT CABLE IS INTENDED FOR CONTINUOUS OPERATION IN THE WINTER AND CAN NOT BE USED TO THAW FROZEN CULVERTS.



DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 208	DWG. NO. 208-54
FREEZE REDUCTION (SN-3)	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION	






STABILIZED CONSTRUCTION ENTRANCE/EXIT TC-1:



A STABILIZED CONSTRUCTION ACCESS IS A DEFINED POINT OF ENTRANCE/EXIT TO A CONSTRUCTION SITE THAT IS STABILIZED TO REDUCE THE TRACKING OF MUD AND DIRT ONTO PUBLIC ROADS BY CONSTRUCTION VEHICLES.

USE STABILIZED CONSTRUCTION ACCESSES WHERE DIRT AND MUD MAY BE TRACKED ONTO PUBLIC ROADS, ADJACENT TO WATER BODIES, WHERE POOR SOILS ARE ENCOUNTERED, WHERE DUST MAY BE A PROBLEM, OR AS SPECIFIED BY THE ENGINEER.

CONSTRUCT STABILIZED CONSTRUCTION ENTRANCES WITH GRAVEL CONSISTING OF 100% PASSING THE 2" SCREEN AND A MAXIMUM OF 10% PASSING THE 3/8" SIEVE OR OTHER ENGINEER APPROVED MATERIAL. PROPERLY GRADE ENTRANCES/EXITS TO PREVENT RUNOFF FROM LEAVING THE SITE. PLACE A MOUNDED BERM OF MATERIAL IF REQUIRED TO PREVENT STORM WATER RUN ON/ RUNOFF AND/OR PROVIDE COVER FOR DRAIN PIPE. ROUTE STORM WATER RUNOFF TO A SEDIMENT CONTROL DEVICE BEFORE RUNOFF EXITS THE SITE.

STABILIZED CONSTRUCTION ENTRANCE SHALL BE MAINTAINED TO PREVENT TRACKING OF SEDIMENT OFF OF THE SITE. REMOVE AND REPLACE AGGREGATE WHEN VOIDS ARE FILLED OR AS DIRECTED BY THE ENGINEER.



DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 208	DWG. NO. 208-56
STABILIZED CONSTRUCTION ENTRANCE/EXIT (TC-1)	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION	



SYMBOL:





ENTRANCE/EXIT TIRE WASH TC-3:

A TIRE WASH IS AN AREA LOCATED AT A STABILIZED CONSTRUCTION ACCESS POINT WHERE PRESSURIZED WATER IS USED TO REMOVE SEDIMENT FROM TIRES AND UNDERCARRIAGE, AND TO PREVENT SEDIMENT FROM BEING TRANSPORTED ONTO PUBLIC ROADWAYS.



TIRE WASHES ARE MEANT TO BE USED ON A PROJECT-BY-PROJECT BASIS AND REQUIRES APPROVAL BY THE ENGINEER. THESE DEVICES REQUIRE A SUPPLY OF WASH WATER AND MAY REQUIRE A TURNOUT OR DOUBLE WIDE ACCESS.

FOLLOW BMP TC-1 FOR STABILIZED CONSTRUCTION ENTRANCES/EXITS. PROVIDE WASH RACK SUITABLE FOR SUPPORTING TRAFFIC LOADS. DIRECT WASH WATER FROM THE RACK, THROUGH A DRAINAGE DITCH, TO A SEDIMENT TRAP DEVICE. ENGINEERS APPROVAL IS REQUIRED PRIOR TO CONSTRUCTION.

TIRE WASH DEVICES OTHER THEN THOSE SHOWN MAY BE USED AS APPROVED BY THE ENGINEER.




SELF-CONTAINED STEEL TIRE WASH

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	208-58
SECTION 208	
ENTRANCE/EXIT TIRE WASH (TC-3)	
EFFECTIVE: JANUARY 2004	
	

TEMPORARY STREAM CROSSINGS NS-4:

A TEMPORARY STREAM CROSSING IS A STRUCTURE PLACED ACROSS A WATERWAY THAT ALLOWS VEHICLES AND/OR HEAVY EQUIPMENT TO CROSS THE WATERWAY DURING CONSTRUCTION. THE STREAM CROSSINGS PROTECT THE STREAM BANKS AND CHANNELS FROM DAMAGE CAUSED BY VEHICLE MOVEMENT WHICH RELEASES SEDIMENT.



TEMPORARY STREAM CROSSINGS CAN CONSIST OF BRIDGES, CULVERTS OR FORDS. FOLLOW STREAM CROSSING GUIDELINES PROVIDED IN THE MDT/FWP TASK FORCE RECOMMENDATIONS REPORT. TEMPORARY STREAM CROSSINGS REQUIRE THE ACQUISITION OF SPECIAL PERMITS.




NOTE:  
SURFACE FLOW OF ROAD DIVERTED BY SWALE AND/OR DIKE

TYPICAL CULVERT CROSSING


TYPICAL BRIDGE CROSSING

REFERENCE	DWG. NO.
STANDARD SPEC.	208-60
SECTION 208	
TEMPORARY STREAM CROSSINGS (NS-4)	
EFFECTIVE: JANUARY 2004	
	







TYPICAL SHOULDER INSTALLATION  
(CONCRETE PAVEMENT)




TYPICAL SHOULDER INSTALLATION  
(ASPHALT PAVEMENT)




INTERMITTENT RUMBLE STRIP SPACING






NATIONAL HIGHWAY ROUTE OR  
PRIMARY ROUTE APPLICATION



INTERSTATE APPLICATION



ISOMETRIC VIEW




	DEPTH	RADIUS	SPAN
CONCRETE	1"	1"	2"
ASPHALT	1/2" TO 3/4"	12" MAX.	6 7/8" TO 8 3/8"

RUMBLE STRIP DETAIL

NOTE:  
DO NOT INSTALL RUMBLE STRIPS OVER CONCRETE BRIDGE DECKS OR WHERE OBSTACLES, SUCH AS CONCRETE BARRIER RAIL, PREVENT PROPER PLACEMENT.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	401-02
SECTION 401	
SHOULDER RUMBLE STRIPS	
EFFECTIVE: DECEMBER 2002	
MONTANA DEPARTMENT OF TRANSPORTATION	MONTANA CADD






**MULTIPLE ARCH CULVERTS**  
(METAL CULVERTS SHOWN)

X: VARIABLE (SEE DTL. DWG. NO. 603-10 FOR CONCRETE CULV. AND 603-34 FOR METAL CULV.)


Y: FOR METAL CULV. AND CULV. WITHOUT FETS:  
Y = 4'-0" (OUTSIDE WALL TO OUTSIDE WALL)

FOR CONCRETE CULV. WITH FETS: USE Y AS REQUIRED FOR PARALLEL PIPE INSTALLATION, PER DTL. DWG. NO. 613-08


NOTE: Y MAY BE INCREASED ON LARGE DIAMETER PIPES (UP TO A MAX. OF 8'-0") TO AID IN INSTALLATION AND BACKFILL. THE QUANTITIES SHOWN IN 552-04, 06 & 08 WERE FIGURED USING Y = 4'-0". ADJUST QUANTITIES AS NEEDED WHEN Y IS OTHER THAN 4'-0".



**MULTIPLE ROUND CULVERTS**  
(METAL CULVERTS SHOWN)




**SINGLE ROUND CULVERT**  
(CONCRETE CULVERT SHOWN)



**ANCHOR BOLT DETAILS**  
6" LONG FOR METAL PIPE  
9" LONG FOR CONCRETE PIPE

ANCHOR BOLT SPACING:  
MIN. OF FIVE 3/4" DIA. GALV. ANCHOR BOLTS  
IN WALL. USE MAX. SPACING OF 1.5'.



**SECTION A-A**

NOTES:

USE CL. "DD" CONCRETE OR EQUAL.

SEE DTL. DWG. NO. 603-18 AND 603-20  
FOR BEDDING UNDER CULVERTS.

SEE DTL. DWG. NO. 613-14 FOR RIPRAP.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	552-00
SECTION 552	
CONCRETE CUTOFF WALLS FOR CULVERTS	
EFFECTIVE: JANUARY 2004	

DIAMETER OR SPAN x RISE	CUBIC YARDS OF CLASS DD CONCRETE (EACH END)										CUBIC YARDS OF RIPRAP (EACH END) ① (DTL. DWG. NO. 613-14)								C. Y. BEDDING MATERIAL ②  PER L.F. OF PIPE (DTL. DWG. NO. 603-18)	
	CUTOFF WALL (DTL. DWG. NO. 552-00)		CONCRETE EDGE PROTECTION (DTL. DWG. NO. 613-08)																	
			1.5:1		2:1		2.5:1		3:1											
			SING.	DBL.	SING.	DBL.	SING.	DBL.	SING.	DBL.	SING.	DBL.	SING.	DBL.	SING.	DBL.				
RCP (SQ. END)																				
48"	1.1	1.8	2.1	3.1	2.6	3.7	3.1	4.4	3.5	5.1	7.7	12.1	9.6	15.0	11.5	18.1	13.6	21.3	0.9	1.8
54"	1.1	1.9	2.3	3.4	2.8	4.1	3.4	4.8	3.9	5.6	8.3	13.0	10.3	16.1	12.4	19.5	14.6	22.9	1.0	2.0
60"	1.2	2.0	2.6	3.7	3.1	4.5	3.7	5.3	4.3	6.1	8.8	13.9	11.0	17.3	13.3	20.9	15.6	24.6	1.1	2.2
66"	1.3	2.1	2.8	4.0	3.3	4.8	4.0	5.7	4.6	6.6	9.4	14.8	11.9	18.9	14.4	22.7	16.9	26.7	1.2	2.4
72"	1.3	2.2	3.0	4.3	3.6	5.2	4.3	6.2	5.0	7.2	10.2	16.1	12.6	20.0	15.2	24.1	17.9	28.3	1.3	2.6
78"	1.4	2.3	3.2	4.7	3.9	5.6	4.6	6.7	5.3	7.7	10.7	17.1	13.3	21.1	16.1	25.5	18.9	29.9	1.4	2.8
84"	1.4	2.4	3.4	5.0	4.1	6.0	4.9	7.1	5.7	8.3	11.3	18.0	14.0	22.3	16.9	26.9	19.9	31.6	1.5	3.0
90"	1.5	2.5	3.6	5.3	4.4	6.4	5.2	7.6	6.1	8.8	11.9	18.9	14.7	23.4	17.8	28.2	20.9	33.2	1.6	3.2
96"	1.6	2.6	3.8	5.6	4.7	6.8	5.5	8.1	6.4	9.4	12.5	19.8	15.5	24.6	18.6	29.6	21.9	34.9	1.7	3.4
RCPA (SQ. END)																				
58.50" x 36.00"	1.1	1.8	1.9	2.8	2.2	3.3	2.6	3.9	3.1	4.5	7.7	12.4	9.6	15.4	11.6	18.6	13.6	21.9	0.9	1.7
65.00" x 40.00"	1.2	1.9	2.0	3.0	2.4	3.6	2.9	4.3	3.3	4.9	8.3	13.4	10.3	16.6	12.4	20.1	14.6	23.6	0.9	1.9
73.00" x 45.00"	1.2	2.0	2.2	3.3	2.7	4.0	3.2	4.7	3.7	5.4	9.0	14.6	11.1	18.1	13.4	21.8	15.8	25.7	1.0	2.0
88.00" x 54.00"	1.3	2.2	2.6	4.0	3.2	4.8	3.7	5.6	4.3	6.5	10.5	17.3	13.0	21.4	15.7	25.8	18.5	30.3	1.1	2.2
102.00" x 62.00"	1.4	2.4	3.0	4.6	3.6	5.5	4.3	6.5	5.0	7.5	11.9	19.6	14.7	24.3	17.7	29.2	20.8	34.4	~	~
115.00" x 72.00"	1.5	2.6	3.3	5.1	4.0	6.1	4.8	7.2	5.5	8.4	12.9	21.5	16.1	26.7	19.4	32.1	22.8	37.8	~	~
122.00" x 77.25"	1.6	2.7	3.6	5.5	4.3	6.6	5.1	7.8	6.0	9.1	13.8	23.0	17.1	28.5	20.7	34.3	24.3	40.4	~	~
138.00" x 87.13"	1.7	2.8	4.1	6.2	4.9	7.5	5.8	8.9	6.8	10.4	15.5	25.9	19.2	32.1	23.2	38.7	27.2	45.5	~	~
154.00" x 96.88"	1.8	3.0	4.5	7.1	5.5	8.5	6.5	10.1	7.6	11.7	17.2	29.0	21.4	36.0	25.8	43.3	30.3	50.9	~	~
168.75" x 106.50"	2.0	3.3	4.9	7.6	5.9	9.2	7.0	10.9	8.1	12.6	18.4	31.2	22.8	38.7	27.5	46.6	32.4	54.7	~	~
RCP (FETS)																				
48"	1.5	2.2	~	~	~	~	~	~	3.7	5.3	~	~	~	~	~	~	16.7	25.5	0.9	1.8
54"	1.6	2.4	~	~	~	~	~	~	4.0	5.8	~	~	~	~	~	~	18.1	27.7	1.0	2.0
60"	1.7	2.6	~	~	3.0	4.4	~	~	~	~	~	~	12.9	20.0	~	~	~	~	1.1	2.2
72"	1.8	2.7	~	~	3.6	5.3	~	~	~	~	~	~	14.8	23.1	~	~	~	~	1.3	2.6
84"	1.8	2.8	3.9	5.7	~	~	~	~	~	~	15.1	23.6	~	~	~	~	~	~	1.4	2.8
RCPA (FETS)																				
48"	1.4	2.2	~	~	~	~	~	~	3.0	4.4	~	~	~	~	~	~	14.2	21.5	0.9	1.7
54"	1.5	2.3	~	~	~	~	~	~	3.2	4.6	~	~	~	~	~	~	15.1	23.1	0.9	1.9
60"	1.7	2.5	~	~	~	~	~	~	3.3	4.8	~	~	~	~	~	~	15.9	24.7	1.0	2.0
72"	1.8	2.7	~	~	3.3	4.9	~	~	~	~	~	~	14.2	22.6	~	~	~	~	1.1	2.2

NOTES:

① QUANTITIES ARE BASED ON A THICKNESS OF 2 FT. AND ARE PROPORTIONED WHEN A DIFFERENT THICKNESS IS SPECIFIED.

② QUANTITIES ARE BASED ON NO. 3 FOUNDATION STABILIZATION WITH A WIDTH EQUAL TO (DIAMETER OR SPAN) + 4 FT. + (2 TIMES SHELL THICKNESS FOR CONCRETE OR 4" FOR METAL) AND A DEPTH EQUAL TO 2 FT. PLUS "X". TO COMPUTE THE TOTAL BEDDING QUANTITY MULTIPLY BY (LENGTH OF PIPE MINUS 24 FEET).

SEE DTL. DWG. NO. 603-18 FOR DEFINITION OF NO. 3 FOUNDATION STABILIZATION AND "X" DIMENSION.

FOR PIPES WITH SKEW BEVEL ENDS - DIVIDE THE QUANTITIES SHOWN BY COSINE OF SKEW ANGLE.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	552-04
SECTION 552, 603, 613	
CONCRETE, RIPRAP AND BEDDING MATERIAL QUANTITIES FOR SING. AND DBL. CULVERT INSTALLATION	
EFFECTIVE: AUGUST 1999	



DIAMETER OR SPAN x RISE	CUBIC YARDS OF CLASS DD CONCRETE (EACH END)										CUBIC YARDS OF RIPRAP (EACH END) ①								C. Y. BEDDING MATERIAL ② PER L. F. OF PIPE (DTL. DWG. NO. 603-18)	
	CUTOFF WALL (DTL. DWG. NO. 552-00)		CONCRETE EDGE PROTECTION (DTL. DWG. NO. 613-06)								(DTL. DWG. NO. 613-14)									
			1.5:1		2:1		2.5:1		3:1		1.5:1		2:1		2.5:1		3:1			
			SING.	DBL.	SING.	DBL.	SING.	DBL.	SING.	DBL.	SING.	DBL.	SING.	DBL.	SING.	DBL.	SING.	DBL.		
SSPPA 6" x 2" CORRUGATIONS 18" CORNER RADIUS																				
6'-1" x 4'-7"	1.5	2.5	1.8	2.8	2.2	3.3	2.5	3.8	~	~	7.8	12.8	9.7	15.9	11.7	19.2	~	~	1.2	2.4
6'-4" x 4'-9"	1.5	2.5	2.0	3.0	2.4	3.6	2.8	4.2	~	~	8.4	13.7	10.4	17.0	12.5	20.5	~	~	1.2	2.3
6'-9" x 4'-11"	1.6	2.7	2.0	3.0	2.3	3.6	2.7	4.2	~	~	8.4	13.8	10.4	17.1	12.5	20.7	~	~	1.3	2.5
7'-0" x 5'-1"	1.6	2.7	2.1	3.2	2.5	3.8	2.9	4.4	~	~	8.8	14.5	10.9	18.0	13.2	21.7	~	~	1.2	2.5
7'-3" x 5'-3"	1.6	2.6	2.2	3.4	2.7	4.1	3.2	4.8	~	~	9.3	15.4	11.6	19.1	14.0	23.0	~	~	1.2	2.5
7'-8" x 5'-5"	1.7	2.8	2.3	3.5	2.7	4.1	3.2	4.9	~	~	9.5	15.7	11.8	19.5	14.2	23.5	~	~	1.3	2.7
7'-11" x 5'-7"	1.7	2.8	2.4	3.6	2.8	4.3	3.3	5.1	~	~	9.8	16.2	12.2	20.1	14.7	24.3	~	~	1.3	2.6
8'-2" x 5'-9"	1.6	2.8	2.5	3.8	3.0	4.6	3.6	5.4	~	~	10.3	17.1	12.8	21.2	15.5	25.6	~	~	1.3	2.6
8'-7" x 5'-11"	1.7	2.9	2.5	3.9	3.1	4.7	3.6	5.5	~	~	10.5	17.5	13.0	21.7	15.7	26.1	~	~	1.4	2.8
8'-10" x 6'-1"	1.7	2.9	2.7	4.1	3.2	4.9	3.8	5.8	~	~	10.9	18.2	13.6	22.5	16.3	27.2	~	~	1.4	2.8
9'-4" x 6'-3"	1.8	3.1	2.7	4.1	3.2	5.0	3.8	5.8	~	~	11.0	18.4	13.6	22.8	16.4	27.5	~	~	1.5	3.0
9'-6" x 6'-5"	1.8	3.1	2.8	4.4	3.4	5.2	4.0	6.2	~	~	11.5	19.3	14.3	23.9	17.2	28.8	~	~	1.5	2.9
9'-9" x 6'-7"	1.8	3.1	3.0	4.5	3.6	5.5	4.2	6.4	~	~	11.9	20.0	14.8	24.7	17.9	29.8	~	~	1.4	2.9
10'-3" x 6'-9"	1.9	3.2	3.0	4.7	3.6	5.6	4.3	6.6	~	~	12.2	20.4	15.1	25.3	18.2	30.5	~	~	1.6	3.1
10'-8" x 6'-11"	2.0	3.5	3.0	4.7	3.6	5.6	4.2	6.6	~	~	12.1	20.4	15.0	25.3	18.1	30.6	~	~	1.7	3.4
10'-11" x 7'-1"	2.0	3.4	3.1	4.9	3.8	5.9	4.5	6.9	~	~	12.7	21.3	15.7	26.5	19.0	31.9	~	~	1.7	3.3
11'-5" x 7'-3"	2.1	3.6	3.2	5.0	3.8	6.0	4.5	7.0	~	~	12.9	21.8	16.0	27.0	19.3	32.6	~	~	1.8	3.6
11'-7" x 7'-5"	2.1	3.6	3.3	5.2	4.0	6.2	4.7	7.3	~	~	13.3	22.5	16.5	28.0	19.9	33.7	~	~	1.7	3.5
11'-10" x 7'-7"	2.0	3.5	3.5	5.4	4.2	6.5	5.0	7.7	~	~	13.9	23.5	17.2	29.1	20.8	35.1	~	~	1.7	3.4
12'-4" x 7'-9"	2.2	3.8	3.5	5.5	4.2	6.6	5.0	7.8	~	~	14.0	23.7	17.3	29.4	20.9	35.5	~	~	1.8	3.7
12'-6" x 7'-11"	2.1	3.7	3.6	5.7	4.4	6.8	5.2	8.1	~	~	14.4	24.5	17.9	30.4	21.6	36.6	~	~	1.8	3.6
12'-8" x 8'-1"	2.1	3.7	3.8	5.9	4.6	7.1	5.4	8.4	~	~	15.0	25.4	18.6	31.5	22.4	37.9	~	~	1.8	3.6
12'-10" x 8'-4"	2.1	3.6	3.9	6.1	4.8	7.4	5.6	8.7	~	~	15.5	26.3	19.3	32.6	23.2	39.2	~	~	1.7	3.5
13'-5" x 8'-5"	2.2	3.9	3.9	6.2	4.7	7.4	5.6	8.8	~	~	15.5	26.4	19.3	32.8	23.2	39.5	~	~	1.9	3.8
13'-11" x 8'-7"	2.3	4.1	4.0	6.3	4.8	7.6	5.7	9.0	~	~	15.8	27.0	19.6	33.5	23.6	40.4	~	~	2.0	4.0
14'-1" x 8'-9"	2.3	4.0	4.1	6.5	5.0	7.8	5.9	9.2	~	~	16.3	27.7	20.2	34.4	24.3	41.5	~	~	2.0	4.0
14'-3" x 8'-11"	2.3	4.0	4.3	6.7	5.2	8.1	6.1	9.6	~	~	16.8	28.6	20.9	35.5	25.1	42.8	~	~	1.9	3.9
14'-10" x 9'-1"	2.4	4.2	4.3	6.8	5.2	8.2	6.2	9.7	~	~	17.0	29.0	21.0	36.0	25.4	43.4	~	~	2.1	4.2
15'-4" x 9'-2"	2.5	4.5	4.3	6.9	5.2	8.3	6.2	9.8	~	~	17.1	29.4	21.2	36.4	25.6	43.9	~	~	2.2	4.5
15'-6" x 9'-5"	2.5	4.4	4.5	7.2	5.4	8.6	6.4	10.2	~	~	17.7	30.4	22.0	37.7	26.5	45.4	~	~	2.2	4.4
15'-8" x 9'-7"	2.4	4.3	4.7	7.4	5.6	8.9	6.7	10.6	~	~	18.3	31.3	22.7	38.8	27.3	46.8	~	~	2.2	4.3
15'-10" x 9'-9"	2.4	4.3	4.8	7.6	5.8	9.2	6.9	10.8	~	~	18.7	32.0	23.2	39.7	28.0	47.9	~	~	2.1	4.2
16'-5" x 9'-11"	2.6	4.5	4.8	7.7	5.8	9.3	6.9	11.0	~	~	18.9	32.5	23.4	40.3	28.3	48.6	~	~	2.3	4.5
16'-7" x 10'-1"	2.5	4.5	5.0	8.0	6.1	9.6	7.2	11.4	~	~	19.5	33.4	24.2	41.5	29.1	50.0	~	~	2.2	4.4
SSPPA 6" x 2" CORRUGATIONS 31" CORNER RADIUS																				
13'-3" x 9'-4"	2.5	4.3	3.8	6.0	4.6	7.3	5.5	8.6	~	~	15.1	25.7	18.8	32.0	22.6	38.5	~	~	2.2	4.3
13'-6" x 9'-6"	2.5	4.3	4.0	6.2	4.8	7.5	5.6	8.9	~	~	15.6	26.5	19.3	32.9	23.3	39.7	~	~	2.1	4.3
14'-0" x 9'-8"	2.6	4.5	4.0	6.3	4.8	7.6	5.7	9.0	~	~	15.8	27.0	19.6	33.5	23.6	40.4	~	~	2.3	4.5
14'-3" x 9'-10"	2.6	4.4	4.2	6.6	5.0	8.0	6.0	9.4	~	~	16.4	28.0	20.4	34.7	24.5	41.9	~	~	2.2	4.5
14'-5" x 10'-0"	2.5	4.4	4.3	6.8	5.2	8.2	6.2	9.7	~	~	16.8	28.7	20.9	35.6	25.2	42.9	~	~	2.2	4.4
14'-11" x 10'-2"	2.7	4.6	4.3	6.9	5.2	8.3	6.2	9.8	~	~	17.0	29.1	21.1	36.1	25.4	43.5	~	~	2.3	4.7
15'-4" x 10'-4"	2.8	4.9	4.3	6.9	5.2	8.4	6.2	9.9	~	~	17.1	29.4	21.2	36.5	25.6	44.0	~	~	2.5	4.9
15'-7" x 10'-6"	2.8	4.8	4.5	7.2	5.5	8.7	6.5	10.3	~	~	17.7	30.4	22.0	37.7	26.5	45.5	~	~	2.4	4.9
15'-10" x 10'-8"	2.7	4.8	4.7	7.5	5.7	9.0	6.7	10.6	~	~	18.3	31.4	22.7	38.9	27.4	46.9	~	~	2.4	4.8
16'-3" x 10'-10"	2.9	5.0	4.7	7.5	5.7	9.0	6.7	10.7	~	~	18.3	31.6	22.8	39.2	27.4	47.3	~	~	2.5	5.1
16'-6" x 11'-0"	2.8	5.0	4.9	7.8	5.9	9.4	7.0	11.1	~	~	18.9	32.6	23.5	40.4	28.3	48.7	~	~	2.5	5.0
17'-0" x 11'-2"	3.0	5.2	4.9	7.8	5.9	9.4	7.0	11.2	~	~	19.1	32.9	23.7	40.9	28.5	49.3	~	~	2.7	5.3
17'-2" x 11'-4"	2.9	5.2	5.0	8.1	6.1	9.7	7.2	11.5	~	~	19.6	33.8	24.3	41.9	29.3	50.5	~	~	2.6	5.2
17'-5" x 11'-6"	2.9	5.1	5.2	8.3	6.3	10.0	7.5	11.9	~	~	20.2	34.8	25.0	43.2	30.2	52.0	~	~	2.6	5.2
17'-11" x 11'-8"	3.0	5.3	5.3	8.5	6.4	10.2	7.5	12.1	~	~	20.4	35.4	25.4	43.9	30.6	52.9	~	~	2.7	5.5
18'-1" x 11'-10"	3.0	5.3	5.4	8.7	6.5	10.5	7.8	12.4	~	~	20.9	36.2	26.0	44.9	31.3	54.1	~	~	2.7	5.4
18'-7" x 12'-0"	3.1	5.5	5.4	8.8	6.6	10.6	7.8	12.5	~	~	21.1	36.6	26.2	45.4	31.6	54.8	~	~	2.8	5.7
18'-9" x 12'-2"	3.1	5.5	5.6	9.0	6.8	10.9	8.1	12.9	~	~	21.7	37.6	26.9	46.7	32.5	56.3	~	~	2.8	5.6
19'-3" x 12'-4"	3.2	5.7	5.6	9.2	6.8	11.0	8.1	13.0	~	~	21.9	38.1	27.2	47.3	32.8	56.9	~	~	3.0	5.9
19'-6" x 12'-6"	3.2	5.7	5.8	9.4	7.1	11.4	8.4	13.5	~	~	22.5	39.1	28.0	48.6	33.7	58.5	~	~	2.9	5.8
19'-8" x 12'-8"	3.2	5.6	6.0	9.6	7.2	11.6	8.6	13.8	~	~	23.0	40.0	28.6	49.6	34.4	59.8	~	~	2.9	5.8
19'-11" x 12'-10"	3.1	5.6	6.1	9.9	7.4	12.0	8.8	14.2	~	~	23.6	40.9	29.3	50.8	35.3	61.2	~	~	2.8	5.7
20'-5" x 13'-0"	3.3	5.8	6.2	10.0	7.5	12.1	8.9	14.3	~	~	23.8	41.5	29.6	51.5	35.6	62.0	~	~	3.0	6.0
20'-7" x 13'-2"	3.2	5.8	6.3	10.2	7.7	12.4	9.1	14.6	~	~	24.3	42.3	30.2	52.5	36.4	63.2	~	~	3.0	5.9

NOTES:

- ① QUANTITIES ARE BASED ON A THICKNESS OF 2 FT. AND ARE PROPORTIONED WHEN A DIFFERENT THICKNESS IS SPECIFIED.
- ② QUANTITIES ARE BASED ON NO. 3 FOUNDATION STABILIZATION WITH A WIDTH EQUAL TO (DIAMETER OR SPAN) + 4 FT. + (2 TIMES SHELL THICKNESS FOR CONCRETE OR 4" FOR METAL) AND A DEPTH EQUAL TO 2 FT. PLUS "X". TO COMPUTE THE TOTAL BEDDING QUANTITY MULTIPLY BY (LENGTH OF PIPE MINUS 24 FEET).


SEE DTL. DWG. NO. 603-18 FOR DEFINITION OF NO. 3 FOUNDATION STABILIZATION AND "X" DIMENSION.

FOR PIPES WITH SKEW BEVEL ENDS - DIVIDE THE QUANTITIES SHOWN BY COSINE OF SKEW ANGLE.


DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	552-06
SECTION 552, 603, 613	
CONCRETE, RIPRAP AND BEDDING MATERIAL QUANTITIES FOR SING. AND DBL. CULVERT INSTALLATION	
EFFECTIVE: JANUARY 2004	




CONNECTIONS



TYPE 1



TYPE 2



TYPE 3

NOTES:

PROVIDE TOE PLATE WHEN SPECIFIED.


GALVANIZE ALL PARTS IN ACCORDANCE WITH AASHTO M 36.

PAINT ANY AREAS WHERE GALVANIZING IS BROKEN OR METAL IS BARE WITH ONE COAT OF ZINC CHROMATE PRIME AND TWO COATS OF ALUMINUM PAINT.


MINOR VARIATIONS IN DESIGN MAY BE ACCEPTABLE ON APPROVAL OF THE ENGINEER.

SEAMS OR JOINTS LENGTHWISE OF THE APRON ARE ACCEPTABLE IF SECURELY BOLTED OR WELDED AND PAINTED AS PROVIDED ABOVE.


ARCH PIPE



ELEVATION




PLAN




TYPICAL CROSS-SECTION  
(ILLUSTRATED WITH TYPE 3 CONNECTION)


ROUND PIPE



ELEVATION



PLAN



TYPICAL CROSS-SECTION  
(ILLUSTRATED WITH TYPE 3 CONNECTION)

3" x 1" CORR. SPAN x RISE	MINIMUM THICKNESS	2 2/3" x 1/2" CORR. SPAN x RISE	MINIMUM THICKNESS	DIMENSIONS					TYPE CONNECTOR
				A 1" TOL.	B MAX.	H 1" TOL.	L 1 1/2" TOL.	F 2" TOL.	
		17" x 13"	0.064"	7"	9"	6"	19"	30"	2
		21" x 15"	0.064"	7"	10"	6"	23"	30"	2
		24" x 18"	0.064"	8"	12"	6"	28"	42"	2
		28" x 20"	0.064"	9"	14"	6"	32"	48"	2
		35" x 24"	0.079"	10"	16"	6"	39"	60"	2
40" x 31"	0.079"	42" x 29"	0.079"	12"	18"	8"	46"	75"	3
46" x 36"	0.109"	49" x 33"	0.109"	13"	21"	9"	53"	85"	3
53" x 41"	0.109"	57" x 38"	0.109"	18"	26"	12"	63"	90"	3
60" x 46"	0.109"	64" x 43"	0.109"	18"	30"	12"	70"	102"	3
66" x 51"	0.109"	71" x 47"	0.109"	18"	33"	12"	77"	114"	3
73" x 55"	0.109"	77" x 52"	0.109"	18"	36"	12"	77"	126"	3
81" x 59"	0.109"	83" x 57"	0.109"	18"	36"	12"	77"	138"	3

PIPE DIA.	MINIMUM THICKNESS	DIMENSIONS					TYPE CONNECTOR
		A 1" TOL.	B MAX.	H 1" TOL.	L 1 1/2" TOL.	F 2" TOL.	
12"	0.064"	6"	6"	6"	21"	24"	1
15"	0.064"	7"	8"	6"	26"	30"	1
18"	0.064"	8"	10"	6"	31"	36"	1
21"	0.064"	9"	12"	6"	36"	42"	1
24"	0.064"	10"	13"	6"	41"	48"	1
30"	0.079"	12"	16"	8"	51"	60"	2
36"	0.079"	14"	19"	9"	60"	72"	2
42"	0.109"	16"	22"	11"	69"	84"	3
48"	0.109"	18"	27"	12"	78"	90"	3
54"	0.109"	18"	30"	12"	84"	102"	3
60"	0.109"	18"	33"	12"	87"	114"	3
66"	0.109"	18"	36"	12"	87"	120"	3
72"	0.109"	18"	39"	12"	87"	126"	3
78"	0.109"	18"	42"	12"	87"	132"	3
84"	0.109"	18"	45"	12"	87"	138"	3

DETAILED DRAWING

REFERENCE DWG. NO.  
STANDARD SPEC. 603-02  
SECTION 603, 709

CMP FLARED END  
TERMINAL SECTION  
(FETS)


EFFECTIVE: AUGUST 1999

MONTANA DEPARTMENT OF TRANSPORTATION

MONTANA CADD




TYPE "A"



TYPE "A"						
DIA.	X	B	C	D	E	T *
12"	4"	2'-0"	4'- $\frac{3}{8}$ "	6'- $\frac{3}{8}$ "	2'-0"	2"
15"	6"	2'-3"	3'-10"	6'-1"	2'-6"	2 $\frac{1}{4}$ "
18"	9"	2'-3"	3'-10"	6'-1"	3'-0"	2 $\frac{1}{2}$ "
24"	9 $\frac{1}{2}$ "	3'-7 $\frac{1}{2}$ "	2'-6"	6'-1 $\frac{1}{2}$ "	4'-0"	3"
30"	1'-0"	4'-6"	1'-7 $\frac{3}{4}$ "	6'-1 $\frac{3}{4}$ "	5'-0"	3 $\frac{1}{2}$ "
36"	1'-3"	5'-3"	2'-10 $\frac{3}{4}$ "	8'-1 $\frac{3}{4}$ "	6'-0"	4"
42"	1'-9"	5'-3"	2'-11"	8'-2"	6'-6"	4 $\frac{1}{2}$ "
48"	2'-0"	6'-0"	2'-2"	8'-2"	7'-3"	5"
54"	2'-3"	5'-5"	2'-11"	8'-4"	7'-6"	5 $\frac{1}{2}$ "

\* WALL "B" THICKNESS

TYPE "B"




TYPE "B"						
DIA.	X	B	C	D	E	T *
12"	4"	2'-0"	4'- $\frac{3}{8}$ "	6'- $\frac{3}{8}$ "	2'-0"	2"
15"	6"	2'-3"	3'-10"	6'-1"	2'-6"	2 $\frac{1}{4}$ "
18"	9"	2'-3"	3'-10"	6'-1"	3'-0"	2 $\frac{1}{2}$ "
24"	9 $\frac{1}{2}$ "	3'-7 $\frac{1}{2}$ "	2'-6"	6'-1 $\frac{1}{2}$ "	4'-0"	3"
30"	1'-0"	4'-6"	1'-7 $\frac{3}{4}$ "	6'-1 $\frac{3}{4}$ "	5'-0"	3 $\frac{1}{2}$ "
36"	1'-3"	5'-3"	2'-10 $\frac{3}{4}$ "	8'-1 $\frac{3}{4}$ "	6'-0"	4"
42"	1'-9"	5'-3"	2'-11"	8'-2"	6'-6"	4 $\frac{1}{2}$ "
48"	2'-0"	6'-0"	2'-2"	8'-2"	7'-0"	5"
54"	2'-3"	5'-5"	2'-9 $\frac{1}{4}$ "	8'-2 $\frac{1}{4}$ "	7'-6"	5 $\frac{1}{2}$ "

\* WALL "B" THICKNESS


TOLERANCES IN THE ADJACENT TABLES MAY NOT VARY MORE THAN  $\pm 1.5\%$  FOR THE DIMENSIONS SHOWN. OTHERWISE THEY MUST CONFORM TO AASHTO M 170.

LARGE DIAMETER PIPE



LARGE DIAMETER CULVERT								
DIA.	SLOPE	T *	X	B	C	D	E	F
60"	2:1	6"	2'-11"	5'-0"	3'-3"	8'-3"	8'-0"	5"
72"	1.86:1	7"	3'-0"	6'-6"	1'-9"	8'-3"	9'-0"	6"
84"	1.5:1	8"	3'-0"	7'-6 $\frac{1}{2}$ "	1'-9"	9'-3 $\frac{1}{2}$ "	10'-0"	6 $\frac{1}{2}$ "


\* WALL "B" THICKNESS



TIE BOLT CONNECTION

TIE BOLTS: USE TWO TIE BOLTS ON ALL FLARED END SECTIONS, ONE ON EACH SIDE AT 60° TO THE VERTICAL. GALVANIZE ALL PARTS. SEE TIE BOLT DETAIL.

CONSTRUCTION: CONSTRUCT ACCORDING TO CLASS III, AASHTO M 170, AS FAR AS DESIGN WILL PERMIT.



TIE BOLT DETAIL  
(TWO PER END SECTION)

\*\*  $\frac{3}{4}$ " FOR 12" TO 54" DIA. RCP  
1" FOR 60" TO 84" DIA. RCP

DETAILED DRAWING


REFERENCE DWG. NO.  
STANDARD SPEC. 603-08  
SECTION 603, 708

PREFABRICATED RCP  
FLARED END TERMINAL  
SECTION (FETS)


EFFECTIVE: AUGUST 1999

MONTANA DEPARTMENT OF TRANSPORTATION







LONGITUDINAL SECTION



END VIEW



PLAN VIEW



\*\* 3/4" FOR 18" TO 54" EQUIV. SIZE  
1" FOR 60" TO 72" EQUIV. SIZE

TIE BOLT DETAIL  
(TWO PER END SECTION)

TIE BOLTS: USE TIE BOLTS ON ALL FLARED END SECTIONS, ONE ON EACH SIDE AT 60° TO THE VERTICAL. GALVANIZE ALL PARTS. SEE TIE BOLT DETAIL.

CONSTRUCTION: CONSTRUCT ACCORDING TO CLASS A-III, AASHTO M 206, AS FAR AS DESIGN WILL PERMIT.

EQUIV. SIZE	SPAN	RISE	T *	X	B	C	D	E	R	SLOPE
18"	22"	13 1/2"	2 1/2"	8 1/2"	45"	27"	72"	36"	3"	3:1
24"	28 1/2"	18"	3"	8 1/2"	39"	33"	72"	48"	3"	3:1
30"	36 1/4"	22 1/2"	3 1/2"	9 1/2"	50"	46"	96"	60"	3"	3:1
36"	43 3/4"	26 3/8"	4"	11 1/8"	60"	36"	96"	72"	6"	3:1
42"	51 1/8"	31 5/16"	4 1/2"	15 3/16"	60"	36"	96"	78"	6"	3:1
48"	58 1/2"	36"	5"	21"	60"	36"	96"	84"	6"	3:1
54"	65"	40"	5 1/2"	25 1/2"	60"	36"	96"	90"	6"	3:1
60"	73 1/2"	45"	6"	31"	60"	36"	96"	96"	6"	3:1
72"	88"	54"	7"	31"	60"	39"	99"	120"	6"	2:1

\* WALL "B" THICKNESS


DETAILED DRAWING  
REFERENCE DWG. NO.  
STANDARD SPEC. 603-10  
SECTION 603

PREFABRICATED RCP ARCH  
FLARED END TERMINAL  
SECTION (FETS)


EFFECTIVE: AUGUST 1999

MONTANA DEPARTMENT OF TRANSPORTATION  
MONTANA CADD


ROAD APPROACH CULVERT END TREATMENT										
QUANTITIES (FOR ESTIMATING ONLY)										
DIA. A RCP	H PIPE LENGTH	F-64 1/2" x 4 1/8" FERRULE LOOP INSERT (EACH)	LENGTH 2 1/2" DIA. SCHEDULE 40 GALV. PIPE	DIMENSIONS (FT. )						
				B	C	D	E	G	R	J
15"	4.75'	~	~	~	~	0.69	0.27	4.0	0.25	0.75
18"	6.5'	~	~	~	~	0.71	0.25	5.75	0.25	0.75
24"	10.0'	10	12.5'	0.5	2.0	0.75	0.21	9.25	0.25	0.75




PLAN VIEW



SECTION A-A



END VIEW



VIEW OF INSERTS

NOTE: PAINT ALL NON-GALVANIZED PARTS IN ACCORDANCE WITH SECTION 710 OF THE STANDARD SPECIFICATIONS.


DETAILED DRAWING  
REFERENCE DWG. NO.  
STANDARD SPEC. 603-12  
SECTION 603, 710

RCP ROAD APPROACH  
CULVERT END TREATMENT  
(RACET)


EFFECTIVE: AUGUST 1999

MONTANA DEPARTMENT OF TRANSPORTATION  
MONTANA CADD







PLAN VIEW



END VIEW



SECTION B-B





SECTION A-A  
ILLUSTRATED WITH 24"  
CMP (30" CMP UTILIZES  
FOUR GALV. STEEL PIPES)





ROAD APPROACH CULVERT END TREATMENT										
QUANTITIES (FOR ESTIMATING ONLY)										
DIA. A CMP	H PIPE LENGTH	3/4" x 3/8" x 1/8" GALV. CHANNEL	LENGTH 3" DIA SCHEDULE 40 GALV. PIPE	DIMENSIONS (FT.)						
				B	C	D	E	G	I	J
15"	7.0'	10'	~	~	~	0.20	0.20	5.0	6.0	1.0
18"	8.0'	10'	~	~	~	0.33	0.33	5.0	7.0	1.0
24"	10.0'	12'	6.0'	0.15	1.95	0.50	0.50	6.0	9.0	1.0
30"	12.5'	16'	10.0'	0.20	1.95	0.60	0.60	8.0	11.5	1.0

NOTES:

- 1) PIPE TO HAVE ANNULAR CORRUGATION OR REROLLED ENDS. USE ONLY APPROVED COUPLING BAND PER STANDARD SPECIFICATION 709.02 CMP. FOR RCP END TREATMENT, SEE DTL. DWG. NO. 603-26 FOR CONNECTION.
- 2) THE TWO 3/4" CHANNELS MAY BE ELIMINATED FROM THE CULVERT END TREATMENT IF:
  - A. THE CULVERT IS FABRICATED WITH 12 GAGE (0.109" THICK) MATERIAL.
  - B. HALF CIRCLE NOTCHES ARE CUT IN THE CULVERT FOR THE STEEL PIPE WITH CONTINUOUS WELD OF THE PERIPHERY IN CONTACT PROVIDED.
  - C. ALL WELDS AND OTHER NON-GALVANIZED PARTS ARE PAINTED IN ACCORDANCE WITH STANDARD SPECIFICATIONS SECTION 710.
- 3) CONNECTIONS MADE PER DTL. DWG. NO. 603-26 REQUIRE PIPE LENGTHS H AND J TO BE INCREASED BY 3".


DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	603-14
SECTION 603, 709, 710	
CMP ROAD APPROACH CULVERT END TREATMENT (RACET)	
EFFECTIVE: AUGUST 1999	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD







NOTE:  
PAINT ALL EXPOSED METAL PARTS WITH ONE COAT OF ZINC RICH PAINT AND TWO COATS OF ALUMINUM PAINT ACCORDING TO STANDARD SPECIFICATION SECTION 710.

DETAILED DRAWING	
REFERENCE	DWG. NO.
SECTION 603, 708, 710	603-17
PRECAST MEDIAN U-TURN CROSS DRAIN AND CONC. BEVELED END	
EFFECTIVE: AUGUST 1999	



NOTE: THE PROJECTION RATIO FOR POSITIVE EMBANKMENT INSTALLATIONS EQUALS THE VERTICAL DISTANCE BETWEEN THE TOP OF THE PIPE AND THE NATURAL GROUND SURFACE DIVIDED BY THE OUTSIDE VERTICAL HEIGHT OF THE PIPE.





NOTES:

- FOR STRUCTURAL PLATE PIPE, THE LENGTH OF BEDDING ARC NEED NOT EXCEED WIDTH OF BOTTOM PLATE.
- SHAPE BEDDING BLANKET OF SILTY LOAM OR SAND TO FIT BOTTOM OF PIPE. THE MINIMUM THICKNESS BEFORE PLACING PIPE IS 3".
- COMPACT SIDE FILL IN 6" LAYERS TO DENSITY SPECIFIED FOR ADJACENT EMBANKMENT. SEE SECTION 203.03.3 OF THE STANDARD SPECIFICATIONS FOR THE DENSITY REQUIREMENTS.
- SEE DTL. DWG. NO. 603-32 AND 603-34 FOR "X" DIMENSIONS.


DETAILED DRAWING	
REFERENCE	DWG. NO.
SECTION 207, 603, 701	603-18
CSP AND SSPP CULVERT BEDDING	
EFFECTIVE: DECEMBER 2002	



NOTE: THE PROJECTION RATIO (P) FOR POSITIVE EMBANKMENT INSTALLATIONS EQUALS THE VERTICAL DISTANCE BETWEEN THE TOP OF THE PIPE AND THE NATURAL GROUND SURFACE DIVIDED BY THE OUTSIDE VERTICAL HEIGHT OF THE PIPE.



### TYPES OF EMBANKMENT BEDDING



### DESCRIPTION OF BEDDING CLASSES

**CLASS A CONCRETE CRADLE BEDDING**  
THE LOWER PART OF THE PIPE EXTERIOR IS BEDDED IN A CONTINUOUS CRADLE CONSTRUCTED OF 2000 PSI CONCRETE OR BETTER, HAVING A MINIMUM THICKNESS UNDER THE PIPE OF ONE-FOURTH THE NOMINAL INSIDE DIAMETER AND EXTENDING UP THE SIDES OF THE PIPE FOR A HEIGHT EQUAL TO ONE-FOURTH OF THE OUTSIDE DIAMETER. THE CRADLE HAS A MINIMUM WIDTH EQUAL TO THE OUTSIDE DIAMETER OF THE PIPE PLUS 8", AND IS CONSTRUCTED MONOLITHICALLY WITHOUT HORIZONTAL CONSTRUCTION JOINTS.

**CLASS B BEDDING**  
(1) THIS CLASS OF BEDDING FOR EMBANKMENT CONDITIONS IS APPLICABLE ONLY WHEN THE PROJECTION RATIO IS 0.7 AND LESS. THE PIPE IS BEDDED CAREFULLY ON FINE GRANULAR MATERIALS OVER AN EARTH FOUNDATION, ACCURATELY SHAPED BY MEANS OF A TEMPLATE TO FIT THE LOWER PART OF THE PIPE EXTERIOR FOR AT LEAST 10% OF THE CULVERT OVERALL HEIGHT. THEN COMPACTABLE SOIL MATERIAL IS RAMMED AND TAMPED IN LAYERS NOT MORE THAN 6" THICK AROUND THE PIPE FOR THE REMAINDER OF THE LOWER 20% OF ITS HEIGHT. BACKFILLING IS COMPLETED TO THE TOP OF THE PIPE, CONFORMING WITH THE APPLICABLE PROVISIONS OF THE STANDARD SPECIFICATIONS.

(2) FOR TRENCH CONDITIONS, THE CULVERT IS PLACED AS DESCRIBED IN B(1) EXCEPT THAT THE EARTH FOUNDATION IS SHAPED TO FIT THE LOWER PART OF THE CULVERT EXTERIOR FOR A WIDTH OF AT LEAST 60% OF THE CULVERT BREADTH. THEN THE REMAINDER OF THE CULVERT IS ENTIRELY SURROUNDED TO A HEIGHT OF AT LEAST 12" ABOVE ITS TOP WITH GRANULAR MATERIAL PLACED BY HAND TO FILL ALL SPACES UNDER AND ADJACENT TO THE CULVERT. THE FILL IS TAMPED THOROUGHLY ON EACH SIDE AND UNDER THE CULVERT AS FAR AS PRACTICAL IN LAYERS NOT TO EXCEED 6" IN THICKNESS.

**CLASS B-1 BEDDING**  
IN THIS TYPE OF INSTALLATION, SOMETIMES CALLED THE IMPERFECT TRENCH METHOD, THE PIPE CULVERT IS FIRST INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF B(2). THEN THE FILL IS COMPACTED AT EACH SIDE OF THE PIPE FOR A LATERAL DISTANCE EQUAL TO TWICE THE OUTSIDE DIAMETER OR 12 FEET, WHICHEVER IS LESS, AND CARRIED UP TO AN ELEVATION ABOVE THE TOP OF THE PIPE EQUAL TO THE OUTSIDE DIAMETER OF THE PIPE PLUS 12". NEXT A TRENCH IS DUG EQUAL IN WIDTH TO THE OUTSIDE DIAMETER OF THE PIPE IN THE FILL DIRECTLY OVER THE CULVERT, DOWN TO AN ELEVATION 12" ABOVE THE TOP OF THE PIPE. CARE IS EXERCISED TO KEEP THE SIDES AS VERTICAL AS POSSIBLE. AFTER THE TRENCH IS EXCAVATED, IT IS REFILLED WITH LOOSE, HIGHLY COMPRESSIBLE SOIL MATERIAL, STRAW, HAY, LEAVES, BRUSH OR SAWDUST MAY BE USED TO FILL THE LOWER ONE-FOURTH TO ONE-THIRD OF THE TRENCH IN ORDER TO INSURE HIGH COMPRESSIBILITY OF THE BACKFILL. THIS BACKFILL OF STRAW, HAY, ETC. MAY NOT BE CARRIED CLOSER THAN 10 FEET TO THE OUTSIDE SLOPE OF THE FILL; THE OUTSIDE 10 FEET IS COMPOSED OF IMPERVIOUS MATERIAL, THOROUGHLY COMPACTED. AFTER THE BACKFILL IS COMPLETED, THE BALANCE OF THE FILL IS CONSTRUCTED BY NORMAL METHODS UP TO THE FINISHED GRADE OF EMBANKMENT.

**CLASS C BEDDING**  
FOR PROJECTING EMBANKMENT CULVERTS, THIS METHOD OF BEDDING IS WITH "ORDINARY" CARE IN AN EARTH FOUNDATION SHAPED IN THE FORM OF AN ARC TO FIT THE LOWER PART OF THE CULVERT EXTERIOR WITH REASONABLE CLOSENESS FOR AT LEAST 10% OF ITS OVERALL HEIGHT. THE REMAINDER OF PIPE IS SURROUNDED BY MATERIAL PLACED BY HAND TOOLS TO COMPLETELY FILL ALL SPACES UNDER AND ADJACENT TO THE PIPE. THEN BACKFILLING IS COMPLETED TO THE TOP AS SPECIFIED IN THE

STANDARD SPECIFICATIONS. IF THE CULVERT IS PLACED ON ROCK FOUNDATIONS, PROJECTING EMBANKMENT CULVERT PIPES ARE BEDDED ON AN EARTH CUSHION HAVING A MINIMUM ALLOWABLE THICKNESS OF 12" ± WITH THE EARTH FOUNDATION CAREFULLY SHAPED AND FILLED AROUND THE CULVERT THE SAME AS ORDINARY PROJECTING EMBANKMENT BEDDING ON AN EARTH FOUNDATION.

**CLASS C-1 BEDDING**  
THE PIPE IS INSTALLED IN ACCORDANCE WITH CLASS C BEDDING, USING THE IMPERFECT TRENCH METHOD AS DESCRIBED UNDER CLASS B-1 BEDDING.

WHEN NATURAL GROUND MATERIAL SIMULATES BEDDING MATERIAL, NO SPECIAL BEDDING MATERIAL NEED BE USED. CLASS C BEDDING IS USED UNLESS OTHERWISE NOTED ON THE PLANS.

**COMPACTION**  
ALL FOUNDATIONS REQUIRE COMPACTION.

DETAILED DRAWING


REFERENCE DWG. NO.  
STANDARD SPEC. 603-20  
SECTION 207, 603, 701

RCP  
CULVERT BEDDING

EFFECTIVE: AUGUST 1999

MONTANA DEPARTMENT OF TRANSPORTATION MONTANA CADD

DIA. D	APPROX. DIA. GASKET MATL. NOT STRETCHED	LENGTH OF JOINT J	D1	D2	L2 (MIN. )	L1 (WALL "B" )	L1 (WALL "C" )	X1	X2	Y1	Y2	Y3
12"	2 1/32"	3 3/8"	15.223"	15.331"	5"	2"	~	1"	3/8"	0.062"	0.090"	0.313"
15"	2 1/32"	3 3/8"	18.723"	18.831"	4 3/4"	2 3/8"	~	1"	3/8"	0.062"	0.090"	0.313"
18"	2 1/32"	3 3/8"	22.098"	22.206"	5"	2 3/8"	~	1"	3/8"	0.062"	0.090"	0.313"
21"	2 1/32"	3 3/8"	25.600"	25.724"	5 1/4"	2 3/8"	~	1"	3/8"	0.062"	0.090"	0.313"
24"	2 1/32"	3 3/8"	28.975"	29.099"	5 1/2"	2 3/4"	2"	1"	3/8"	0.062"	0.090"	0.313"
27"	2 1/32"	4"	32.476"	32.608"	5 1/2"	2 3/4"	2"	1"	3/8"	0.062"	0.090"	0.313"
30"	2 1/32"	4"	35.976"	36.108"	5 1/2"	2 3/4"	2"	1"	3/8"	0.062"	0.090"	0.313"
33"	2 1/32"	4 1/8"	39.476"	39.616"	5 3/4"	2 3/8"	2 1/8"	1"	3/8"	0.062"	0.090"	0.313"
36"	2 1/32"	4 1/8"	42.976"	43.116"	6"	3 1/8"	2 3/8"	1"	3/8"	0.062"	0.090"	0.313"
42"	3/4"	4 5/8"	50.183"	50.183"	6 3/4"	3 3/4"	3"	1 1/8"	1"	0.067"	0.129"	0.376"
48"	3/4"	4 3/4"	57.023"	57.193"	7 1/4"	4 1/8"	3 3/8"	1 1/8"	1"	0.067"	0.129"	0.376"
54"	3/4"	5"	63.007"	63.192"	7 1/2"	3 3/8"	2 3/8"	1 1/8"	1"	0.067"	0.129"	0.376"
60"	3/4"	5"	69.007"	69.192"	7 1/2"	3 3/8"	2 3/8"	1 1/8"	1"	0.067"	0.129"	0.376"
66"	13/16"	5"	75.007"	75.192"	7 1/2"	2 3/4"	2"	1 1/8"	1"	0.067"	0.129"	0.376"
72"	13/16"	5 1/4"	79.250"	79.400"	~	~	~	1 1/8"	1 1/4"	0.093"	0.190"	0.376"
78"	13/16"	5 1/4"	86.250"	86.400"	~	~	~	1 1/8"	1 1/4"	0.093"	0.190"	0.376"
84"	13/16"	5 1/4"	91.500"	91.650"	~	~	~	1 1/8"	1 1/4"	0.093"	0.190"	0.376"
90"	13/16"	5 1/4"	97.750"	97.900"	~	~	~	1 1/8"	1 1/4"	0.093"	0.190"	0.376"
96"	13/16"	5 1/4"	104.250"	104.400"	~	~	~	1 1/8"	1 1/4"	0.093"	0.190"	0.376"
102"	13/16"	5 1/4"	110.750"	110.900"	~	~	~	1 1/8"	1 1/4"	0.093"	0.190"	0.376"
108"	13/16"	5 1/4"	117.250"	117.400"	~	~	~	1 1/8"	1 1/4"	0.093"	0.190"	0.376"



NOTES:  
TYPICAL FOR STORM DRAIN AND IRRIGATION APPLICATIONS (FOR HEADS UP TO 20 FEET).  
USE RUBBER GASKETS THAT MEET THE REQUIREMENTS OF STANDARD SPECIFICATION 707.02.1.

DETAILED DRAWING

REFERENCE DWG. NO.  
STANDARD SPEC. 603-22  
SECTION 603, 707, 708

WATER TIGHT JOINT FOR REINFORCED CONCRETE PIPE


EFFECTIVE: AUGUST 1999

MONTANA DEPARTMENT OF TRANSPORTATION MONTANA CADD




DIA. D	XSEC. WATER AREA (SQ. FT.)	WT. PER L. F. OF PIPE (LB.)	T * MIN. WALL THICKNESS	J LENGTH OF JOINT	A (NOMINAL) $= \frac{D2 - D1}{2}$	D1	D2	D3	D4
12"	0.79	92	2"	1 3/4"	3/16"	13 1/4"	13 5/8"	13 7/8"	14 1/4"
15"	1.23	127	2 1/4"	2"	3/16"	16 1/2"	16 7/8"	17 1/4"	17 5/8"
18"	1.77	168	2 1/2"	2 1/4"	3/16"	19 5/8"	20"	20 5/8"	20 3/4"
21"	2.40	214	2 3/4"	2 1/2"	3/16"	22 7/8"	23 1/4"	23 3/4"	24 1/8"
24"	3.14	265	3"	2 3/4"	3/16"	26"	26 5/8"	27"	27 5/8"
27"	3.98	322	3 1/4"	3"	3/16"	29 1/4"	29 5/8"	30 1/4"	30 5/8"
30"	4.91	384	3 1/2"	3 1/4"	3/16"	32 3/8"	32 3/4"	33 1/2"	33 5/8"
33"	5.94	452	3 3/4"	3 1/2"	1/4"	35 1/2"	36"	36 3/4"	37 1/4"
36"	7.07	524	4"	3 3/4"	1/4"	38 3/4"	39 1/4"	40"	40 1/2"
42"	9.62	685	4 1/2"	4"	1/4"	45 1/8"	45 3/8"	46 1/2"	47"
48"	12.57	867	5"	4 1/4"	1/4"	51 1/2"	52"	53"	53 1/2"
54"	15.90	1070	5 1/2"	4 1/2"	1/4"	57 7/8"	58 3/8"	59 3/8"	59 5/8"
60"	19.63	1296	6"	5"	1/4"	64 1/4"	64 3/4"	66"	66 1/2"
66"	23.76	1542	6 1/2"	5 1/2"	1/4"	70 5/8"	71 1/8"	72 1/2"	73"
72"	28.27	1810	7"	6"	1/4"	77"	77 1/2"	79"	79 1/2"
78"	33.18	2098	7 1/2"	6 1/2"	1/4"	83 3/8"	83 7/8"	85 5/8"	86 1/3"
84"	38.48	2410	8"	7"	1/4"	89 3/4"	90 1/4"	92 1/8"	92 5/8"
90"	44.18	2740	8 1/2"	7"	1/4"	95 3/4"	96 1/4"	98 5/8"	98 5/8"
96"	50.27	2950	9"	7"	1/4"	102 1/8"	102 5/8"	104 1/2"	105"
102"	56.75	3075	9 1/2"	7 1/2"	1/4"	109"	109 1/2"	111 1/2"	112"
108"	63.62	3870	10"	7 1/2"	1/4"	115 1/2"	116"	118"	118 1/2"


\* WALL "B" THICKNESS




TYPICAL LONGITUDINAL SECTION  
36" DIAMETER PIPES AND LARGER




TYPICAL LONGITUDINAL SECTION  
33" DIAMETER PIPES AND SMALLER




JOINT DETAIL



SECTION A-A




SECTION B-B



REINFORCING AT ENDS OF PIPE


NOTES:  
TOLERANCES IN DIMENSIONS IN ACCORDANCE  
WITH AASHTO M 170.  
TYPICAL FOR DRAINAGE APPLICATIONS.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	603-24
SECTION 603, 708	
REINFORCED CONCRETE PIPE JOINT	
EFFECTIVE: AUGUST 1999	



SECTION A-A

CONNECTION DETAILS





TYPICAL FIELD CAST CONCRETE BEND

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	603-26
SECTION 603, 708	
TYPICAL FIELD CAST CONCRETE CONNECTIONS	
EFFECTIVE: AUGUST 1999	





This Frame left blank




NOTES:

CORRUGATION MAY BE EITHER ANNULAR OR HELICAL. BEND ON ELBOW ( $\theta$ ) IS AS SHOWN UNLESS OTHERWISE SPECIFIED IN THE PLANS OR BY THE ENGINEER.

\* INCLUDED WITH ROADWAY QUANTITIES.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 603	DWG. NO. 603-28
EMBANKMENT PROTECTOR	
EFFECTIVE: AUGUST 1999	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD






NOTE:  
SEE DTL. DWG. NO. 552-00  
FOR ANCHOR BOLT DETAILS.

SECTION C-C

ELEVATION



SECTION A-A

NOTES:

DESIGNATE THESE STRUCTURES, IN PLANS AND PROPOSAL, AS "VEHICULAR UNDERPASS." CONFORM MATERIALS, INSTALLATION, AND OTHER PROVISIONS TO THE STANDARD SPECIFICATIONS. USE THE TERM "VEHICULAR UNDERPASS," REGARDLESS OF THE USE OR PURPOSE OF THE STRUCTURE.

PROVIDE END TREATMENT FOR ALL VEHICULAR UNDERPASSES INCLUDING CUTOFF WALLS, BACKFILL RETAINING WALLS AND CONCRETE SLOPE COLLARS.

PROVIDE SURFACING FOR THE INSIDE OF THE STRUCTURE, CROSS-SLOPED TO ALLOW A DRAINAGE COURSE ALONG ONE SIDE.

FOR PLATE THICKNESS SEE ROAD DESIGN MANUAL FILL HEIGHT TABLES.


USE CLASS "DD" CONCRETE OR EQUAL.

SEE DTL. DWG. NO. 552-08 FOR QUANTITIES.



DEPTH OF SURFACING *		
MATERIAL	ALTERNATE "A"	ALTERNATE "B"
PL. MIX SURF.	—	0.20'
CR. TOP SURF.	0.20'	0.20'
CR. BASE OR SELECT SURF.	BAL.	BAL.

DIAMETER	A	B	C	V	X	* D	BACKFILL RETAINER (C. Y. )	CONCRETE COLLAR (C. Y. )
96"	4'	4'	6.9'	4.0'	2.0'	0.5'	0.04	0.66
120"	7'	7'	7.1'	5.0'	2.5'	1.4'	0.17	0.82
150"	10'	8'	8.6'	6.25'	3.13'	2.5'	0.43	1.08
162"	10'	8'	10.0'	6.75'	3.38'	2.2'	0.38	1.16
186"	12'	10'	10.8'	7.75'	3.88'	2.9'	0.59	1.34
192"	12'	10'	11.5'	8.0'	4.0'	2.7'	0.55	1.38
204"	12'	10'	12.9'	8.5'	4.25'	2.5'	0.51	1.46
216"	12'	10'	14.2'	9.0'	4.50'	2.3'	0.47	1.54
228"	16'	12'	12.5'	9.5'	4.75'	4.4'	1.23	1.72
240"	16'	12'	14.0'	10.0'	5.0'	4.0'	1.10	1.72


SURFACING QUANTITIES PER LINEAR FOOT FOR DEPTH "D" *									
ALTERNATE "A"		ALTERNATE "B"							
C. Y. SURFACING		TONS SURFACING		C. Y. SURFACING		TONS BIT. MATL.			
DIAMETER	CRUSHED TOP SURF.	CR. BASE OR SEL. SURF.	COVER MATERIAL	PLANT MIX	CRUSHED TOP SURF.	CR. BASE OR SEL. SURF.	PLANT MIX	PRIME	SEAL
96"	0.027	0.027	0.0056	0.052	0.020	0.007	0.0031	0.0005	0.0007
120"	0.050	0.205	0.0097	0.097	0.047	0.158	0.0058	0.0009	0.0012
150"	0.073	0.574	0.0139	0.141	0.070	0.504	0.0084	0.0014	0.0017
162"	0.073	0.490	0.0139	0.140	0.069	0.420	0.0084	0.0014	0.0017
186"	0.088	0.794	0.0167	0.169	0.085	0.709	0.0102	0.0017	0.0020
192"	0.087	0.743	0.0167	0.168	0.085	0.659	0.0101	0.0016	0.0020
204"	0.088	0.681	0.0167	0.169	0.084	0.596	0.0102	0.0016	0.0020
216"	0.087	0.615	0.0167	0.168	0.084	0.531	0.0101	0.0016	0.0020
228"	0.118	1.724	0.0222	0.227	0.116	1.609	0.0136	0.0022	0.0026
240"	0.117	1.539	0.0222	0.226	0.115	1.424	0.0136	0.0022	0.0026




NOTE:  
INCLUDE CONCRETE COLLAR  
WHEN SPECIFIED.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	603-30
SECTION 552, 603	
VEHICULAR UNDERPASS AND BACKFILL RETAINER & CUTOFF WALL DETAIL	
EFFECTIVE: AUGUST 1999	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD





NOTE:  
FOR DETAILS COVERING CUTOFF WALLS  
SEE DTL. DWG. NO. 552-00.



DIA.	X (FT. )	V (FT. )	H (FT. ) FOR BEVELS:		AREA "A" (SQ. FT. ) *
			1.5: 1	2: 1	
CSP 3" x 1" OR 5" x 1" CORRUGATIONS					
48"	1.000	2.000	3.000	4.000	2.63
54"	1.125	2.250	3.375	4.500	3.31
60"	1.250	2.500	3.750	5.000	4.06
66"	1.375	2.750	4.125	5.500	4.89
72"	1.500	3.000	4.500	6.000	5.79
78"	1.625	3.250	4.875	6.500	6.77
84"	1.750	3.500	5.250	7.000	7.83
90"	1.875	3.750	5.625	7.500	8.97
96"	2.000	4.000	6.000	8.000	10.18
102"	2.125	4.250	6.375	8.500	11.47
108"	2.250	4.500	6.750	9.000	12.83
114"	2.375	4.750	7.125	9.500	14.27
120"	2.500	5.000	7.500	10.000	15.79

DIA.	X (FT. )	Y (FT. )	H (FT. ) FOR BEVELS:		AREA "A" (SQ. FT. ) *
			1.5: 1	2: 1	
SSPP 6" x 2" CORRUGATIONS					
126"	2. 625	5. 250	7. 875	10. 500	17. 39
132"	2. 750	5. 500	8. 250	11. 000	19. 06
138"	2. 875	5. 750	8. 625	11. 500	20. 81
144"	3. 000	6. 000	9. 000	12. 000	22. 64
150"	3. 125	6. 250	9. 375	12. 500	24. 54
156"	3. 250	6. 500	9. 750	13. 000	26. 52
162"	2. 375	6. 750	10. 125	13. 500	28. 58
168"	3. 500	7. 000	10. 500	14. 000	30. 71
174"	3. 625	7. 250	10. 875	14. 500	32. 92
180"	3. 750	7. 500	11. 250	15. 000	35. 21
186"	3. 875	7. 750	11. 625	15. 500	37. 57
192"	4. 000	8. 000	12. 000	16. 000	40. 01
198"	4. 125	8. 250	12. 375	16. 500	42. 53
204"	4. 250	8. 500	12. 750	17. 000	45. 12
210"	4. 375	8. 750	13. 125	17. 500	47. 79
216"	4. 500	9. 000	13. 500	18. 000	50. 54
228"	4. 750	9. 500	14. 250	19. 000	56. 26
240"	5. 000	10. 000	15. 000	20. 000	62. 29
252"	5. 250	10. 500	15. 750	21. 000	68. 63



\* AREA "A" IS TO THE MIDDLE OF THE CORRUGATIONS.


DETAILED DRAWING

REFERENCE DWG. NO.  
STANDARD SPEC. 603-32  
SECTION 603

STEP BEVEL FOR  
CIRCULAR METAL CULVERT

EFFECTIVE: AUGUST 1999

 MONTANA DEPARTMENT  
OF TRANSPORTATION  MONTANA  
CADD



SEE DTL. DWG. NO. 552-00  
COVERING CUTOFF WALLS

SPAN	RISE	EQUIV. DIA.	X (FT. )	V (FT. )	H (FT. ) FOR BEVELS:			AREA "A" (SQ. FT. )
					1.5: 1	2: 1	2.5: 1	
SSPPA 6" x 2" CORRUGATIONS WITH 18" CORNER RADIUS								
6'-1"	4'-7"	66"	2.3	2.3	3.4	4.6	5.7	12.8
6'-9"	4'-11"	72"	2.4	2.5	3.8	5.0	6.3	14.8
7'-3"	5'-3"	78"	2.1	3.2	4.7	6.3	7.9	14.1
7'-11"	5'-7"	84"	2.3	3.3	4.9	6.6	8.2	16.8
8'-7"	5'-11"	90"	2.3	3.6	5.4	7.2	9.0	18.0
9'-4"	6'-3"	96"	2.5	3.8	5.6	7.5	9.4	21.0
9'-9"	6'-7"	102"	2.2	4.4	6.6	8.8	11.0	19.8
10'-8"	6'-11"	108"	2.8	4.1	6.2	8.2	10.3	26.6
11'-5"	7'-3"	114"	2.8	4.5	6.7	8.9	11.1	27.9
11'-10"	7'-7"	120"	2.5	5.1	7.6	10.2	13.6	26.4
12'-6"	7'-11"	126"	2.7	5.2	7.8	10.4	13.0	30.0
12'-10"	8'-4"	132"	2.3	6.0	8.9	11.9	14.9	26.9
SSPPA 6" x 2" CORRUGATIONS WITH 31" CORNER RADIUS								
13'-3"	9'-4"	~	3.9	5.5	8.2	10.9	13.6	45.7
13'-6"	9'-6"	~	3.8	5.7	8.6	11.5	14.3	45.7
14'-0"	9'-8"	144"	4.0	5.7	8.5	11.4	14.2	49.1
14'-3"	9'-10"	~	3.8	6.1	9.1	12.1	15.2	47.6
14'-5"	10'-0"	~	3.7	6.3	9.5	12.7	15.9	47.4
14'-11"	10'-2"	~	4.0	6.2	9.3	12.4	15.5	52.4
15'-4"	10'-4"	156"	4.3	6.0	9.1	12.1	15.1	57.6
15'-7"	10'-6"	~	4.1	6.4	9.6	12.8	16.1	55.9
15'-10"	10'-8"	~	3.9	6.8	10.2	13.6	17.0	54.2
16'-3"	10'-10"	~	4.3	6.5	9.8	13.1	16.4	61.1
16'-6"	11'-0"	168"	4.1	6.9	10.4	13.9	17.3	59.4
17'-0"	11'-2"	~	4.4	6.8	10.2	13.6	17.0	64.7
17'-2"	11'-4"	~	4.3	7.1	10.6	14.1	17.6	64.6
17'-5"	11'-6"	~	4.1	7.4	11.2	14.9	18.6	62.6
17'-11"	11'-8"	180"	4.3	7.4	11.1	14.8	18.5	66.6
18'-1"	11'-10"	~	4.2	7.7	11.5	15.3	19.2	66.4
18'-7"	12'-0"	~	4.5	7.5	11.3	15.0	18.8	72.2
18'-9"	12'-2"	~	4.3	7.9	11.8	15.8	19.7	70.1
19'-3"	12'-4"	192"	4.6	7.7	11.6	15.5	19.4	76.3
19'-6"	12'-6"	~	4.4	8.1	12.2	16.3	20.3	74.1
19'-8"	12'-8"	~	4.3	8.4	12.6	16.8	21.0	73.7
19'-11"	12'-10"	~	4.1	8.8	13.2	17.6	22.0	71.3
20'-5"	13'-0"	204"	4.4	8.6	12.9	17.3	21.6	77.6
20'-7"	13'-2"	~	4.3	8.9	13.4	17.8	22.3	77.2

SPAN	RISE	EQUIV. DIA.	X (FT. )	V (FT. )	H (FT. ) FOR BEVELS:			AREA "A" (SQ. FT. )
					1.5:1	2:1	2.5:1	
CSPA 3" x 1" CORRUGATIONS (SEE NOTE ⓧ)								
60"	46"	54"	1.7	2.3	3.5	4.7	5.8	7.1
66"	51"	60"	1.9	2.6	3.9	5.2	6.5	8.7
73"	55"	66"	2.1	2.8	4.1	5.5	6.9	10.7
81"	59"	72"	2.0	3.2	4.8	6.5	8.1	11.1
87"	63"	78"	2.1	3.5	5.2	6.9	8.6	13.2
95"	67"	84"	2.3	3.7	5.5	7.3	9.2	15.3
103"	71"	90"	2.5	3.9	5.8	7.7	9.6	17.8
112"	75"	96"	2.6	4.1	6.1	8.1	10.2	20.2
117"	79"	102"	2.8	4.3	6.4	8.5	10.7	23.1
128"	83"	108"	3.0	4.5	6.7	8.9	11.2	25.9
137"	87"	114"	3.1	4.7	7.0	9.4	11.7	29.0
142"	91"	120"	3.3	4.9	7.3	9.7	12.2	32.2
CSPA 2½" x ½" CORRUGATIONS (SEE NOTE ⓧ)								
57"	38"	48"	1.1	2.1	3.1	4.2	5.2	4.5
64"	43"	54"	1.2	2.4	3.5	4.7	5.9	5.6
71"	47"	60"	1.4	2.6	3.8	5.1	6.4	6.9
77"	52"	66"	1.5	2.8	4.3	5.7	7.1	8.2
83"	57"	72"	1.6	3.1	4.7	6.3	7.8	9.6

NOTES:

BEVEL TO TOP OF CORNER PLATE.

PIPE ENDS ARE SQUARE (PERPENDICULAR  
TO CENTERLINE OF PIPE) AND FILL SLOPES  
ARE WARPED TO ACCOMMODATE THE SQUARE  
ENDS UNLESS SPECIFIED OTHERWISE ON  
PLANS.



ⓧ TABULATED VALUES BASED ON NOMINAL PIPE  
DIMENSIONS. IN PLACE DIMENSIONS SUBJECT  
TO TOLERANCES LISTED IN CURRENT AASHTO  
M 36 AND M 196.

DETAILED DRAWING

REFERENCE DWG. NO.  
STANDARD SPEC. 603-34  
SECTION 603


BEVEL ON ARCH  
METAL CULVERT

EFFECTIVE: AUGUST 1999

 MONTANA DEPARTMENT  
OF TRANSPORTATION  MONTANA  
CADD



This Frame left blank



SECTION A-A

DIAMETER	X	* D	CLEAR RISE	H	W	BACKFILL RETAINER (CUBIC YARDS)
84"	21.0"	0.50'	6.5'	6.0'	3.6'	0.1
90"	22.5"	0.75'	6.75'	6.0'	4.5'	0.1
96"	24.0"	0.83'	7.17'	6.34'	4.9'	0.1

SURFACING QUANTITIES PER LINEAR FOOT FOR DEPTH "D" *					
DIAMETER	FULL DEPTH GRAVEL	0.20' PMS AND REMAINING DEPTH GRAVEL			
	C. Y. SURF.	TONS SURF.	C. Y. SURF.	TONS BIT. MATERIAL	
	CR. TOP SURF.	PLANT MIX	CR. TOP SURF.	PLANT MIX	PRIME
84"	0.045	0.046	0.021	0.0028	0.0004
90"	0.085	0.060	0.054	0.0036	0.0006
96"	0.102	0.066	0.068	0.0040	0.0006

NOTES:



UNLESS OTHERWISE SPECIFIED, INSTALL STOCKPASSES WITH CUTOFF WALLS AND BACKFILL RETAINERS AT EACH END, GRAVEL FILL AND BEDDING MATERIAL.

WHEN SPECIFIED, INSTALL COMBINATION STOCKPASSES AND DRAINS WITH CUTOFF WALLS, BACKFILL RETAINERS AT BOTH ENDS, CONCRETE EDGE PROTECTION AT THE INLET END, RANDOM RIPRAP AT THE OUTLET END, BEDDING MATERIAL AND ASPHALT SURFACING; CROSS SLOPE ASPHALT SURFACING TO ALLOW DRAINAGE COURSE ALONG ONE SIDE. (SEE DTL. DWG. NO. 613-14 AND 613-06.)


UNLESS OTHERWISE SPECIFIED, STEP BEVEL PIPE ENDS AT A 1.5:1 SLOPE.

THE MINIMUM THICKNESS FOR CORRUGATED STEEL PIPE STOCKPASS IS 0.079". (SEE FILL HEIGHT TABLES FOR OTHER THAN THE MINIMUM REQUIREMENTS.)





SEE DTL. DWG. NO. 552-00, 603-30 AND 603-18.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 603	DWG. NO. 603-36
CORRUGATED STEEL PIPE STOCKPASS	
EFFECTIVE: AUGUST 1999	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD





NOTE:  
WHEN MEDIAN INLET COVER IS INSTALLED OVER PIPES LARGER  
THAN 36", WITHOUT ADEQUATE COVER TO PERMIT THE USE OF  
TYPE I INSTALLATION, PROVIDE A DETAIL OF THE INSTALLATION  
IN THE PLANS.






GRATE AND REINFORCING STEEL (LB.) *			
TYPE	CMP AND RCP		
	24"	30"	36"
1	50	~	~
2	85	95	105
3	85 ☉	95 ☉	105 ☉
GRATE	165	185	210

\* QUANTITIES ARE FOR ESTIMATING PURPOSES ONLY.  
 ⦿ TYPE 3 IS A SPECIAL CASE TO BE FIGURED FOR THE PARTICULAR INSTALLATION.

CLASS "DD" CONC. OR EQUAL (C. Y.) *						
TYPE	24"		30"		36"	
	CMP	RCP	CMP	RCP	CMP	RCP
1	0.4	0.4	~	~	~	~
2	1.0	1.0	1.1	1.0	1.2	1.1
3	0.9 (A)	0.9 (A)	1.0 (A)	0.9 (A)	1.0 (A)	0.9 (A)

NOTE:  
PAINT ALL EXPOSED METAL PARTS WITH ONE COAT OF ZINC RICH  
PAINT AND TWO COATS OF ALUMINUM PAINT IN ACCORDANCE WITH  
SECTION 710 OF THE STANDARD SPECIFICATIONS.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 604	DWG. NO. 604-00
MEDIAN INLET COVER	
EFFECTIVE: AUGUST 1999	
 MONTANA DEPARTMENT OF TRANSPORTATION	
 MONTANA CAPITOL	



\* MINIMUM WEIGHT FOR FRAME AND LID IS 400 LB.  
TOOL RING AND COVER TO A MACHINE FIT.

UPPER PART IS A CONE TO REDUCE DIAMETER FROM 48" TO 24". CUT BOTTOM OF LOWER SECTION SQUARE TO FIT BASE. GROUT JOINT BETWEEN BASE AND WALL. A GROUT CONSISTING OF ONE PART PORTLAND CEMENT AND TWO PARTS APPROVED SAND MAYBE USED; AN APPROVED PREMIXED GROUT, AVAILABLE COMMERCIALY, MAY BE USED.


CONFORM ALL MANHOLE CONSTRUCTION, EXCEPT-  
ING FRAME, LID, AND BASE, TO AASHTO M 199.  
THIS PROVIDES THAT REINFORCEMENT MAY BE  
MADE OF (1) COLD DRAWN STEEL WIRE- AASHTO  
M 32, (2) STEEL WIRE FABRIC- AASHTO M 55,  
OR (3) STEEL BARS- AASHTO M 31.

THE CONSTRUCTION AND REINFORCEMENT OF THE BASE FOR EACH TYPE MUST BE COMPATIBLE WITH THE CONDITIONS AND THE WEIGHT OF THE SUPER-STRUCTURE. AASHTO M 199 PROVIDES FOR 4000 PSICONCRETE. THE MIX CALLS FOR 6 SACKS OF CEMENT PER CUBIC YARD. REINFORCEMENT SHOWN IS ILLUSTRATIVE ONLY. SEE AASHTO M 199.


THE ECCENTRIC CONE TRANSITION WILL BE PERMITTED WHEN ITS USE WILL BE AS GOOD OR BETTER THAN THE ONES SHOWN, OR IF IT IS MORE ADAPTABLE TO EXISTING CONDITIONS.

USE MANHOLE STEPS THAT ARE METALLIC AND COATED WITH COPOLYMER POLYPROPYLENE, OR AN APPROVED EQUAL. THE MINIMUM DESIGN LIVE LOAD FOR A SINGLE CONCENTRATED LOAD IS 300 POUNDS.



TYPE 3 MANHOLE ROOF SLAB					
PIPE DIA.	SLAB DIA.	T	K	BOTTOM BARS	TOP BARS
48"	58"	6"	6"	#4 AT 6"	~
54"	65"	8"	6"	#4 AT 6"	~
60"	72"	8"	7"	#4 AT 6"	#3 AT 6"
66"	79"	8"	7"	#4 AT 6"	#3 AT 6"
72"	86"	8"	8"	#4 AT 6"	#3 AT 6"
78"	93"	8"	8"	#4 AT 4"	#4 AT 4"
84"	100"	8"	9"	#4 AT 4"	#4 AT 4"
90"	107"	8"	9"	#4 AT 4"	#4 AT 4"
96"	114"	8"	9"	#5 AT 4"	#4 AT 4"
102"	121"	8"	9"	#5 AT 4"	#4 AT 4"




TYPE 3 MANHOLE




TYPE 3 MANHOLE ROOF SLAB

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 604, 711	DWG. NO. 604-02
CONCRETE MANHOLE	
EFFECTIVE: AUGUST 1999	
 MONTANA DEPARTMENT OF TRANSPORTATION	
 MONTANA CADD	






PLAN  
NEENAH FOUNDRY R-3286-8V (JUNE 1992  
REVISION) OR APPROVED EQUAL (VANE STYLE)





SECTION A-A



SECTION B-B  
\*\* STANDARD UNLESS OTHERWISE NOTED ON THE PLANS.

NOTE:  
ALL CONCRETE IS CLASS "DD" OR  
APPROVED EQUAL.


#### COMBINATION




ROOF SLAB

SEE DETAILED DRAWING NO. 604-02 FOR DIAMETER,  
SLAB THICKNESS AND REINFORCING REQUIREMENTS  
FOR COMBINATION TYPE 3 MANHOLE, TYPE II CURB  
INLET.


DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	604-03
SECTION 604	
CURB INLET TYPE II	
EFFECTIVE: AUGUST 1999	



PLAN  
NEENAH CASTING R-3210-L (VANE  
STYLE) OR APPROVED EQUAL




SECTION A-A





SECTION B-B

NOTE:  
ALL CONCRETE IS CLASS "DD" OR  
APPROVED EQUAL.



SINGLE DROP INLET  
TYPE IV

#### COMBINATION






ROOF SLAB



SEE DETAILED DRAWING NO. 604-02 FOR DIAMETER,  
SLAB THICKNESS AND REINFORCING REQUIREMENTS  
FOR COMBINATION TYPE 3 MANHOLE, TYPE IV DROP  
INLET.



DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	604-04
SECTION 604	
DROP INLET TYPE IV	
EFFECTIVE: AUGUST 1999	















DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 604	DWG. NO. 604-06
<p>TYPE IV DROP INLET WITH SLOTTED DRAIN</p>	
EFFECTIVE: AUGUST 1999	
	MONTANA DEPARTMENT OF TRANSPORTATION
	




DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 604	DWG. NO. 604-08
TYPE II CURB INLET WITH SLOTTED DRAIN	
EFFECTIVE: AUGUST 1999	
 MONTANA DEPARTMENT OF TRANSPORTATION	
 MONTANA CADD	






QUANTITIES *		
	CONCRETE	REINF. STL.
TYPE I	0.45 C.Y.	40 LB.
TYPE II	1.5 C.Y.	145 LB.
TYPE III	1.0 C.Y.	90 LB.


\* FOR ESTIMATING PURPOSES ONLY



ROUND, SINGLE DROP INLET  
TYPE I



DOUBLE DROP INLET  
TYPE II



SINGLE DROP INLET  
TYPE III

#### NOTES:

USE TYPE I, TYPE II AND TYPE III DROP INLETS IN SAG LOCATIONS ONLY.


ALL CONCRETE IS CLASS "DD" OR APPROVED EQUAL.

SEE PLANS FOR DETAILS AND QUANTITIES.


\*\* STANDARD UNLESS OTHERWISE NOTED ON PLANS.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	604-14
SECTION 604	
DROP INLETS	
EFFECTIVE: DECEMBER 2002	
MONTANA DEPARTMENT OF TRANSPORTATION	MONTANA CADD







## TYPICAL INSTALLATION



## TYPICAL INSTALLATION




## WOOD POST AND MOUNTING DETAIL




CURB WHEN SPECIFIED  
(SEE DTL. DWG. NO.  
603-28 AND 609-05)

## TYPICAL INSTALLATION




### STEEL POST AND MOUNTING DETAIL

① STANDARD UNLESS SPECIFIED OTHERWISE IN PLANS.



CURB WHEN SPECIFIED  
(SEE DTL. DWG. NO.  
603-28 AND 609-05)

## TYPICAL INSTALLATION






REFLECTOR  
(SEE NOTES)

NOTES:

- ① INSTALL ALL BOLTS WITH HEADS ON TRAFFIC SIDE OF INSTALLATION.
  - ② USE WOOD BLOCKS OR OTHER NCHRP 350 APPROVED BLOCKS. AFFIX BLOCKS TO POSTS WITH TWO 16 PENNY GALV. NAILS OR 1/4 GAGE WIRE WRAP.
  - ③ ATTACH REFLECTORS TO POSTS EVERY 25 FEET, INCLUDING TERMINAL SECTIONS, WITH THE REFLECTORIZED SURFACE FACING ADJACENT TRAFFIC. FABRICATE REFLECTORS FROM 0.063" THICK ALUMINUM ALLOY MEETING THE REQUIREMENTS OF STD. SPEC. 704. FASTEN REFLECTOR TO WOOD POST USING TWO 16 PENNY RING-SHANKED GALVANIZED NAILS AND TWO 3/8" DIA. WASHERS IN PRE-DRILLED HOLES.
  - ④ ON EXISTING GUARDRAIL INSTALLATIONS, THE MINIMUM RAIL HEIGHT IS 1'-6".
  - ⑤ WIDENING IS REQUIRED IF FINISHED SHOULDER IS LESS THAN 2'-0" FROM THE TRAFFIC LANE.
- \* SEE DTL. DWG. NO. 608-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

\*SEE DTL. DWG. NO. 606-80 FOR SCHEDULE  
OF GUARDRAIL HARDWARE.



	<b>MONTANA DEPARTMENT OF TRANSPORTATION</b>	
<b>EFFECTIVE: JANUARY 2004</b>	<b>METAL GUARDRAIL - WOOD POSTS</b>	
<b>REFERENCE STANDARD SPEC. SECTION 606</b>	<b>DWG. NO. 606-05A</b>	
<b>DETAILED DRAWING</b>		

REFLECTOR  
(SEE NOTES)

NOTES:


- ① INSTALL ALL BOLTS WITH HEADS ON TRAFFIC SIDE OF INSTALLATION.
  - ② USE ROUTED WOOD BLOCKS OR OTHER NCHRP 350 APPROVED BLOCKS.
  - ③ ATTACH REFLECTORS TO POSTS EVERY 25 FEET, INCLUDING TERMINAL SECTIONS, WITH THE REFLECTORIZED SURFACE FACING ADJACENT TRAFFIC. FASTEN REFLECTOR TO STEEL POST USING AN APPROVED ADHESIVE. REFLECTORS MAY BE BOLTED TO POSTS PROVIDED HOLES IN POSTS ARE DRILLED BEFORE BEING GALVANIZED.
  - ④ ON EXISTING GUARDRAIL INSTALLATIONS, THE MINIMUM RAIL HEIGHT IS 1'-6".
  - ⑤ WIDENING IS REQUIRED IF FINISHED SHOULDER IS LESS THAN 2'-0" FROM THE TRAFFIC LANE.
- \* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

\*SEE DTL. DWG. NO. 606  
OF GUARDRAIL HARDWARE.

	MONTANA DEPARTMENT OF TRANSPORTATION	
EFFECTIVE: JANUARY 2004		
METAL GUARDRAIL - STEEL POSTS		
DETAILED DRAWING REFERENCE STANDARD SPEC, SECTION 606	DWG. NO. 606-05B	




This Frame left blank






SEE DTL. DWG. 606-05A & 606-05B FOR METAL GUARDRAIL (W-BEAM).


COMPACT SLOPES TO MEET THE DENSITY REQUIREMENTS OF STANDARD SPECIFICATION SECTION 203.03.




BILL OF MATERIAL		
PC	QTY	DESCRIPTION
60G	1	DEEP BEAM G.R. (25'-0")
62G	1	DEEP BEAM G.R. (25'-0")
704A	1	CABLE ANCHOR BRACKET
782G	1	BEARING PLATE, 8" x 8" x 5/8"
995A	1	GUARDRAIL EXTRUDER
3000G	1	CABLE ASSEMBLY
3300G	6	5/8" DIA. WASHER
3340G	22	5/8" DIA. HEX NUT
3360G	16	5/8" DIA. x 1/4" SPLICE BOLT
3500G	6	5/8" DIA. x 10" POST BOLT
3701G	19	3/4" DIA. WASHER
3704G	16	3/4" DIA. HEX NUT
3717G	15	3/4" DIA. x 2 1/2" HEX HEAD BOLT
3718G	1	3/4" DIA. x 3" HEX HEAD BOLT
3900G	2	1" DIA. WASHER
3910G	2	1" DIA. HEX NUT
4076B	6	WOOD BLOCK, 6" x 8" x 1'-2"
4254G	18	3/8" DIA. WASHER
4255G	2	3/8" DIA. FENDER WASHER (1 1/2" O.D.)
4258G	16	3/8" DIA. LOCKWASHER
4261G	2	3/8" DIA. x 1 1/2" HEX HEAD BOLT
4699G	16	3/4" DIA. LOCKWASHER
6321G	16	3/8" DIA. x 2" HEX HEAD BOLT
6405G	18	3/8" DIA. HEX NUT
33871A	1	ETPLUS HBA POST P1 (UPPER)
33872A	7	ETPLUS HBA POST P2 TO P8 (UPPER)
33873A	2	ETPLUS HBA POST P1 & P2 (LOWER)
33874A	6	ETPLUS HBA POST P3 TO P8 (LOWER)
33875G	1	6'-6" ANGLE STRUT ET HBA




DETAIL D



VIEW D-D




VIEW H-H



DETAIL K  
(AT POST P1)


NOTE:

SECTION "A-A" IS SIMILAR AT POST P5 EXCEPT RAIL IS NOT ATTACHED.




SECTION A-A

(TYP AT POSTS P3, P4, P6, P7 & P8)




SECTION B-B

(AT POST P2)



DETAIL H

(AT POST P2)



VIEW K-K

NOTES:



- THE 5/8" DIA. FLAT WASHER IS USED UNDER THE NUT, BEHIND THE POST ONLY. NO WASHER IS USED AT THE RAIL.
- USE THE ET-PLUS TERMINAL SECTION ON DIVIDED ROADWAYS IF THE WIDTH IS 25 FEET OR GREATER BETWEEN FINISHED SURFACES. CONSIDER OTHER TERMINAL SECTIONS IF THE WIDTH IS LESS THAN 25 FEET BETWEEN FINISHED SURFACES.
- FLARE THE END SECTION AWAY FROM TRAFFIC AT A RATE OF 50:1 FOR 50 FEET (ILLUSTRATED). FLARES OF 50:1 FOR 100 FEET MAY ALSO BE USED. THE FLARE MAY BE OMITTED ON ROADS WITH SHOULDERS GREATER THAN 2 FEET IN WIDTH.
- PLACE A SELF-ADHESIVE OBJECT MARKER ON THE GUARDRAIL EXTRUDER FACE, HAVING ALTERNATING RETRO-REFLECTIVE BLACK AND YELLOW STRIPES SLOPED DOWNWARD AT AN ANGLE OF 45° TOWARDS THE SIDE ON WHICH TRAFFIC IS TO PASS.
- ATTACH REFLECTORS TO TERMINAL SECTION POSTS, PER DTL. DWG. NO. 606-05A & 606-05B.
- AFTER FINAL ASSEMBLY, RECHECK CABLE TO MAKE SURE IT IS TAUT AND HAS NOT RELAXED.
- OBTAIN ENGINEER'S APPROVAL OF MANUFACTURER INSTALLATION OPTIONS WHEN SITE CONDITIONS PREVENT THE USE OF THE OPTION SHOWN ON THIS DETAIL.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-13A
SECTION 606	
OPTIONAL TERMINAL SECTION - ET-PLUS	
EFFECTIVE: DECEMBER 2002	
MONTANA DEPARTMENT OF TRANSPORTATION	




SEE DTL. DWG. NO. 606-05A & 606-05B  
FOR METAL GUARDRAIL (W-BEAM).

COMPACT SLOPES TO MEET THE  
DENSITY REQUIREMENTS OF STANDARD  
SPECIFICATION SECTION 203.03.



DETAIL D  
(TYP. AT POSTS P2 THRU P8)




IMPACT HEAD CONNECTION DETAIL


BILL OF MATERIAL		
PC	QTY	DESCRIPTION
S3000	1	IMPACT HEAD
S1305	1	W-BEAM GUARDRAIL END SECTION (25'-0")
G1205	1	W-BEAM GUARDRAIL (25'-0")
HP1A	1	FIRST POST ASSEMBLY TOP
HP1B	1	FIRST POST ASSEMBLY BOTTOM
HP2A	1	SECOND POST ASSEMBLY TOP
HP2B	1	SECOND POST ASSEMBLY BOTTOM
HP3A	6	BREAKAWAY LINE POST TOP
HP3B	6	BREAKAWAY LINE POST BOTTOM
E750	1	BEARING PLATE
S760	1	CABLE ANCHOR BOX
E770	1	BCT CABLE ANCHOR ASSEMBLY
S785	1	GROUNDLINE STRUT
P616	6	ROUTED WOOD BLOCKOUT
B580122	17	5/8" DIA. x 1 1/4" SPLICE BOLT
B580904A	1	5/8" DIA. x 9" HEX BOLT
B580204A	28	5/8" DIA. x 2" HEX BOLT
B581002	6	5/8" DIA. x 10" H.G.R. BOLT
N055	29	5/8" DIA. HEX NUT
N050	23	5/8" DIA. H.G.R. NUT
W050	65	5/8" DIA. H.G.R. WASHER
N100	2	1" DIA. ANCHOR CABLE HEX NUT
W100	2	1" DIA. ANCHOR CABLE WASHER
B140304	2	1/4" DIA. x 3" HEX BOLT
N014	2	1/4" DIA. HEX NUT
W014	4	1/4" DIA. WASHER
SB58A	8	CABLE ANCHOR BOX SHOULDER BOLT
N055A	8	1/2" DIA. A325 STRUCTURAL NUT
W050A	16	5/16" DIA. (1 1/16" O.D.) A325 STRUCTURAL WASHER

# NOTES:


- THE 5/8" DIA. H.G.R. WASHER IS USED UNDER THE NUT, BEHIND THE POST ONLY. NO WASHER IS USED AT THE RAIL.
- USE THE SKT 350 TERMINAL SECTION ON DIVIDED ROADWAYS IF THE WIDTH IS 25 FEET OR GREATER BETWEEN FINISHED SURFACES. CONSIDER OTHER TERMINAL SECTIONS IF THE WIDTH IS LESS THAN 25 FEET BETWEEN FINISHED SURFACES.
- FLARE THE END SECTION AWAY FROM TRAFFIC AT A RATE OF 50:1 FOR 50 FEET (ILLUSTRATED). FLARES OF 50:1 FOR 100 FEET MAY ALSO BE USED. THE FLARE MAY BE OMITTED ON ROADS WITH SHOULDERS GREATER THAN 2 FEET IN WIDTH.
- PLACE A SELF-ADHESIVE OBJECT MARKER ON THE GUARDRAIL IMPACT HEAD FACE, HAVING ALTERNATING RETRO-REFLECTIVE BLACK AND YELLOW STRIPES SLOPED DOWNWARD AT AN ANGLE OF 45° TOWARDS THE SIDE ON WHICH TRAFFIC IS TO PASS.
- ATTACH REFLECTORS TO TERMINAL SECTION POSTS, PER DTL. DWG. NO. 606-05A & 606-05B.
- AFTER FINAL ASSEMBLY, RECHECK CABLE TO MAKE SURE IT IS TAUT AND HAS NOT RELAXED.
- OBTAIN ENGINEER'S APPROVAL OF MANUFACTURER INSTALLATION OPTIONS WHEN SITE CONDITIONS PREVENT THE USE OF THE OPTION SHOWN ON THIS DETAIL.



SECTION B-B  
(TYP. AT POSTS P3 THRU P8)



SECTION A-A  
(AT POST P2)




DETAIL K  
(AT POST P1)




DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-13B
SECTION 606	
OPTIONAL TERMINAL SECTION - SKT 350	
EFFECTIVE: DECEMBER 2002	
MONTANA DEPARTMENT OF TRANSPORTATION	MONTANA CADD




This Frame left blank









- NOTES:
- ① TAPERED CONCRETE CURBS:  
TYPE 1, SEE DTL. DWG. NO. 606-26  
TYPE 3, SEE DTL. DWG. NO. 606-27
  - ② TAPERED CONCRETE CURBS ARE ALSO REQUIRED ON CONCRETE APPROACH SLABS.
  - ③ PORTIONS OF GUARDRAIL & BLOCKOUTS ARE OMITTED FOR CLARITY.
  - ④ LAP GUARDRAIL IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE. (SEE DTL. DWG. NO. 606-05A).
  - ⑤ LAP W-BEAM TERMINAL CONNECTOR (RWE02a-b) IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE.
  - ⑥ USE WOOD BLOCKS OR OTHER NCHRP 350 APPROVED BLOCKS FOR BLOCKOUTS.
  - ⑦ DO NOT FLARE BRIDGE APPROACH SECTIONS.
  - ⑧ SEE DTL. DWG. NO. 606-25A FOR SKEWED BRIDGES.
  - ⑨ SEE DTL. DWG. NO. 606-05A FOR METAL GUARDRAIL (W-BEAM).



METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 1  
(FOR BRIDGES USING CONCRETE BARRIER RAIL)






METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 2  
(FOR BRIDGES WITHOUT CURBS)




METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 3  
(FOR BRIDGES WITH EXISTING CONCRETE CURBS)

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-24A
SECTION 606	
BRIDGE APPROACH SECTIONS - WOOD POSTS	
EFFECTIVE: JUNE 2003	







- NOTES:
- ① TAPERED CONCRETE CURBS:  
TYPE 1, SEE DTL. DWG. NO. 606-26  
TYPE 3, SEE DTL. DWG. NO. 606-27
  - ② TAPERED CONCRETE CURBS ARE ALSO REQUIRED ON CONCRETE APPROACH SLABS.
  - ③ PORTIONS OF GUARDRAIL & BLOCKOUTS ARE OMITTED FOR CLARITY.
  - ④ LAP GUARDRAIL IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE. (SEE DTL. DWG. NO. 606-05B).
  - ⑤ LAP W-BEAM TERMINAL CONNECTOR (RWE02a-b) IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE.
  - ⑥ USE ROUTED WOOD BLOCKS OR OTHER NCHRP 350 APPROVED BLOCKS FOR BLOCKOUTS.
  - ⑦ DO NOT FLARE BRIDGE APPROACH SECTIONS.
  - ⑧ SEE DTL. DWG. NO. 606-25B FOR SKEWED BRIDGES.
  - ⑨ SEE DTL. DWG. NO. 606-05B FOR METAL GUARDRAIL (W-BEAM).



METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 1  
(FOR BRIDGES USING CONCRETE BARRIER RAIL)




METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 2  
(FOR BRIDGES WITHOUT CURBS)




METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 3  
(FOR BRIDGES WITH EXISTING CONCRETE CURBS)

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-24B
SECTION 606	
BRIDGE APPROACH SECTIONS - STEEL POSTS	
EFFECTIVE: JUNE 2003	





**METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 1**  
(FOR SKEWED BRIDGES USING CONCRETE BARRIER RAIL)




**METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 3**  
(FOR SKEWED BRIDGES WITH EXISTING CONCRETE CURBS)


**NOTES:**

- ① TAPERED CONCRETE CURBS:  
TYPE 1, SEE DTL. DWG. NO. 606-26  
TYPE 3, SEE DTL. DWG. NO. 606-27
- ② TAPERED CONCRETE CURBS ARE ALSO REQUIRED ON CONCRETE APPROACH SLABS.
- ③ LAP GUARDRAIL IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE. (SEE DTL. DWG. NO. 606-05A).
- ④ LAP W-BEAM TERMINAL CONNECTOR (RWE02a-b) IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE.
- ⑤ USE WOOD BLOCKS OR OTHER NCHRP 350 APPROVED BLOCKS FOR BLOCKOUTS.
- ⑥ DO NOT FLARE BRIDGE APPROACH SECTIONS.
- ⑦ SEE DTL. DWG. NO. 606-24A FOR ADDITIONAL INFORMATION.
- ⑧ SEE DTL. DWG. NO. 606-05A FOR METAL GUARDRAIL (W-BEAM).

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-25A
SECTION 606	
SKEWED BRIDGE APPROACH SECTIONS - WOOD POSTS	
EFFECTIVE: DECEMBER 2002	



**METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 1**  
(FOR SKEWED BRIDGES USING CONCRETE BARRIER RAIL)




**METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 3**  
(FOR SKEWED BRIDGES WITH EXISTING CONCRETE CURBS)

**NOTES:**

- ① TAPERED CONCRETE CURBS:  
TYPE 1, SEE DTL. DWG. NO. 606-26  
TYPE 3, SEE DTL. DWG. NO. 606-27
- ② TAPERED CONCRETE CURBS ARE ALSO REQUIRED ON CONCRETE APPROACH SLABS.
- ③ LAP GUARDRAIL IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE. (SEE DTL. DWG. NO. 606-05B).
- ④ LAP W-BEAM TERMINAL CONNECTOR (RWE02a-b) IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE.
- ⑤ USE WOOD BLOCKS OR OTHER NCHRP 350 APPROVED BLOCKS FOR BLOCKOUTS.
- ⑥ DO NOT FLARE BRIDGE APPROACH SECTIONS.
- ⑦ SEE DTL. DWG. NO. 606-24B FOR ADDITIONAL INFORMATION.
- ⑧ SEE DTL. DWG. NO. 606-05B FOR METAL GUARDRAIL (W-BEAM).


DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-25B
SECTION 606	
SKEWED BRIDGE APPROACH SECTIONS - STEEL POSTS	
EFFECTIVE: JUNE 2003	






WIRE ROPE DETAIL


BILL OF REINFORCING STEEL (ONE SECTION ONLY)									
 TYPE 1									
BENT BARS (ALL DIMENSIONS ARE OUT TO OUT)									
MARK	SIZE	NO.	TYPE	LENGTH	A	B	C	D	E
C1	#4	1	I	4'-8"	11"	1'-4"	1'-1"	9"	3 1/2"
C2				4'-2"	9 1/2"	1'-2"	1 1/2"	8"	
C3				3'-9"	8 1/2"	1'-1/2"	10"	7"	
C4				3'-3"	7"	10 1/2"	8"	6 1/2"	
C5				2'-11"	6"	9"	7"	6"	
C6				2'-4"	4"	7"	5"	5"	
C7				2'-0"	3 1/2"	5 1/2"	3 1/2"	4 1/2"	3 1/2"
C8		1	I	1'-6"	2"	3 1/2"	2"	3 1/2"	1 1/2"
B1	#4	4	STRAIGHT	6'-9"	~	~	~	~	~




PLAN



VIEW A-A



VIEW B-B




SECTION C-C

NOTES:


- ① TAPERED CONCRETE CURB IS USED WITH BRIDGE APPROACH SECTION TYPE 1 (SEE DTL. DWG. NO. 606-24A AND 606-24B).
- ② WIRE ROPE CONSISTS OF ZINC-COATED STEEL WIRE 7 STRAND UTILITY GRADE WITH A MINIMUM BREAKING STRENGTH OF 25,000 LB., COMFORMING TO ASTM SPECIFICATION A 475.
- ③ ALL REINFORCING STEEL IS OF THE DEFORMED TYPE, MEETING THE REQUIREMENTS OF AASHTO M 31 (ASTM A 615, GRADE 60).
- ④ ALL CONCRETE IS CLASS "DD".  
TOTAL CONCRETE PER 7' TAPERED CURB EST. = 0.2 C.Y.  
TOTAL REBAR WEIGHT PER 7' TAPERED CURB EST. = 34 LB.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-26
SECTION 606	
TAPERED CONCRETE CURB DETAIL	
EFFECTIVE: JUNE 2003	




END VIEW

BILL OF REINFORCING STEEL (ONE SECTION ONLY)						
 TYPE 1						
BENT BARS (ALL DIMENSIONS ARE OUT TO OUT)						
MARK	SIZE	NO.	TYPE	LENGTH	A	B
C1	#4	1	I	1'-4"	6"	4"
C2				1'-8"	7"	6"
C3				1'-11"	8"	7"
C4				2'-3"	9"	9"
C5				2'-6"	10"	10"
C6		1	I	2'-10"	11"	1'-0"
B1		4	STRAIGHT	5'-8"	~	~
B2	#4	2	STRAIGHT	2'-0"	~	~



PLAN



ELEVATION

NOTES:

- ① REMOVE THE EXISTING SURFACE UNDER THE NEW TAPERED CONCRETE CURB AS APPROVED BY THE ENGINEER. EMBED THE TAPERED CONCRETE CURB A MINIMUM OF 4" BELOW THE GRADE MEASURED AT THE INSIDE FACE OF THE TAPER.
- ② ALL REINFORCING STEEL IS OF THE DEFORMED TYPE, MEETING THE REQUIREMENTS OF AASHTO M 31 (ASTM A 615, GRADE 60).
- ③ ALL CONCRETE IS CLASS "DD".  
TOTAL CONCRETE PER 6' TAPERED CURB EST. = 0.2 C.Y.  
TOTAL REBAR WEIGHT PER 6' TAPERED CURB EST. = 27 LB.
- ④ TAPERED CONCRETE CURB IS USED WITH BRIDGE APPROACH SECTION TYPE 3 (SEE DTL. DWG. NO. 606-24A AND 606-24B).
- ⑤ ADJUST DIMENSION TO MATCH EXISTING CURB.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-27
SECTION 606	
TAPERED CONCRETE CURB DETAIL	
EFFECTIVE: DECEMBER 2002	







TABLE 1:

BAYS	24" WIDTH MODEL NO.	30" WIDTH MODEL NO.	36" WIDTH MODEL NO.	SYSTEM LENGTH	EFFECTIVE LENGTH	PAD LENGTH	MAX DESIGN SPEED (M. P. H.)	NO. OF CARTRIDGES	
								TYPE I	TYPE II
1	OS2401*	OS3001*	OS3601*	7'-1"	5'-8"	9'-0"	25	2	0
2	OS2402*	OS3002*	OS3602*	10'-1"	8'-8"	9'-0"	37	2	1
3	OS2403*	OS3003*	OS3603*	13'-1"	11'-8"	12'-0"	44	3	1
4	OS2404*	OS3004*	OS3604*	16'-1"	14'-8"	15'-0"	50	3	2
5	OS2405*	OS3005*	OS3605*	19'-1"	17'-8"	18'-0"	56	4	2
6	OS2406*	OS3006*	OS3606*	22'-1"	20'-8"	21'-0"	62	4	3
7	OS2407*	OS3007*	OS3607*	25'-1"	23'-8"	24'-0"	65	4	4
8	OS2408*	OS3008*	OS3608*	28'-1"	26'-8"	27'-0"	68	4	5
9	OS2409*	OS3009*	OS3609*	31'-1"	29'-8"	30'-0"	71	4	6
10	OS2410*	OS3010*	OS3610*	34'-1"	32'-8"	33'-0"	75	5	6
11	OS2411*	OS3011*	OS3611*	37'-1"	35'-8"	36'-0"	75	5	7
12	OS2412*	OS3012*	OS3612*	40'-1"	38'-8"	39'-0"	75	5	8

\* G = GREY OR Y = YELLOW

NOTES:

- ATTACHMENT SHOWN IS TO SHAPES WITH RECTANGULAR CROSS SECTIONS SUCH AS: PIERS, PARAPETS AND MODIFIED CONCRETE BARRIER RAIL. TRAFFIC FLOW IS UNIDIRECTIONAL. ATTACHMENTS AND TRANSITIONS TO OTHER SHAPES, BARRIERS, RAILINGS AND BIDIRECTIONAL TRAFFIC FLOWS ARE AVAILABLE FROM THE MANUFACTURER.
- THE SYSTEM SHOWN INCLUDES THE TENSION STRUT BACKUP ASSEMBLY AND THE CONCRETE PAD AS DETAILED. SEE THE MANUFACTURER FOR DRAWINGS DETAILING THE REINFORCING STEEL FOR THE CONCRETE PAD AND FOR OTHER BACKUP & CONCRETE PAD OPTIONS.
- PROVIDE ADEQUATE CLEARANCE FOR THE DISTANCE SHOWN TO ALLOW FENDER PANELS TO SLIDE REARWARD UPON IMPACT.
- SEE MANUFACTURER FOR MORE INFORMATION ON SPECIFIC DESIGNS, INSTALLATION AND MAINTENANCE OF THE QUADGUARD SYSTEM.






TABLE 2:

ITEM	STOCK NO.	DESCRIPTION	REQ'D
1	2760051-0000	MONORAIL, ONE BAY	#
2	2760061-0000	MONORAIL, TWO BAYS	#
3	2760071-0000	MONORAIL, THREE BAYS	#
4	2760041-0000	MONORAIL END CAP	1
5	3525300-0000	ANCHOR KIT	#
6	2699571-0000	5/8" DIA. x 3 1/2" HEX BOLT	1
7	2704141-0000	5/8" DIA. HEX NUT	1
8	2708231-0000	5/8" DIA. LOCK WASHER	1


TABLE 3:

ASSEMBLY NO.	TOTAL RAIL LENGTH	# ITEM 1	# ITEM 2	# ITEM 3	# ITEM 5	NO. OF BAYS
3540060-0100	0"	0	0	0	0	1
3540060-0200	36.0"	1	0	0	2	2
3540060-0300	72.0"	0	1	0	3	3
3540060-0400	108.1"	0	0	1	4	4
3540060-0500	144.1"	1	0	1	5	5
3540060-0600	180.1"	0	1	1	6	6
3540060-0700	216.1"	0	0	2	7	7
3540060-0800	252.1"	1	0	2	8	8
3540060-0900	288.2"	0	1	2	9	9
3540060-1000	324.2"	0	0	3	10	10
3540060-1100	360.2"	1	0	3	12	11
3540060-1200	396.2"	0	1	3	13	12




DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-30A
IMPACT ATTENUATOR - QUADGUARD	
EFFECTIVE: DECEMBER 2002	
MONTANA DEPARTMENT OF TRANSPORTATION	







BILL OF MATERIAL		
PC	QTY	DESCRIPTION
* 970A	1	TRACC UNIT ASSEMBLY
3310G	4	5/8" DIA. LOCKWASHER
4451G	4	5/8" DIA. x 6" WEDGE EXP. ANCHOR
6707G	8	5/8" DIA. x 1" RND. HEAD STOVE BOLT
6708G	8	5/8" DIA. HEX NUT
6709G	8	5/8" DIA. FENDER WASHER (3/4" O.D.)
6825B	4	REFLECTIVE TAPE
6826B	1	PLASTIC NOSEPIECE
ANCHOR HARDWARE (CONCRETE BASE)		
6352G	27	5/8" DIA. x 7 1/2" THREADED ROD
3310G	27	5/8" DIA. LOCKWASHER
3361G	27	5/8" DIA. HEX NUT
3300G	27	5/8" DIA. FLAT WASHER
4747G	2	KELKEN EPOXY (QUART CAN)
ANCHOR HARDWARE (ASPHALT BASE)		
6380G	27	5/8" DIA. x 1'-6" THREADED ROD
3310G	27	5/8" DIA. LOCKWASHER
3361G	27	5/8" DIA. HEX NUT
3300G	27	5/8" DIA. FLAT WASHER
4747G	6	KELKEN EPOXY (QUART CAN)

\* SEE DET. DWG. NO. 606-31B




#### NOTES:

- ATTACHMENT SHOWN IS TO SHAPES WITH RECTANGULAR CROSS SECTIONS SUCH AS: PIERS, PARAPETS, AND MODIFIED CONCRETE BARRIER RAIL. TRAFFIC FLOW IS UNIDIRECTIONAL. ATTACHMENTS AND TRANSITIONS TO OTHER SHAPES, BARRIERS, RAILINGS AND BIDIRECTIONAL TRAFFIC FLOWS ARE AVAILABLE FROM THE MANUFACTURER.
- REINFORCEMENT DRAWINGS FOR THE CONCRETE PAD SHOWN, AS WELL AS OTHER PAD SIZES ARE AVAILABLE FROM THE MANUFACTURER.
- SEE MANUFACTURER FOR MORE INFORMATION ON SPECIFIC DESIGNS, INSTALLATION AND MAINTENANCE OF THE TRACC SYSTEM.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-30B
SECTION 606	
IMPACT ATTENUATOR - TRACC	
EFFECTIVE: DECEMBER 2002	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD






ITEM	STOCK NO.	DESCRIPTION	REQ'D
1	SEE TABLE A	DIAPHRAGM	1
8	2760091-0000	MONORAIL GUIDE	2
9	2704341-0000	3/4" DIA. HEX NUT	4
10	2699121-0000	3/4" DIA. x 2" HEX BOLT	4
11	2708201-0000	3/4" DIA. LOCK WASHER	4
12	2760292-0000	CARTRIDGE SUPPORT BRACKET	2

ASSEMBLY NO.	STOCK NO.	DESCRIPTION
3540071-0000	2761011-0000	24" WIDE DIAPHRAGM
3540072-0000	2761021-0000	30" WIDE DIAPHRAGM
3540073-0000	2761031-0000	36" WIDE DIAPHRAGM


DIAPHRAGM ASSEMBLY



ITEM	STOCK NO.	DESCRIPTION	REQ'D
1	3540130-0*00	NOSE, W/ SUPPORT BRACKET	1
2	2699341-0000	5/8" DIA. x 2" RAIL BOLT	6
3	2704191-0000	5/8" DIA. HEX NUT	6
4	2708871-0000	WASHER (BAR 1/8" x 1 1/4" x 2", W/ 5/8" DIA. HOLE)	6
5	2760251-0000	PULL-OUT BRACKET	2

\* 0 INDICATES GRAY  
\* 1 INDICATES YELLOW

NOSE ASSEMBLY  
ASSEMBLY NO. 3540050-0100 (YELLOW)  
ASSEMBLY NO. 3540050-0000 (GRAY)




ITEM	STOCK NO.	DESCRIPTION	REQ'D
1	2760081-0000	FENDER PANEL	1
2	2699341-0000	5/8" DIA. x 2" RAIL BOLT	2
3	2704191-0000	5/8" DIA. HEX NUT	2
4	2708841-0000	CAST MUSHROOM WASHER	1
5	2706604-0000	5/8" DIA. x 5" SCREW	1
6	2704141-0000	5/8" DIA. HEX NUT	1
7	2708291-0000	5/8" DIA. WASHER	4
8	2021611-0000	ELASTOMERIC BUSHING	1

NOTE:

- ① UNDERLYING PANEL IS EITHER ANOTHER FENDER PANEL OR, IN THE CASE OF THE LAST FENDER PANEL IT COULD BE A BACKUP SIDE PANEL, EXTENSION PANEL OR TRANSITION PANEL.
- ② TWO FENDER PANEL ASSEMBLIES ARE REQUIRED PER BAY.

FENDER PANEL ASSEMBLY  
ASSEMBLY NO. 3540040-0000



ITEM	STOCK NO.	DESCRIPTION	REQ'D
1	SEE TABLE A	TENSION BACKUP	1
2	2760141-0000	SIDE PANEL	2
9	3525300-0000	ANCHOR KIT	3
10	2704191-0000	5/8" DIA. HEX NUT	4
11	2699341-0000	5/8" DIA. x 2" RAIL BOLT	4
12	2760293-0000	CARTRIDGE SUPPORT BRACKET	1
13	2760294-0000	CARTRIDGE SUPPORT LOCKING BAR	1

ASSEMBLY NO.	STOCK NO.	DESCRIPTION
3540031-0000	2760011-0000	24" WIDE TENSION BACKUP
3540032-0000	2760021-0000	30" WIDE TENSION BACKUP
3540033-0000	2760031-0000	36" WIDE TENSION BACKUP






NOTE:

- ③ WHEN TRANSITIONING THE QUADGUARD SYSTEM TO EXISTING BARRIERS, SEE MANUFACTURER FOR PROPER USE OF SIDE PANEL (ITEM 2).

BACKUP ASSEMBLY

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-31A
SECTION 606	
IMPACT ATTENUATOR - QUADGUARD ASSEMBLY DETAILS	
EFFECTIVE: DECEMBER 2002	










BILL OF MATERIAL		
PC	QTY	DESCRIPTION
33325A	2	BASE ASSEMBLY
33326G	1	54" RIP PLATE 1
33327G	1	60" RIP PLATE 2
33328G	1	69" RIP PLATE 3
33329G	1	75" RIP PLATE 4
33330G	2	93" RIP PLATE 5
33331G	2	87" RIP PLATE 6
33332G	2	20' BEAM GUIDE
33333A	1	END SHOE (LEFT)
33334A	1	END SHOE (RIGHT)
33335A	1	SLED WELDMENT
33336A	1	CUTTER
33337A	4	ONE-BAY FENDER PANEL
33338A	16	TWO-BAY FENDER PANEL
33339A	7	FRAME WELDMENT
33340A	1	BACKUP FRAME WELDMENT
33341A	32	SLOT PLATE
33342A	1	EXTRA CROSSTIE
33343A	4	9' FORMED CHANNEL
3340G	32	5/8" DIA. HGR NUT
3361G	42	5/8" DIA. HEX NUT
3391G	32	5/8" DIA. x 1 3/4" HEX HEAD BOLT
3400G	16	5/8" DIA. x 2" HGR BOLT
3435G	16	5/8" DIA. x 3 1/2" HGR BOLT
3704G	9	3/4" DIA. HEX NUT
3718G	9	3/4" DIA. x 3" HEX HEAD BOLT
4258G	294	3/8" DIA. LOCKWASHER
4261G	6	3/8" DIA. x 1 1/2" HEX HEAD BOLT
4372G	84	5/8" DIA. FLAT WASHER
5306G	10	5/8" DIA. x 2 1/4" HEX HEAD BOLT
6322G	140	3/8" DIA. x 4" HEX HEAD BOLT
6323G	148	3/8" DIA. x 4 1/2" HEX HEAD BOLT
6405G	294	3/8" DIA. HEAVY HEX NUT

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-31B
IMPACT ATTENUATOR - TRACC ASSEMBLY DETAILS	
EFFECTIVE: DECEMBER 2002	
MONTANA DEPARTMENT OF TRANSPORTATION	MONTANA CADD







SPLICE CABLE USING A COUPLING DEVICE AS SHOWN, OR AN ALTERNATE METHOD APPROVED BY THE ENGINEER.



NOTE:  
REFLECTORS ARE TO BE 14 GAGE ALUMINUM ALLOY





#### NOTES:



- ① FOR CABLE GUARDRAIL RUNS OF:  
1044 FEET OR LESS: USE COMPENSATING CABLE END ASSEMBLY (RCE01\*) ON ONE END AND TURNBUCKLE CABLE END ASSEMBLY \* ON THE OTHER END OF EACH CABLE.  
GREATER THAN 1044 FEET, UP TO 2052 FEET MAXIMUM: USE COMPENSATING CABLE END ASSEMBLY (RCE01\*) ON BOTH ENDS OF EACH CABLE.
  - ② LINE POST SPACING:  
TANGENTS AND CURVES OF LESS THAN 8 DEGREES: 16 FEET.  
CURVES GREATER THAN 8 DEGREES UP TO 13 DEGREES: 12 FEET.  
NOTE: DO NOT INSTALL CABLE GUARDRAIL ON THE INSIDE SHOULDER OF ANY CURVE.
  - ③ UNIFORMLY TENSION ALL CABLES TO COMPRESS SPRINGS BY 3 1/2".
  - ④ DO NOT INSTALL CABLE GUARDRAIL FOR OBSTACLES WITHIN 12 FEET OF THE INSTALLATION LINE.
  - ⑤ DO NOT USE CABLE GUARDRAIL WITH FILL SLOPES STEEPER THAN 2:1, UNLESS THE DISTANCE BETWEEN THE BACK OF THE POSTS AND THE BREAK IN THE FILL SLOPE IS AT LEAST 8 FEET.
  - ⑥ ATTACH REFLECTORS TO EVERY OTHER LINE POST (32 FEET TYP.), BEGINNING AT POST P3. DO NOT ATTACH REFLECTORS TO POSTS P1 AND P2.
  - ⑦ WIDENING IS REQUIRED IF FINISHED SHOULDER IS LESS THAN 2'-0" FROM THE TRAFFIC LANE.
- \* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-40
SECTION 606	
CABLE GUARDRAIL	
EFFECTIVE: DECEMBER 2002	
MONTANA DEPARTMENT OF TRANSPORTATION	MONTANA CADD






ANCHOR UNIT & RE-BAR INSTALLATION DETAILS



ANCHOR POST DETAIL



CABLE END ASSEMBLY TO ANCHOR BRACKET DETAIL

NOTE:

INSTALL ONE WASHER UNDER HEAD, ONE BETWEEN PLATES & ONE UNDER NUT. AN ADDITIONAL WASHER MAY BE PLACED BETWEEN PLATES TO PLUMB THE ANCHOR POST.


NOTES:

1. INSTALL THE CONCRETE ANCHOR INTO THE EXCAVATION, AS DETAILED, SO THAT THE BOTTOM OF THE ANCHOR HAS A FULL AND EVEN BEARING ON THE SURFACE UNDER IT. BACKFILL AROUND THE CONCRETE ANCHOR IN ACCORDANCE WITH SECTION 203.03.3 OF THE STANDARD SPECIFICATIONS.
2. THE CONCRETE ANCHOR CAN BE PLACED AS ONE OR TWO PIECES. THIS DETAIL PRIMARILY SHOWS A TWO PIECE INSTALLATION. FOR ONE PIECE INSTALLATIONS, USE ALL THE SAME DIMENSIONS, LESS THE TAPERED KEYWAY AND THE ADDITIONAL REBAR, AS SHOWN.
3. IF LIFTING DEVICES ARE EMBEDDED INTO THE CONCRETE ANCHORS, INSURE THAT THEY HAVE A SAFE WORKING LOAD OF 4 TONS FOR THE ONE PIECE ANCHOR AND 2 TONS EACH FOR EACH OF THE HALVES OF THE TWO PIECE ANCHOR UNIT.
4. USE CLASS "DD" CONCRETE TO CONSTRUCT ANCHOR.


\*SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

NOTE:


DIMENSIONS FOR LEFT AND RIGHT HAND ANCHOR UNITS ARE THE SAME, WITH THE POSITION OF THE ANCHOR POST AND ANCHOR BRACKET BEING THE ONLY DIFFERENCE.




PLAN  
(LEFT HAND ANCHOR UNIT)



PLAN  
(RIGHT HAND ANCHOR UNIT)






ELEVATION  
(LEFT HAND ANCHOR UNIT)

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-41
SECTION 606	
CABLE GUARDRAIL TERMINAL ANCHOR ASSEMBLY	
EFFECTIVE: JUNE 2003	
	











- NOTES:
- ① USE BOX BEAM RAIL IN MINIMUM NOMINAL LENGTHS OF 18 FEET UNLESS APPROVED BY THE ENGINEER.
- ② INSTALL EXPANSION JOINTS ON ALL BOX BEAM GUARDRAIL INSTALLATIONS GREATER THAN 300 FEET IN LENGTH AT INTERVALS NOT TO EXCEED 500 FEET.
- ③ ATTACH REFLECTIVE TABS TO EVERY FOURTH POST (24 FEET TYP. ON ANGLE TABS SLIGHTLY TOWARDS TRAFFIC. DO NOT USE REFLECTIVE TABS ON WY-BET TERMINALS. WY-BET TERMINALS RECEIVE REFLECTIVE CHANNELS.
- ④ DO NOT INSTALL BOX BEAM GUARDRAIL FOR OBSTACLES WITHIN 5 FEET OF THE BACK OF THE RAIL.
- ⑤ WIDENING IS REQUIRED IF FINISHED SHOULDER IS LESS THAN 2' -0" FROM THE TRAFFIC LANE.
- \* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.




**MONTANA DEPARTMENT OF TRANSPORTATION**  
 EFFECTIVE: JANUARY 2004







NOTES:

① SEE DTL. DWG. NO. 606-50 FOR  
STANDARD BOX BEAM GUARDRAIL  
AND ASSOCIATED DETAILS.

\* SEE DTL. DWG. NO. 606-80 FOR  
SCHEDULE OF GUARDRAIL HARDWARE.





DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-52
SECTION 606	
BOX BEAM ONE-WAY DEPARTURE TERMINAL SECTION	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION	
 MONTANA CADD	





BOX BEAM - BRIDGE APPROACH SECTION TYPE 1

BOX BEAM - BRIDGE APPROACH SECTION TYPE 2




- NOTES:
- ① WIDENING IS REQUIRED IF FINISHED SHOULDER IS LESS THAN 2'-0" FROM THE TRAFFIC LANE.
  - ② SEE DTL. DWG. NO. 606-50 FOR STANDARD BOX BEAM GUARDRAIL AND ASSOCIATED DETAILS.
  - \* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.
  - # SEE BRIDGE PLANS.


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-53
BOX BEAM BRIDGE APPROACH SECTIONS	
EFFECTIVE: JANUARY 2004	




This Frame left blank








PLAN



ELEVATION





NOTES:

- ① PLACE A SELF-ADHESIVE OBJECT MARKER ON THE FACE OF THE NOSE ASSEMBLY, HAVING ALTERNATING RETRO-REFLECTIVE BLACK AND YELLOW STRIPES SLOPED DOWNWARD AT AN ANGLE OF 45° TOWARDS THE SIDE ON WHICH TRAFFIC IS TO PASS.
- ② FLARE THE END SECTION AWAY FROM TRAFFIC AT A RATE OF 50:1 FOR 50 FEET (ILLUSTRATED). FLARES OF 50:1 FOR 100 FEET MAY ALSO BE USED. THE FLARE MAY BE OMITTED ON ROADS WITH SHOULDERS GREATER THAN 2 FEET IN WIDTH.


- ③ OBTAIN ENGINEERS APPROVAL OF MANUFACTURER INSTALLATION OPTIONS WHEN SITE CONDITIONS PREVENT THE USE OF THE OPTION SHOWN ON THIS DETAIL.

- ④ SEE DTL. DWG. NO. 606-50 FOR STANDARD BOX BEAM GUARDRAIL AND ASSOCIATED DETAILS.


GUARDRAIL WIDENING

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-55A
SECTION 606	
OPTIONAL BOX BEAM TERMINAL SECTION - WY-BET	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD






PLAN



ELEVATION





GUARDRAIL WIDENING


NOTES:

- ① PLACE A SELF-ADHESIVE OBJECT MARKER ON THE FACE OF THE NOSE ASSEMBLY, HAVING ALTERNATING RETRO-REFLECTIVE BLACK AND YELLOW STRIPES SLOPED DOWNWARD AT AN ANGLE OF 45° TOWARDS THE SIDE ON WHICH TRAFFIC IS TO PASS.
- ② FLARE THE END SECTION AWAY FROM TRAFFIC AT A RATE OF 50:1 FOR 50 FEET (ILLUSTRATED). FLARES OF 50:1 FOR 100 FEET MAY ALSO BE USED. THE FLARE MAY BE OMITTED ON ROADS WITH SHOULDERS GREATER THAN 2 FEET IN WIDTH.


- ③ OBTAIN ENGINEERS APPROVAL OF MANUFACTURER INSTALLATION OPTIONS WHEN SITE CONDITIONS PREVENT THE USE OF THE OPTION SHOWN ON THIS DETAIL.
- ④ SEE DTL. DWG. NO. 606-50 FOR STANDARD BOX BEAM GUARDRAIL AND ASSOCIATED DETAILS.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-55B
SECTION 606	
OPTIONAL BOX BEAM TERMINAL SECTION - BEAT	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD







POST ATTACHMENT DETAIL  
(TYP. AT POSTS P6, P7 AND P8)




POST ATTACHMENT DETAIL  
(POST P5)



POST ATTACHMENT DETAIL  
(TYP. AT POSTS P2, P3 AND P4)




END ANCHORAGE ASSEMBLY




SECTION A-A

BILL OF MATERIAL		
PC	QTY	DESCRIPTION
706G	1	PIPE SLEEVE, 2" DIA. x 6"
721G	1	PLATE WASHER, 3" x 4" x 3/8"
722G	1	NOSE RESTRAINT CABLE BRACKET
736G	2	STEEL TUBE, 6" x 8" x 5'-0"
766G	2	SOIL PLATE, 18" x 24" x 1/4"
774A	1	SLOTTED BEARING PLATE
3000G	1	CABLE ASSEMBLY
3148G	2	1/4" DIA. x 2" LAG SCREW
3240G	3	5/16" DIA. ROUND WASHER
3245G	3	5/16" DIA. HEX NUT
3254G	3	3/8" DIA. x 1 1/2" LAG SCREW
3255G	5	3/8" DIA. ROUND WASHER
3264G	2	3/8" DIA. x 5" LAG SCREW
3350G	4	5/8" DIA. HEX NUT
3478G	4	5/8" DIA. x 7 1/2" HEX BOLT
3700G	4	3/4" DIA. ROUND WASHER
3710G	2	3/4" DIA. HEX NUT
4044G	4	1 1/4" DIA. HEX NUT
4066B	1	WOOD POST, 6" x 8" x 3'-6 1/2"
4106B	3	RUBBER PAD, 1 1/2" x 3 1/2" x 4"
4192G	4	1/4" CABLE CLAMP
4300G	18	1/2" DIA. ROUND WASHER
4303G	9	1/2" DIA. HEX NUT
4308G	9	1/2" DIA. x 1 1/2" HEX BOLT
4719G	2	3/4" DIA. x 10" HEX BOLT
4902G	2	1" DIA. ROUND WASHER
4903G	4	1" DIA. HEX NUT
5044G	1	AIRCRAFT CABLE, 1/4" DIA. x 6'-10"
5092G	2	1/4" AIRCRAFT CABLE THIMBLE
5188G	3	5/16" DIA. x 7 1/2" HEX BOLT
5423G	1	1 1/4" DIA. x 36" ALL THREAD ROD
9640G	3	POST ANGLE, 5" x 3 1/2" x 3/8" x 4 1/2"
9641G	3	SHELF ANGLE, 4 1/2" x 1/8" x 1'-7 1/8"
9642G	1	SHELF ANGLE, 4 1/2" x 1/8" x 11 1/8"
9852A	1	STRUT AND YOKE ASSEMBLY
14959A	1	5'-4" STEEL POST
32300A	1	WY-BET NOSE ASSEMBLY
32301A	1	HSS 6" x 6" x 10" INTERMEDIATE SPACER
32305A	1	BREAKAWAY TENSILE CONNECTOR
32306A	1	HSS 6" x 6" x 3/16" TELESOPING SECTION
32307A	1	OUTER TUBE
32309B	1	6" O.D. x 1/4" x 12'-7 3/8" COMPOSITE TUBE
32310B	1	6" O.D. x 1/8" x 5'-11 1/8" COMPOSITE TUBE
32312G	3	REFLECTOR CHANNEL
32515A	6	5'-4" STEEL POST

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-56A
SECTION 606	
WY-BET BOX BEAM TERMINAL SECTION DETAILS	
EFFECTIVE: DECEMBER 2002	
	




This Frame left blank




BILL OF MATERIAL	
ITEM	QTY DESCRIPTION
A	1 LOWER FIRST POST, W6x15, 8'-0" LG.
B	1 UPPER FIRST POST, W6x9, 1'-9 1/2" LG.
C	1 SUPPORT BRACKET, 10 GAGE BENT PLATE
D	1 POST BREAKER
E	1 END TUBE RAIL, TS 6" x 6" x 1/8" x 12'-0"
F	1 CABLE ASSEMBLY
G	1 BEARING PLATE
H	1 BOX BEAM HEAD
I	1 RAIL SUPPORT BRACKET, L 5" x 3 1/2" x 3/8" x 4 1/2"
J	1 BOX BEAM POST W/ SOIL PLATE
K	2 END TUBE SECTION TIE PLATE
a	2 5/16" DIA. x 7/2" HEX BOLT (GRADE 5)
b	1 1/4" DIA. x 3" HEX BOLT (GRADE 2)
c	2 1/2" DIA. x 2" HEX BOLT (GRADE 2)
d	8 5/8" DIA. x 2" HEX BOLT (GRADE 5)
e	1 5/8" DIA. x 8" HEX BOLT (GRADE 5)
f	1 5/8" DIA. x 3" HEX BOLT (GRADE 5)
g	2 3/16" DIA. HEX NUT
h	1 1/4" DIA. HEX NUT
j	2 1/2" DIA. HEX NUT
k	14 5/8" DIA. HEX NUT
n	2 1" DIA. ANCHOR CABLE HEX NUT
p	4 5/16" DIA. WASHER
q	1 1/4" DIA. WASHER
r	3 1/2" DIA. WASHER
s	10 3/8" DIA. WASHER
u	2 1" DIA. ANCHOR CABLE WASHER

NOTE:  
① BEAT TERMINAL SECTION TO INCLUDE 36'-0" OF BOX BEAM GUARDRAIL AS SHOWN ON DTL. DWG. NO. 606-55B.


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-56B
BEAT BOX BEAM TERMINAL SECTION DETAILS	
EFFECTIVE: DECEMBER 2002	
 MONTANA DEPARTMENT OF TRANSPORTATION	





#### LOOP FABRICATION REQUIREMENTS:

- USE REINFORCING STEEL CONFORMING TO ASTM A706, GRADE 60 FOR REBAR BEING WELDED TO LOOPS.
- LOOP ENDS CONSIST OF SMOOTH ROUND BARS CONFORMING TO AASHTO M270, GRADE 36.
- COLD BEND THE LOOPS BY USING A JIG THAT WILL PRODUCE AN ACCURATE RADIUS WITHOUT MARRING THE BAR. DO NOT HEAT THE BAR TO FACILITATE BENDING.
- WELD REBAR TO LOOPS USING 1/8" DIA. E8018 ROD. DO NOT TACK WELD THE PIECES TOGETHER PRIOR TO WELDING.
- WELDER MUST BE CERTIFIED IN ACCORDANCE WITH THE CURRENT EDITION OF AWS D1.4. DO NOT PLACE THE WELDED ASSEMBLY IN THE FORM UNTIL IT HAS BEEN INSPECTED.



#### NOTES:


- USE CLASS "DD" CONCRETE OR EQUIVALENT.
  - REINFORCING STEEL CONSISTS OF DEFORMED BARS CONFORMING TO AASHTO M31, GRADE 60.
  - CONNECT EACH 10' SECTION WITH CONNECTING PINS AS DETAILED AND CONFORMING TO AASHTO M270, GRADE 36 OR BETTER. CONNECTING PINS NEED NOT BE PAINTED.
  - CUTOUPS ON ENDS OF EACH SECTION ARE SHOWN WITH SLIGHT TAPER TO FACILITATE FORM REMOVAL. RECTANGULAR CUTOUPS ARE ACCEPTABLE.
  - THE CONTRACTOR IS RESPONSIBLE FOR THE PROPER FIT-UP OF THE PRECAST CONCRETE BARRIER RAIL ASSEMBLY AND PIN SUFFICIENT NUMBER OF PRECAST SECTIONS IN THE FABRICATIONS PLANT TO DETERMINE THAT PROPER FIT-UP CAN BE MAINTAINED ON ALL ROADWAY ALIGNMENT, CURVES AS WELL AS ON TANGENT. THIS IS TO BE DETERMINED EARLY IN FABRICATION.
  - ATTACH REFLECTORS TO RAIL EVERY 30'. FOLLOW THE MANUFACTURER'S SPECIFICATIONS FOR ADHESIVE MOUNTING. IN NARROW PAVED (FLUSH) MEDIAN APPLICATIONS, REFLECTORIZE BOTH SIDES.
- \* 3/4" CHAMFER ENTIRE OPENING (OR SUFFICIENTLY ROUNDED SO THAT A SMOOTH EDGE RESULTS.) 1/2" CHAMFER IS ACCEPTABLE.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-60
SECTION 554, 606	
CONCRETE BARRIER RAIL	
EFFECTIVE: JANUARY 2004	












END VIEW




CONNECTING PIN DETAIL




END VIEW




LOOP DETAIL




ELEVATION VIEW




ELEVATION VIEW




END VIEW



REBAR DETAIL



REFLECTOR  
(SEE NOTES)



#### NOTES:

- USE CLASS "DD" CONCRETE OR EQUIVALENT.
- REINFORCING STEEL CONSISTS OF DEFORMED BARS CONFORMING TO AASHTO M31, GRADE 60.
- CONNECT EACH 10' SECTION WITH CONNECTING PINS AS DETAILED AND CONFORMING TO AASHTO M270, GRADE 36 OR BETTER. CONNECTING PINS NEED NOT BE PAINTED.
- CUTOUTS ON ENDS OF EACH SECTION ARE SHOWN WITH SLIGHT TAPER TO FACILITATE FORM REMOVAL. RECTANGULAR CUTOUTS ARE ACCEPTABLE.
- THE CONTRACTOR IS RESPONSIBLE FOR THE PROPER FIT-UP OF THE PRECAST CONCRETE BARRIER RAIL. ASSEMBLE AND PIN SUFFICIENT NUMBER OF PRECAST SECTIONS IN THE FABRICATIONS PLANT TO DETERMINE THAT PROPER FIT-UP CAN BE MAINTAINED ON ALL ROADWAY ALIGNMENT, CURVES AS WELL AS ON TANGENT. THIS IS TO BE DETERMINED EARLY IN FABRICATION.
- ATTACH REFLECTORS TO RAIL EVERY 30'. FOLLOW THE MANUFACTURER'S SPECIFICATIONS FOR ADHESIVE MOUNTING. IN NARROW PAVED (FLUSH) MEDIAN APPLICATIONS, REFLECTORIZE BOTH SIDES.


\* 3/4" CHAMFER ENTIRE OPENING (OR SUFFICIENTLY ROUNDED SO THAT A SMOOTH EDGE RESULTS.) 1/2" CHAMFER IS ACCEPTABLE.

#### LOOP FABRICATION REQUIREMENTS:


- USE REINFORCING STEEL CONFORMING TO ASTM A706, GRADE 60 FOR REBAR BEING WELDED TO LOOPS.
- LOOP ENDS CONSIST OF SMOOTH ROUND BARS CONFORMING TO AASHTO M270, GRADE 36.
- COLD BEND THE LOOPS BY USING A JIG THAT WILL PRODUCE AN ACCURATE RADIUS WITHOUT MARRING THE BAR. DO NOT HEAT THE BAR TO FACILITATE BENDING.
- WELD REBAR TO LOOPS USING 1/8" DIA. E8018 ROD. DO NOT TACK WELD THE PIECES TOGETHER PRIOR TO WELDING.
- WELDER MUST BE CERTIFIED IN ACCORDANCE WITH THE CURRENT EDITION OF AWS D1.4. DO NOT PLACE THE WELDED ASSEMBLY IN THE FORM UNTIL IT HAS BEEN INSPECTED.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-64
SECTION 554, 606	
TALL CONCRETE BARRIER RAIL	
EFFECTIVE: JANUARY 2004	







END VIEW




CONNECTING PIN DETAIL



END VIEW



LOOP DETAIL




ELEVATION VIEW

PLAN VIEW


ELEVATION VIEW

LOOP FABRICATION REQUIREMENTS:


1. USE REINFORCING STEEL CONFORMING TO ASTM A706, GRADE 60 FOR REBAR BEING WELDED TO LOOPS.
2. LOOP ENDS CONSIST OF SMOOTH ROUND BARS CONFORMING TO AASHTO M270, GRADE 36.
3. COLD BEND THE LOOPS BY USING A JIG THAT WILL PRODUCE AN ACCURATE RADIUS WITHOUT MARRING THE BAR. DO NOT HEAT THE BAR TO FACILITATE BENDING.
4. WELD REBAR TO LOOPS USING 1/8" DIA. E8018 ROD. DO NOT TACK WELD THE PIECES TOGETHER PRIOR TO WELDING.
5. WELDER MUST BE CERTIFIED IN ACCORDANCE WITH THE CURRENT EDITION OF AWS D1.4. DO NOT PLACE THE WELDED ASSEMBLY IN THE FORM UNTIL IT HAS BEEN INSPECTED.




END VIEW



REBAR DETAIL



REFLECTOR  
(SEE NOTES)



NOTES:





- ① USE CLASS "DD" CONCRETE OR EQUIVALENT.
- ② REINFORCING STEEL CONSISTS OF DEFORMED BARS CONFORMING TO AASHTO M31, GRADE 60.
- ③ CONNECT EACH 10' SECTION WITH CONNECTING PINS AS DETAILED AND CONFORMING TO AASHTO M270, GRADE 36 OR BETTER. CONNECTING PINS NEED NOT BE PAINTED.
- ④ CUTOUTS ON ENDS OF EACH SECTION ARE SHOWN WITH SLIGHT TAPER TO FACILITATE FORM REMOVAL. RECTANGULAR CUTOUTS ARE ACCEPTABLE.
- ⑤ THE CONTRACTOR IS RESPONSIBLE FOR THE PROPER FIT-UP OF THE PRECAST CONCRETE BARRIER RAIL. ASSEMBLE AND PIN SUFFICIENT NUMBER OF PRECAST SECTIONS IN THE FABRICATIONS PLANT TO DETERMINE THAT PROPER FIT-UP CAN BE MAINTAINED ON ALL ROADWAY ALIGNMENT, CURVES AS WELL AS ON TANGENT. THIS IS TO BE DETERMINED EARLY IN FABRICATION.
- ⑥ ATTACH REFLECTORS TO RAIL EVERY 30'. FOLLOW THE MANUFACTURER'S SPECIFICATIONS FOR ADHESIVE MOUNTING. IN NARROW PAVED (FLUSH) MEDIAN APPLICATIONS, REFLECTORIZE BOTH SIDES.

\* 3/4" CHAMFER ENTIRE OPENING (OR SUFFICIENTLY ROUNDED SO THAT A SMOOTH EDGE RESULTS.) 1/2" CHAMFER IS ACCEPTABLE.


\*\* USE THIS RAIL ON A CASE BY CASE BASIS AS SPECIFIED IN PLANS.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-65
SECTION 554, 606	
ALTERNATE TALL CONCRETE BARRIER RAIL	
EFFECTIVE: JANUARY 2004	







NOTE:  
LEFT AND RIGHT REBAR DETAILS ARE FOR NORMAL TALL AND REGULAR CONCRETE BARRIER RAIL SECTIONS. TAPER REBAR HEIGHT AND WIDTH AS NEEDED BY MAINTAINING THE VERTICAL POSITION FROM THE BOTTOM AND THE 1/2" CLEARANCE AT ALL LOCATIONS.



#### LOOP FABRICATION REQUIREMENTS:


1. USE REINFORCING STEEL CONFORMING TO ASTM A706, GRADE 60 FOR REBAR BEING WELDED TO LOOPS.
2. LOOP ENDS CONSIST OF SMOOTH ROUND BARS CONFORMING TO AASHTO M270, GRADE 36.
3. COLD BEND THE LOOPS BY USING A JIG THAT WILL PRODUCE AN ACCURATE RADIUS WITHOUT MARRING THE BAR. DO NOT HEAT THE BAR TO FACILITATE BENDING.
4. WELD REBAR TO LOOPS USING 1/8" DIA. E8018 ROD. DO NOT TACK WELD THE PIECES TOGETHER PRIOR TO WELDING.
5. WELDER MUST BE CERTIFIED IN ACCORDANCE WITH THE CURRENT EDITION OF AWS D1.4. DO NOT PLACE THE WELDED ASSEMBLY IN THE FORM UNTIL IT HAS BEEN INSPECTED.





#### NOTES:


- ① USE CLASS "DD" CONCRETE OR EQUIVALENT.
- ② REINFORCING STEEL CONSISTS OF DEFORMED BARS CONFORMING TO AASHTO M31, GRADE 60.
- ③ CONNECT EACH 10' SECTION WITH CONNECTING PINS AS DETAILED AND CONFORMING TO AASHTO M270, GRADE 36 OR BETTER. CONNECTING PINS NEED NOT BE PAINTED.
- ④ CUTOUTS ON ENDS OF EACH SECTION ARE SHOWN WITH SLIGHT TAPER TO FACILITATE FORM REMOVAL. RECTANGULAR CUTOUTS ARE ACCEPTABLE.
- ⑤ THE CONTRACTOR IS RESPONSIBLE FOR THE PROPER FIT-UP OF THE PRECAST CONCRETE BARRIER RAIL. ASSEMBLY AND PIN SUFFICIENT NUMBER OF PRECAST SECTIONS IN THE FABRICATIONS PLANT TO DETERMINE THAT PROPER FIT-UP CAN BE MAINTAINED ON ALL ROADWAY ALIGNMENT, CURVES AS WELL AS ON TANGENT. THIS IS TO BE DETERMINED EARLY IN FABRICATION.
- ⑥ ATTACH REFLECTORS TO RAIL EVERY 30'. FOLLOW THE MANUFACTURER'S SPECIFICATIONS FOR ADHESIVE MOUNTING. IN NARROW PAVED (FLUSH) MEDIAN APPLICATIONS, REFLECTORIZE BOTH SIDES.
- ⑦ SEE DETAILED DRAWINGS 606-60 AND 606-64 FOR INFORMATION ON THE ADJACENT CONCRETE BARRIER RAIL SECTIONS.

\* 3/4" CHAMFER ENTIRE OPENING (OR SUFFICIENTLY ROUNDED SO THAT A SMOOTH EDGE RESULTS.) 1/2" CHAMFER IS ACCEPTABLE.




DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-66
SECTION 544, 606	
CONCRETE BARRIER RAIL TRANSITION	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD






LEFT END VIEW




ELEVATION VIEW




RIGHT END VIEW

NOTE:


REBAR TYPICAL AT LEFT END ONLY. TAPER THE REBAR HEIGHT AS NEEDED, BY MAINTAINING THE VERTICAL POSITION FROM THE BOTTOM AND THE 1/2" CLEARANCE AT ALL LOCATIONS.



REBAR DETAIL LEFT END



LEFT END VIEW




ELEVATION VIEW


NOTES:

- ① USE CLASS "DD" CONCRETE OR EQUIVALENT.
- ② REINFORCING STEEL CONSISTS OF DEFORMED BARS CONFORMING TO AASHTO M31, GRADE 60.
- ③ CONNECT EACH 10' SECTION WITH CONNECTING PINS AS DETAILED AND CONFORMING TO AASHTO M270, GRADE 36 OR BETTER. CONNECTING PINS NEED NOT BE PAINTED.
- ④ CUTOUTS ON LEFT END OF EACH SECTION ARE SHOWN WITH SLIGHT TAPER TO FACILITATE FORM REMOVAL. RECTANGULAR CUTOUTS ARE ACCEPTABLE.
- ⑤ THE CONTRACTOR IS RESPONSIBLE FOR THE PROPER FIT-UP OF THE PRECAST CONCRETE BARRIER RAIL. ASSEMBLE AND PIN SUFFICIENT NUMBER OF PRECAST SECTIONS IN THE FABRICATIONS PLANT TO DETERMINE THAT PROPER FIT-UP CAN BE MAINTAINED ON ALL ROADWAY ALIGNMENT, CURVES AS WELL AS ON TANGENT. THIS IS TO BE DETERMINED EARLY IN FABRICATION.
- ⑥ SEE DTL. DWG. NO. 606-60 FOR INFORMATION ON THE ADJACENT CONCRETE BARRIER RAIL SECTION.

\* 3/4" CHAMFER ENTIRE OPENING (OR SUFFICIENTLY ROUNDED SO THAT A SMOOTH EDGE RESULTS.) 1/2" CHAMFER IS ACCEPTABLE.




CONNECTING PIN DETAIL



ISOMETRIC VIEW

LOOP FABRICATION REQUIREMENTS:

1. USE REINFORCING STEEL CONFORMING TO ASTM A706, GRADE 60 FOR REBAR BEING WELDED TO LOOPS.
2. LOOP ENDS CONSIST OF SMOOTH ROUND BARS CONFORMING TO AASHTO M270, GRADE 36.
3. COLD BEND THE LOOPS BY USING A JIG THAT WILL PRODUCE AN ACCURATE RADIUS WITHOUT MARRING THE BAR. DO NOT HEAT THE BAR TO FACILITATE BENDING.
4. WELD REBAR TO LOOPS USING 1/8" DIA. E8018 ROD. DO NOT TACK WELD THE PIECES TOGETHER PRIOR TO WELDING.
5. WELDER MUST BE CERTIFIED IN ACCORDANCE WITH THE CURRENT EDITION OF AWS D1.4. DO NOT PLACE THE WELDED ASSEMBLY IN THE FORM UNTIL IT HAS BEEN INSPECTED.



LOOP DETAIL

DETAILED DRAWING	
REFERENCE	DWG. NO.
SECTION 554, 606	606-68
CONCRETE BARRIER RAIL TERMINAL SECTION (ONE-WAY DEPARTURE)	
EFFECTIVE: JANUARY 2004	



SCHEDULE OF GUARDRAIL HARDWARE			
DESIGNATION ①	DESCRIPTION	DTL. DWG. NO. (606-###)	GUARDRAIL TYPE ②
FBB01-05	5/8" DIA. GUARDRAIL BOLT AND RECESS NUT	82	W
FBH01	5/16" DIA. HOOK BOLT	92	C
FBH02	5/16" DIA. ALTERNATE HOOK BOLT	92	C
FBX10a	3/8" DIA. HEX BOLT	82	B
FBX12a	1/2" DIA. HEX BOLT	82	B, C
FBX16a	5/8" DIA. HEX BOLT	82	W
FBX20a	3/4" DIA. HEX BOLT	82	W
FBX20b	3/4" DIA. HIGH STRENGTH HEX BOLT	82	B
FCA01	CABLE ASSEMBLY	84	W
FMM01	CABLE WEDGE	94	C
FMM02	POST SLEEVE	84	W
FNS20	3/4" DIA. SQUARE NUT	82	C
FNX08a	5/16" DIA. HEX NUT	82	C
FNX10a	3/8" DIA. HEX NUT	82	B
FNX12a	1/2" DIA. HEX NUT	82	B, C
FNX16a	5/8" DIA. HEX NUT	82	W
FNX20a	3/4" DIA. HEX NUT	82	C, W
FNX20b	3/4" DIA. HIGH STRENGTH HEX NUT	82	B
FNX24a	1" DIA. HEX NUT	82	W
FPA01	GUARDRAIL ANCHOR BRACKET & END PLATE	84	W
FPA02	CABLE ANCHOR BRACKET	95	C
FPB01	BEARING PLATE	18 & 46	W
FPP01	BOX BEAM SUPPORT BRACKET	97	B
FRH20a	3/4" DIA. HOOKED ANCHOR ROD	82	C
FWC10a	3/8" DIA. FLAT WASHER	82	B
FWC12a	1/2" DIA. FLAT WASHER	82	B, C
FWC16a	5/8" DIA. FLAT WASHER	82	W
FWC20a	3/4" DIA. FLAT WASHER	82	C, W
FWC20b	3/4" DIA. HARDENED FLAT WASHER	82	B
FWC24a	1" DIA. FLAT WASHER	82	W
FWR03	RECTANGULAR PLATE WASHER	84	W
PDB01	WOOD BLOCKOUT	05A & 05B	W
PDE02	WOOD GUARDRAIL POST	05A	W
PDE09	CRT POST	46	W
PDF01	WOOD BREAKAWAY POST	46	W
PDF03	END POST	18	W
PLS01	SOIL PLATE	92 & 97	B, C
PLS03	SOIL PLATE	46	W
PSE01	CABLE GUARDRAIL LINE POST	92	C
PSE05	TYPE D BOX BEAM POST	97	B
PSE06	CABLE GUARDRAIL ANCHOR POST	95	C
PSE08	TYPE A BOX BEAM POST	97	B
PTE05	STEEL TUBE	46	W
PWE01	STEEL GUARDRAIL POST	05B	W
RBM01	BOX BEAM RAIL	98	B
RBM05	BOX BEAM TERMINAL RAIL	98	B
RBS01	BOX BEAM SPLICE PLATE	98	B
RCE01	COMPENSATING CABLE END ASSEMBLY	94	C
RCE03	CABLE END ASSEMBLY	94	C
RCM01	3/4" DIA. CABLE	94	C
RWE01a-b	W-BEAM END SECTION (FLARED)	88	W
RWE02a-b	W-BEAM TERMINAL CONNECTOR	88	W
RWE06a-b	W-BEAM END SECTION (BUFFER)	88	W
RWM02a-b	W-BEAM (12' - 6" LENGTH)	88	W
RWM22a-b	W-BEAM (25' - 0" LENGTH)	88	W
SEC01	CABLE GUARDRAIL TERMINAL ANCHOR ASSEMBLY	41	C

SCHEDULE OF GUARDRAIL HARDWARE			
DESIGNATION ①	DESCRIPTION	DTL. DWG. NO. (606-###)	GUARDRAIL TYPE ②
N/A	TURNBUCKLE CABLE END ASSEMBLY	94	C
N/A	KEEPER PLATE	95	C
N/A	TYPE B BOX BEAM POST	97	B
N/A	TS6 x 6 x 3/16 BR. APP. SECT. UPPER RAIL NO. 1	98	B
N/A	TS6 x 2 x 1/4 BR. APP. SECT. LOWER RAIL NO. 1	98	B
N/A	TS6 x 2 x 1/4 BR. APP. SECT. LOWER RAIL NO. 2	98	B
N/A	TS6 x 2 TO TS6 x 6 CONNECTION SLEEVE	98	B
N/A	TS6 x 2 CONNECTION SLEEVE	98	B

NOTES:

① SEE AASHTO-AGC-ARTBA JOINT COMMITTEE TASK FORCE 13 REPORT "A GUIDE TO STANDARDIZED HIGHWAY BARRIER HARDWARE" PUBLICATION FOR ADDITIONAL AND DETAILED HARDWARE SPECIFICATIONS.

② GUARDRAIL TYPE CODES:

W = W-BEAM METAL GUARDRAIL  
C = CABLE GUARDRAIL  
B = BOX BEAM GUARDRAIL

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-80


SCHEDULE OF  
GUARDRAIL HARDWARE

EFFECTIVE: JANUARY 2004






This Frame left blank




HEX BOLTS

BOLT SIZE	DESIGNATION *	L	T (MIN. )
REGULAR HEX BOLTS			
3/8" DIA.	FBX10a	3 1/2"	1 1/2"
3/8" DIA.	FBX10a	7 1/2"	1 1/2"
1/2" DIA.	FBX12a	1 1/2"	FULL
1/2" DIA.	FBX12a	2 1/2"	1 3/4"
5/8" DIA.	FBX16a	1 1/2"	FULL
3/4" DIA.	FBX20a	8"	2"
3/4" DIA.	FBX20a	9 1/2"	2"
HIGH STRENGTH HEX BOLTS			
3/4" DIA.	FBX20b	2"	1 1/2"
3/4" DIA.	FBX20b	4"	2"
3/4" DIA.	FBX20b	8"	2"




HEX NUT

NUT SIZE	DESIGNATION *
REGULAR HEX NUTS	
5/16" DIA.	FNX08a
3/8" DIA.	FNX10a
1/2" DIA.	FNX12a
5/8" DIA.	FNX16a
3/4" DIA.	FNX20a
1" DIA.	FNX24a
HIGH STRENGTH HEX NUTS	
3/4" DIA.	FNX20b




FLAT WASHERS

WASHER SIZE	DESIGNATION *
REGULAR FLAT WASHERS	
3/8" DIA.	FWC10a
1/2" DIA.	FWC12a
5/8" DIA.	FWC16a
3/4" DIA.	FWC20a
1" DIA.	FWC24a
HARDENED FLAT WASHERS	
3/4" DIA.	FWC20b




5/8" DIA. GUARDRAIL BOLT & RECESS NUT  
FBB01-05\*

DESIGNATION *	L	T (MIN. )
FBB01	1 1/4"	FULL
FBB02	2"	1 1/2"
FBB03	10"	1 3/4"
FBB04	1' - 6"	2 1/2"
FBB05	2' - 1"	2"



3/4" DIA. SQUARE NUT  
FNS20\*



3/4" DIA. HOOKED ANCHOR ROD  
FRH20a\*

NOTES:

- ① BOLTS AND ANCHOR RODS ARE TO CONFORM TO THE REQUIREMENTS OF ASTM F568 CLASS 4.6. NUTS ARE TO CONFORM TO THE REQUIREMENTS OF AASHTO M291 (ASTM A563) CLASS 5. USE STEEL WASHERS.
- ② HIGH STRENGTH BOLTS ARE TO CONFORM TO THE REQUIREMENTS OF AASHTO M164 (ASTM A325) TYPE 1. HIGH STRENGTH NUTS ARE TO CONFORM TO THE REQUIREMENTS OF AASHTO M291 (ASTM A563) CLASS 10S. HARDENED WASHERS ARE TO CONFORM TO THE REQUIREMENTS OF AASHTO M293 (ASTM F436).
- ③ GALVANIZE BOLTS, NUTS AND WASHERS IN ACCORDANCE WITH AASHTO M232 (ASTM A153). NO PUNCHING, DRILLING OR CUTTING IS PERMITTED AFTER GALVANIZING.

\*SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

DETAILED DRAWING


REFERENCE DWG. NO.  
STANDARD SPEC. 606-82  
SECTION 606

GUARDRAIL HARDWARE

EFFECTIVE: JANUARY 2004

MONTANA DEPARTMENT OF TRANSPORTATION MONTANA CADD






#### NOTES:


- FOR RELATED FASTENER HARDWARE SEE FWC24a\*, FNX24a\* AND FPA01\*.
- MACHINE THE SWAGED FITTING FROM HOT-ROLLED CARBON STEEL, CONFORMING TO THE REQUIREMENTS OF ASTM A576, GRADE 1035, AND ANNEAL SUITABLE FOR COLD SWAGING. GALVANIZE THE SWAGED FITTING IN ACCORDANCE WITH AASHTO M111 (ASTM A123) BEFORE SWAGING. DRILL A LOCK PIN HOLE TO ACCOMMODATE A 1/4" PLATED SPRING STEEL PIN THROUGH THE HEAD OF THE SWAGED FITTING TO RETAIN THE STUD IN THE PROPER POSITION.
- THE STUD IS TO CONFORM TO THE REQUIREMENTS OF ASTM F568 CLASS 8.8 AND BE GALVANIZED IN ACCORDANCE WITH AASHTO M232 (ASTM A153). PRIOR TO GALVANIZING, MILL A 3/8" SLOT INTO THE STUD END FOR THE LOCKING PIN.
- WIRE ROPE IS TO CONFORM TO THE REQUIREMENTS OF AASHTO M30 AND BE 3/4" PREFORMED, 6 x 19, WIRE STRAND CORE OR INDEPENDENT WIRE ROPE CORE (IWRC), GALVANIZED, RIGHT REGULAR LAY, MANUFACTURED OF IMPROVED PLOW STEEL WITH A MINIMUM BREAKING STRENGTH OF 42,800 POUNDS.
- THE SWAGED FITTING, STUD AND NUT (FNX24a\*) MUST DEVELOP THE BREAKING STRENGTH OF THE WIRE ROPE.

CABLE ASSEMBLY  
FCA01\*



ANCHOR BRACKET & END PLATE  
FPA01\*

POST SLEEVE  
FMM02\*




RECTANGULAR PLATE WASHER  
FWR03\*

#### NOTES:


- ANCHOR BRACKETS, END PLATES AND RECTANGULAR PLATE WASHERS ARE TO CONFORM TO THE REQUIREMENTS OF AASHTO M270 (ASTM A709) GRADE 36 STEEL PLATE. POST SLEEVES ARE TO CONFORM TO THE REQUIREMENTS OF ASTM A53 GRADE B.
- GALVANIZE FABRICATED PARTS IN ACCORDANCE WITH AASHTO M111 (ASTM A123). NO PUNCHING, DRILLING OR CUTTING IS PERMITTED AFTER GALVANIZING.

\*SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-84
SECTION 606	
W-BEAM METAL GUARDRAIL HARDWARE	
EFFECTIVE: DECEMBER 2002	



W-BEAM  
RWM02a-b\* (12'-6" LENGTH) OR RWM22a-b\* (25'-0" LENGTH)




W-BEAM END SECTION (BUFFER)  
RWE06a-b\*


#### NOTES:

* DESTINATION SUFFIX	METAL THICKNESS
a	12 GAGE
b	10 GAGE

\*SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.




W-BEAM END SECTION (FLARED)  
RWE01a-b\*




W-BEAM TERMINAL CONNECTOR  
RWE02a-b\*

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-88
SECTION 606	
W-BEAM METAL GUARDRAIL HARDWARE	
EFFECTIVE: JUNE 2003	






CABLE GUARDRAIL POST AND SOIL PLATE  
PSE01\* AND PLS01\*




5/16" DIA. HOOK BOLT  
FBH01\*




ALTERNATE 5/16" DIA. HOOK BOLT  
FBH02\*

- NOTES:
- ① ALL HOLES ARE 9.5 mm EXCEPT AS NOTED.
  - ② MANUFACTURE POSTS AND SOIL PLATES USING AASHTO M270M (ASTM A709M) GRADE 250 STEEL. ALL WELDING IS TO CONFORM TO THE APPLICABLE AWS CODE.
  - ③ HOOK BOLTS ARE TO CONFORM TO THE REQUIREMENTS OF ASTM 568M CLASS 4.6. NUTS ARE TO CONFORM TO THE REQUIREMENTS OF AASHTO M291M (ASTM A563M) CLASS 5.
  - ④ GALVANIZE FABRICATED PARTS IN ACCORDANCE WITH AASHTO M111M (ASTM A123M). GALVANIZE HOOK BOLTS AND NUTS IN ACCORDANCE WITH AASHTO M232M (ASTM A153M). NO PUNCHING, DRILLING, WELDING OR CUTTING IS PERMITTED ON COMPONENTS AFTER GALVANIZING.
  - ⑤ NUTS ARE OF THE HEAVY HEX TYPES. INSTALL BOLTS TO DEVELOP AN ULTIMATE PULL OPEN STRENGTH FROM 2225 N TO 4450 N APPLIED IN A DIRECTION NORMAL TO THE LONGITUDINAL AXIS OF THE POST.
- \* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.


DETAILED DRAWING	
REFERENCE	DWG. NO.
SECTION 606	606-92
CABLE GUARDRAIL HARDWARE	
EFFECTIVE: DECEMBER 2002	
MONTANA DEPARTMENT OF TRANSPORTATION	




COMPENSATING CABLE END ASSEMBLY  
RCE01\*




TURNBUCKLE CABLE END ASSEMBLY



CABLE END ASSEMBLY  
RCE03\*



CABLE WEDGE  
FMM01\*











3/4" DIA. CABLE  
RCM01\*


- NOTES:
- ① WIRE ROPE AND CONNECTING HARDWARE ARE TO CONFORM TO THE REQUIREMENTS OF AASHTO M30 TYPE I CLASS A, 3/4" ROPE. CONNECTING HARDWARE MUST DEVELOP THE FULL STRENGTH OF A SINGLE CABLE (25,000 LB). CAST STEEL COMPONENTS ARE TO CONFORM TO THE REQUIREMENTS OF AASHTO M103 (ASTM A27). MALLEABLE IRON CASTINGS ARE TO CONFORM TO THE REQUIREMENTS OF ASTM A47.
  - ② AT ALL LOCATIONS WHERE THE CABLE IS CONNECTED TO A CABLE SOCKET WITH A WEDGE TYPE CONNECTION, CRIMP ONE WIRE OF THE CABLE OVER THE BASE OF THE WEDGE TO HOLD IT FIRMLY IN PLACE.
  - ③ COMPENSATING DEVICES ARE TO HAVE SPRING CONSTANTS OF 450 POUNDS PER INCH, PLUS OR MINUS 50 POUNDS PER INCH, AND PERMIT A TRAVEL OF 6 INCHES PLUS OR MINUS 1 INCH.
  - ④ DESIGN SOCKET BASKETS FOR USE WITH THE WEDGE DETAILED IN THIS DRAWING.
  - ⑤ ALTERNATE HARDWARE DESIGNS WILL BE CONSIDERED FOR APPROVAL PROVIDED THEIR CONNECTION DETAILS, FOR THE PURPOSE OF MAINTENANCE SUBSTITUTIONS, ARE COMPATIBLE WITH THE DETAILS OF THIS DRAWING AND THEIR OPERATING CHARACTERISTICS ARE SIMILAR TO THOSE OF THE HARDWARE IN THIS DRAWING.
- \* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

DETAILED DRAWING	
REFERENCE	DWG. NO.
SECTION 606	606-94
CABLE GUARDRAIL HARDWARE	
EFFECTIVE: DECEMBER 2002	
MONTANA DEPARTMENT OF TRANSPORTATION	






\* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.




TYPE D BOX BEAM POST AND SOIL PLATE  
PSE05\* AND PLS01\*

EFFECTIVE: JANUARY 2004


 MONTANA DEPARTMENT  
OF TRANSPORTATION  
CADD






BOX BEAM RAIL (TS6 x 6 x 3/16)


RBM01\*




TS6 x 6 x 3/16 BR. APP. SECT. UPPER RAIL NO. 1




TS6 x 2 x 1/4 BR. APP. SECT. LOWER RAIL NO. 1




TS6 x 2 x 1/4 BR. APP. SECT. LOWER RAIL NO. 2



TS6 x 6 x 3/16 SECTION VIEW




TS6 x 2 x 1/4 SECTION VIEW




BOX BEAM EXPANSION SPLICE END

ONE END OF BOX BEAM RAIL ONLY. REQUIRED FOR BOTH RAILS AT THE EXPANSION SPLICE.




BOX BEAM TERMINAL RAIL (TS6 x 6 x 3/16)

RBM05\*





END COVER PLATE DETAIL

(BAR 5" x 3/16" x 0'-5 3/4")




BOX BEAM SPLICE PLATE

RBS01\*



TS6 x 2 TO TS6 x 6 CONNECTION SLEEVE



TS6 x 2 CONNECTION SLEEVE


# NOTES:

- MANUFACTURE BOX BEAM RAIL ELEMENTS FROM EITHER ASTM A500 GRADE B COLD ROLLED TUBING, ASTM A501 HOT-ROLLED TUBING OR AUTOMOTIVE ROLLOVER PROTECTIVE STEEL (ROPS). WHEN ASTM A500 GRADE B STEEL IS USED, TEST THE MATERIAL PER ASTM E436.
- FABRICATE SPLICE PLATES AND CONNECTION SLEEVES FROM AASHTO M270 GRADE 36 STEEL PLATE. THE NUTS ARE TO BE PLAIN UN-COATED 3/4" DIA. HIGH STRENGTH HEX NUTS. WELD THE NUTS TO THE PLATES IN ACCORDANCE WITH THE APPLICABLE AWS CODE.
- GALVANIZE FABRICATED RAIL, CONNECTION SLEEVES, AND SPLICE PLATES IN ACCORDANCE WITH AASHTO M111. NO PUNCHING, DRILLING, WELDING OR CUTTING IS PERMITTED ON COMPONENTS AFTER GALVANIZING.

\* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.



DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-98
SECTION 606	
BOX BEAM GUARDRAIL HARDWARE	
EFFECTIVE: JANUARY 2004	
MONTANA DEPARTMENT OF TRANSPORTATION	MONTANA CADD






WIRE SPACING TABLE			
COMBINATION WOVEN WIRE & BARBED WIRE FENCE		BARBED WIRE FENCE	
48" FENCE HEIGHT		48" FENCE HEIGHT	
32" WW-2 BW *	32" WW-3 BW *	3 BW	4 BW
TYPE F2-32WW	TYPE F3-32WW	TYPE F3	TYPE F4






FENCE TYPE	RUN = L	PANELS REQUIRED
COMBINATION WOVEN BARBED	LESS THAN 33'	NONE
	33' - 330'	SINGLE
	OVER 330' TO 660' MAX.	DOUBLE
BARBED	LESS THAN 66'	NONE
	66' - 660'	SINGLE
	OVER 660' TO 990' MAX.	DOUBLE

NOTE:  
TIE OFF ON ALL CROSS HATCHED OR SHADED  
POSTS.



DOUBLE PANEL AT FENCE  
CORNER OR ANGLE BREAK  
FENCE PANEL TYPES




ALTERNATE DEADMAN  
WHEN APPROVED BY THE ENGINEER THE ABOVE DEADMAN  
MAY BE USED IN LIEU OF A ROCK OR PRECAST CONCRETE  
BLOCK AS SPECIFIED ON DTL. DWG. NO. 607-05.

#### NOTES:


ATTACH BARBED WIRES TO POSTS BY WRAPPING AROUND THE POST AT LEAST TWO TIMES,  
THEN WRAPPING AROUND ITSELF FIVE TIMES.

TO ATTACH WOVEN WIRE TO AN END POST, REMOVE TWO OR THREE VERTICAL STAY WIRES  
FROM THE END OF THE FENCE. PLACE THE FIRST COMPLETE VERTICAL STAY WIRE AGAINST  
THE POST. START AT THE MIDDLE OF THE HORIZONTAL LINE WIRES, WRAPPING AROUND  
THE END POST AT LEAST TWO TIMES AND THEN WRAPPING AROUND ITSELF FIVE TIMES.


DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	607-10
SECTION 607	
FENCING DETAILS	
EFFECTIVE: JANUARY 2004	




FENCE LAYOUT ON STEEP SLOPES




FENCE LAYOUT ON SHARP VERTICAL CURVES  
TO AVOID TRYING TO CONFORM WOVEN WIRE TO UNEVEN TERRAIN




FENCE CONNECTION TO CATTLE GUARD  
SECURELY FASTEN FENCE WIRE TO THE WINGS  
AND ARRANGE SO THAT ANIMALS CANNOT PASS.



FENCE LAYOUT AT  
CHANGE IN R/W WIDTH




FENCE LAYOUT AT CROSS-FENCE CONNECTION



FENCE LAYOUT AT LOCAL ROAD  
UNDER INTERSTATE


DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	607-15
SECTION 607	
FENCING DETAILS	
EFFECTIVE: AUGUST 1999	






WOOD FARM ENTRANCE GATE (TYPE G-1)

NOTE: USE 10d NAILS AND CLINCH FOR GATE CONSTRUCTION.



WIRE FARM ENTRANCE GATE (TYPE G-2)

NOTE: USE SAME WIRE SCHEME ON GATE AS THAT USED ON FENCE, UNLESS STATED OTHERWISE IN R/W AGREEMENT.



METAL FARM ENTRANCE GATE (TYPE G-3)




NOTES:

ALL GATES ARE 16'-0" WIDE UNLESS R/W AGREEMENT STATES OTHERWISE.

ALL GATES WILL HAVE A SINGLE OR DOUBLE PANEL AT EACH END.

\* TYPE G-3 GATES ARE AVAILABLE IN WIDTHS FROM 4' TO 20' IN 2' INCREMENTS.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	607-20
SECTION 607	
FARM ENTRANCE GATES	
EFFECTIVE: JANUARY 2004	
MONTANA DEPARTMENT OF TRANSPORTATION	



NOTES:

SEE THE STANDARD SPECIFICATIONS FOR FURTHER REQUIREMENTS.

DO NOT INSTALL DOUBLE PANELS MORE THAN 300' APART ON TANGENTS OR MORE THAN 250' APART ON ANY CURVE. FOR CURVES SHARPER THAN 5', INSTALL A DOUBLE PANEL ON EACH CURVE END, PLUS ONE ADDITIONAL PANEL FOR EACH 10' OF DEFLECTION, EVENLY SPACED, BETWEEN THE CURVE ENDS.

PULL POST BRACING ON 6 FOOT FENCE IS THE SAME AS CORNER BRACING.

A DROP BAR LOCKING DEVICE IS REQUIRED FOR ALL DOUBLE GATE INSTALLATIONS. THE DROP BAR MUST BE ABLE TO BE INSERTED INTO THE CONCRETE BLOCK AT LEAST SIX INCHES.


ALL CONCRETE IS CLASS "F" OR BETTER.

WHEN FENCE IS LESS THAN 50' FROM THE EDGE OF A DRIVING LANE, USE A 3/8" DIA. GALVANIZED STEEL CABLE IN PLACE OF THE TOP METAL BRACE RAIL.


HEIGHT OF FABRIC	WIRE FABRIC ABOVE GROUND	DEPTH OF CONCRETE	DEPTH OF POST IN CONC. (MIN.)
6'	1" TO 2"	36"	32"
5'	1" TO 2"	36"	32"
4'	1" TO 2"	30"	26"
3'	1" TO 2"	30"	26"

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	607-25
SECTION 607	
CHAIN LINK FENCE	
EFFECTIVE: AUGUST 1999	
MONTANA DEPARTMENT OF TRANSPORTATION	







FRONT VIEW




2 FRAME



END VIEW



1 SILL



3 FRAME

# GENERAL NOTES

- (A) ANCHOR SYSTEM DETAIL  
USE ANCHOR SYSTEM #1 UNLESS SOIL AND MOISTURE CONDITIONS NECESSITATE THE USE OF AN ALTERNATE SYSTEM, OR AS DIRECTED BY THE ENGINEER. CONSULT DETAILED DRAWING NUMBERS 607-40 AND 607-45 FOR ANCHOR SYSTEMS #3 (ROCKY CONDITIONS) AND #2 (SWAMPY CONDITIONS).
- (B) SLAT FASTENING  
FASTEN SLATS TO THE FRAME WITH 3 ~ 12d COMMON BARBED SHANK NAILS AT EACH LOCATION.
- (C) BRACE FASTENING  
FASTEN BRACES TO THE FRAME WITH 4 ~ 8d COMMON NAILS AT EACH LOCATION AND CLINCH.
- (D) FRAME TO SILL AND FRAME TO FRAME FASTENING  
FASTEN THE SILL AND FRAME MEMBERS TO THE FRAME AT EACH LOCATION WITH 2 ~ 5/8" DIA. x 5" STANDARD MACHINE BOLTS, EACH WITH HEX NUT AND TWO FLAT WASHERS. SEE NOTE (X) AT RIGHT.
- (E) LINE POSTS  
PLACE LINE POSTS AT EACH END OF EACH LINE OF SNOW FENCE AS SHOWN. POSTS ARE 6'-6" LONG WITH A MINIMUM DIAMETER OF 3" AND A MAXIMUM DIAMETER OF 6". BUTT TREAT 3' MINIMUM.
- (F) WIRE TIE  
USE 12 GAGE OR HEAVIER GALVANIZED WIRE TO FORM THE WIRE TIES.
- (G) SLOPE BRACE FASTENING  
FASTEN SLOPE BRACES WITH 3 ~ 16d COMMON BARBED SHANK NAILS AT EACH LOCATION.

LUMBER - 8' SNOW FENCE W/ ANCHOR SYSTEM #1			
BILL OF MATERIALS FOR ONE PANEL			
ITEM NO.	NO. OF PIECES	LUMBER SIZE	DESCRIPTION
1*	3	2" x 6" x 8'-0"	FRAME (SILL)
2*	3	2" x 6" x 7'-6"	FRAME
3*	3	2" x 6" x 8'-6"	FRAME
* NOTE: PRESSURE TREAT ALL 2" x 6" MEMBERS (ENTIRE FRAME)			
4	1	1" x 6" x 16'-0"	BRACE
5	8	1" x 6" x 16'-0"	SLAT
6**	2	2" x 6" x 10'-0"	SLOPE BRACE
** NOTE: USE ONLY WHEN SLOPE IS 5:1 OR GREATER			


HARDWARE - 8' SNOW FENCE W/ ANCHOR SYSTEM #1		
BILL OF MATERIALS FOR ONE PANEL		
QUANTITY	DESCRIPTION	
18	5/8" DIA. x 5" HEX BOLT (THREADED FULL LENGTH) AND NUT	
36	FLAT WASHER FOR 5/8" DIA. BOLT	
1 LB.	12d COMMON BARBED SHANK NAIL	
12	#6 REBAR x 5'-0" (3/4" DIA.)	
6 PIECES	12 GAGE TIE WIRE x 5'-0" ±	
1/3 LB.	8d COMMON NAILS	
1/4 LB.	16d COMMON BARBED SHANK NAILS	

ALL NAILS MAY BE EITHER HAND DRIVEN OR DRIVEN WITH A PNEUMATIC NAILER.


(X) NOTE:  
AFTER 5/8" DIA. BOLTS HAVE BEEN TIGHTENED, BURR THE THREAD DIRECTLY BEHIND THE NUT TO PREVENT EVENTUAL LOOSENING OF THE NUTS.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	607-30
SECTION 607	
8' WOOD SNOW FENCE W/ ANCHOR SYSTEM #1	
EFFECTIVE: AUGUST 1999	





FRONT VIEW



NOTE:  
PLACEMENT OF REBAR ANCHORS  
TIGHT AGAINST SNOW FENCE  
MEMBERS (1) (3) & (4) IS CRITICAL  
TO PREVENT OVERTURNING AND  
SLIDING. SEE ANCHOR SYSTEM #1  
DETAILS, DTL. DWG. NO. 607-40.

DIG OUT AS REQUIRED FOR ENDS OF MEMBERS (2) (3) & (4) AND  
THE ENTIRE LENGTH OF SILL (1) TO ASSURE FULL BEARING OF SILL  
AGAINST TERRAIN.

END VIEW

GENERAL NOTES

- (A) ANCHOR SYSTEM DETAIL  
USE ANCHOR SYSTEM #1 UNLESS SOIL AND MOISTURE CONDITIONS NECESSITATE THE USE  
OF AN ALTERNATE SYSTEM, OR AS DIRECTED BY THE ENGINEER. CONSULT DETAILED  
DRAWING NUMBERS 607-40 AND 607-45 FOR ANCHOR SYSTEMS #3 (ROCKY CONDITIONS)  
AND #2 (SWAMPY CONDITIONS).
- (B) SLAT FASTENING  
FASTEN SLATS TO THE FRAME WITH 3 ~ 12d COMMON BARBED SHANK NAILS AT EACH  
LOCATION.
- (C) BRACE FASTENING  
FASTEN BRACES TO THE FRAME WITH 4 ~ 8d COMMON NAILS AT EACH LOCATION AND  
CLINCH.
- (D) FRAME TO SILL AND FRAME TO FRAME FASTENING  
FASTEN THE SILL AND FRAME MEMBERS TO THE FRAME AT EACH LOCATION WITH 2 ~  
5/8" DIA. x 5" STANDARD MACHINE BOLTS, EACH WITH HEX NUT AND TWO FLAT  
WASHERS. SEE NOTE (X) AT RIGHT.
- (E) LINE POSTS  
PLACE LINE POSTS AT EACH END OF EACH LINE OF SNOW FENCE AS SHOWN. POSTS  
ARE 6'-6" LONG WITH A MINIMUM DIAMETER OF 3" AND A MAXIMUM DIAMETER OF 6".  
BUTT TREAT 3' MINIMUM.
- (F) WIRE TIE  
USE 12 GAGE OR HEAVIER GALVANIZED WIRE TO FORM THE WIRE TIES.
- (G) BACK & SLOPE BRACE FASTENING  
FASTEN BACK BRACES TO THE FRAME WITH 2 ~ 16d NAILS, AND FASTEN THE SLOPE  
BRACES WITH 3 ~ 16d BARBED SHANK NAILS AT EACH LOCATION.

LUMBER - 12' SNOW FENCE W/ ANCHOR SYSTEM #1			
BILL OF MATERIALS FOR ONE PANEL			
ITEM NO.	NO. OF PIECES	LUMBER SIZE	DESCRIPTION
(1)*	3	2" x 6" x 12'-0"	SILL
(2)*	3	2" x 6" x 7'-0"	FRAME
(3)*	3	2" x 6" x 13'-0"	FRAME
(4)*	3	2" x 6" x 13'-0"	FRAME
* NOTE: PRESSURE TREAT ALL 2" x 6" MEMBERS (ENTIRE FRAME)			
(5)	1	2" x 4" x 12'-0"	BACK BRACE
(6)	1	1" x 6" x 18'-0"	BRACE
(7)	12	1" x 6" x 16'-0"	SLAT
(8)**	2	2" x 6" x 13'-0"	SLOPE BRACE
** NOTE: USE ONLY WHEN SLOPE IS 5:1 OR GREATER			


HARDWARE - 12' SNOW FENCE W/ ANCHOR SYSTEM #1		
BILL OF MATERIALS FOR ONE PANEL		
QUANTITY	DESCRIPTION	
(D)	30	5/8" DIA. x 5" HEX BOLT (THREADED FULL LENGTH) AND NUT
(D)	60	FLAT WASHER FOR 5/8" DIA. BOLT
(C)	1/2 LB.	8d COMMON NAILS
(B)	1 2/3 LB.	12d COMMON BARBED SHANK NAILS
(G)	1/2 LB.	16d COMMON BARBED SHANK NAILS
(A)	12	#6 REBAR x 5'-0" (3/4" DIA.)
(F)	6 PIECES	12 GAGE TIE WIRE x 5'-0" ±

ALL NAILS MAY BE EITHER HAND DRIVEN OR DRIVEN WITH A PNEUMATIC NAILER.


DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	607-35
SECTION 607	
12' WOOD SNOW FENCE W/ ANCHOR SYSTEM #1	
EFFECTIVE: AUGUST 1999	
	MONTANA CADD



# ANCHOR SYSTEM #3 (FOR ROCKY CONDITIONS)




LEFT END VIEW




FRONT VIEW

NOTE:  
HOLES SHOWN IN DETAILS BELOW ARE FOR LEFT END OF FENCE.  
HOLES SHOWN HIDDEN ARE FOR RIGHT END OF FENCE.




DETAIL M

DETAIL N



DETAIL L



DETAIL H

## LUMBER - SNOW FENCE W/ ANCHOR SYSTEM #3

### BILL OF MATERIALS FOR ONE PANEL

SAME AS FOR SNOW FENCE W/ ANCHOR SYSTEM #1

## HARDWARE - SNOW FENCE W/ ANCHOR SYSTEM #3


### BILL OF MATERIALS FOR ONE PANEL

QUANTITY	DESCRIPTION
4	5" x 3" x 3/8" x 5" L
4	5/8" DIA. x 4'-0" BAR W/ 3 HEX NUTS
4	FLAT WASHERS FOR 5/8" DIA. BAR
0.16 C. Y.	CLASS D CONCRETE
4	#6 REBAR x 2'-0" (3/4" DIA.)
4 PIECES	12 GAGE TIE WIRE x 2'-0" ±
30	5/8" DIA. x 5" HEX BOLT (THREADED FULL LENGTH) AND NUT
60	FLAT WASHERS FOR 5/8" DIA. BOLT

NOTE: NAILS REQUIRED ARE SAME AS SHOWN ON HARDWARE SUMMARY FOR SNOW FENCE W/ ANCHOR SYSTEM #1

(X) NOTE:  
AFTER 5/8" DIA. BOLTS HAVE BEEN TIGHTENED,  
BURR THE THREAD DIRECTLY BEHIND THE NUT  
TO PREVENT EVENTUAL LOOSENING OF THE NUTS.

## ANCHOR SYSTEM #1 (STANDARD)




TOP

FRONT

SIDE

### WIRE TIE DETAIL

USE 12 GAGE OR HEAVIER GALVANIZED  
WIRE TO FORM THE WIRE TIES.




USE TWO #6 REINFORCING BARS FOR EACH END OF EACH  
SILL MEMBER. DRIVE THE BARS UP TIGHT TO THE FRAME  
TO PREVENT SLIDING. TIE THE REINFORCING BARS AS SHOWN  
IN THE WIRE TIE DETAIL. THE PLACEMENT OF THE ANCHORS  
IS CRITICAL IN PREVENTING OVERTURNING AND SLIDING OF  
THE FENCE.

STANDARD ANCHOR DETAIL


DETAILED DRAWING	DWG. NO.
REFERENCE	607-40
STANDARD SPEC.	SECTION 607
WOOD SNOW FENCE ANCHOR SYSTEM #3 AND #1 DETAILS	
EFFECTIVE: AUGUST 1999	
MONTANA DEPARTMENT OF TRANSPORTATION	MONTANA CADD



ANCHOR SYSTEM #2  
(FOR SWAMPY CONDITIONS)





LEFT END VIEW




FRONT VIEW

NOTE:  
HOLES SHOWN IN DETAILS BELOW ARE FOR LEFT END OF FENCE.  
HOLES SHOWN HIDDEN ARE FOR RIGHT END OF FENCE.




DETAIL J

DETAIL K




DETAIL H


NOTE:  
USE ON FRONT AND BACK OF CENTER SUPPORT.



DETAIL I



WIRE ROPE CONNECTION



DEADMAN DETAIL

LUMBER - SNOW FENCE W/ ANCHOR SYSTEM #2	
BILL OF MATERIALS FOR ONE PANEL	
SAME AS FOR SNOW FENCE W/ ANCHOR SYSTEM #1	


HARDWARE - SNOW FENCE W/ ANCHOR SYSTEM #2	
BILL OF MATERIALS FOR ONE PANEL	
QUANTITY	DESCRIPTION
4	5" x 3" x 3/8" x 5" L
8	3/8" WIRE CLAMPS
4	1/2" DIA. DROP FORGED EYEBOLTS W/ 3 HEX NUTS
4	FLAT WASHERS FOR 1/2" DIA. EYEBOLTS
4	#6 REBAR x 2'-0" (3/4" DIA.)
4 PIECES	12 GAGE TIE WIRE x 2'-0" ±
29 FT.	3/8" DIA. WIRE ROPE
2	6" DIA. x 5'-0" POST DEADMEN
30	5/8" DIA. x 5" HEX BOLT (THREADED FULL LENGTH) AND NUT
60	FLAT WASHERS FOR 5/8" BOLT
NOTE: NAILS REQUIRED ARE SAME AS SHOWN ON HARDWARE SUMMARY FOR SNOW FENCE W/ ANCHOR SYSTEM #1	

(X) NOTE:  
AFTER 5/8" DIA. BOLTS HAVE BEEN TIGHTENED, BURR THE THREAD DIRECTLY BEHIND THE NUT TO PREVENT EVENTUAL LOOSENING OF THE NUTS.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	607-45
SECTION 607	
WOOD SNOW FENCE ANCHOR SYSTEM #2 DETAILS	
EFFECTIVE: AUGUST 1999	
MONTANA DEPARTMENT OF TRANSPORTATION	
MONTANA CADD	




This Frame left blank







CURB RAMP TYPES




(A)  
PERPENDICULAR PUBLIC SIDEWALK CURB RAMP  
(SEE DETAILED DRAWING NUMBER 608-25 FOR  
ADDITIONAL DETAILS)



(B)  
PARALLEL PUBLIC SIDEWALK CURB RAMP  
(SEE DETAILED DRAWING NUMBER 608-30  
FOR ADDITIONAL DETAILS)



(C)  
COMBINED (PARALLEL/PERPENDICULAR) PUBLIC  
SIDEWALK CURB RAMP (SEE DETAILED DRAWING  
NUMBERS 608-25 AND 608-30 FOR ADDITIONAL  
DETAILS)



(D)  
DIAGONAL PUBLIC SIDEWALK CURB RAMP  
(SEE DETAILED DRAWING NUMBER 608-35  
FOR ADDITIONAL DETAILS)

- GENERAL NOTES:**
- IN NEW CONSTRUCTION, USE PUBLIC SIDEWALK CURB RAMPS IN THE FOLLOWING ORDER OF PREFERENCE:
    - PERPENDICULAR PUBLIC SIDEWALK CURB RAMP.
    - PARALLEL PUBLIC SIDEWALK CURB RAMP.
    - COMBINED (PARALLEL/PERPENDICULAR) PUBLIC SIDEWALK CURB RAMP.
    - DIAGONAL PUBLIC SIDEWALK CURB RAMP.
  - SINGLE DIAGONAL OR DEPRESSED CORNER PUBLIC SIDEWALK CURB RAMPS SERVING TWO STREET CROSSING DIRECTIONS ARE NOT PERMITTED IN NEW CONSTRUCTION.
  - WHEN ALTERING EXISTING FACILITIES, MEET NEW CONSTRUCTION REQUIREMENTS FOR PUBLIC SIDEWALK CURB RAMPS TO THE MAXIMUM EXTENT FEASIBLE.
- CONSTRUCTION REQUIREMENTS:**
- OBTAIN A SURFACE TEXTURE ON THE RAMP BY COARSE BROOMING, TRANSVERSE TO THE RAMP SLOPE.
  - TAKE CARE DURING CONSTRUCTION TO ASSURE UNIFORM RAMP GRADES, FREE OF SAGS AND SHARP GRADE CHANGES.

APPENDIX IV  
AMERICANS WITH DISABILITIES ACT (ADA)  
ACCESSIBILITY GUIDELINES FOR BUILDINGS AND  
FACILITIES  
AUGUST 1994 EDITION


REFERENCE STANDARD SPEC. SECTION 608	DETAILED DRAWING DWG. NO. 608-15
--	--

NEW CONSTRUCTION  
PUBLIC SIDEWALK  
CURB RAMPS


EFFECTIVE: DECEMBER 2002




CURB RAMP TYPES



(A)  
PERPENDICULAR PUBLIC SIDEWALK CURB RAMP  
(SEE DETAILED DRAWING NUMBER 608-25 FOR  
ADDITIONAL DETAILS)




(B)  
PARALLEL PUBLIC SIDEWALK CURB RAMP  
(SEE DETAILED DRAWING NUMBER 608-30  
FOR ADDITIONAL DETAILS)




(C)  
COMBINED (PARALLEL/PERPENDICULAR) PUBLIC  
SIDEWALK CURB RAMP (SEE DETAILED DRAWING  
NUMBERS 608-25 AND 608-30 FOR ADDITIONAL  
DETAILS)

CURB RAMP TYPES



(D)  
DIAGONAL PUBLIC SIDEWALK CURB RAMP  
(SEE DETAILED DRAWING NUMBER 608-35  
FOR ADDITIONAL DETAILS)



(E)  
SINGLE DIAGONAL PUBLIC SIDEWALK CURB  
RAMP (SEE DETAILED DRAWING NUMBER  
608-35 FOR ADDITIONAL DETAILS)

**GENERAL NOTES:**

- WHEN ALTERING EXISTING FACILITIES, USE PUBLIC SIDEWALK CURB RAMPS IN THE FOLLOWING ORDER OF PREFERENCE:
  - PERPENDICULAR PUBLIC SIDEWALK CURB RAMP
  - PARALLEL PUBLIC SIDEWALK CURB RAMP
  - COMBINED (PARALLEL/PERPENDICULAR) PUBLIC SIDEWALK CURB RAMP
  - DIAGONAL PUBLIC SIDEWALK CURB RAMP
  - SINGLE DIAGONAL PUBLIC SIDEWALK CURB RAMP
- NOTE: USE DIAGONAL PUBLIC SIDEWALK CURB RAMPS AS THE LAST OPTION AND CONSTRUCT TO COMPLY WITH ALL ADA SLOPE AND CONSTRUCTION CRITERIA TO THE GREATEST EXTENT POSSIBLE.
- PLACE CURB RAMPS TO AVOID EXISTING DRAINAGE STRUCTURES AND OTHER OBSTRUCTIONS TO THE GREATEST EXTENT POSSIBLE.
- USE THE FLATTEST SLOPES POSSIBLE FOR ALL CURB RAMPS. MAXIMUM SLOPES ARE SHOWN FOR GUIDANCE AT DIFFICULT SITES AND SHOULD BE AVOIDED IF POSSIBLE.
- FINAL FIELD LOCATION OF THE CURB RAMPS WILL BE DETERMINED BY THE ENGINEER.
- IF R/W DOES NOT PERMIT LANDINGS FOR THESE RAMPS, USE ANOTHER RAMP DESIGN.
- PEDESTRIAN ACCESS POINTS AT CROSSWALKS ARE TO BE WHOLLY CONTAINED WITHIN THE CROSSWALK LINES.
- FOR ADDITIONAL INFORMATION CONSULT:
  - APPENDIX IV AMERICANS WITH DISABILITIES ACT (ADA) ACCESSIBILITY GUIDELINES FOR BUILDINGS AND FACILITIES AUGUST, 1994 EDITION

**CONSTRUCTION REQUIREMENTS:**

- OBTAIN A SURFACE TEXTURE ON THE RAMP BY COARSE BROOMING, TRANSVERSE TO THE RAMP SLOPE.
- TAKE CARE DURING CONSTRUCTION TO ASSURE UNIFORM RAMP GRADES, FREE OF SAGS AND SHARP GRADE CHANGES.


REFERENCE STANDARD SPEC. SECTION 608	DETAILED DRAWING DWG. NO. 608-20
--	--

ALTERATIONS TO EXISTING  
FACILITIES - PUBLIC  
SIDEWALK CURB RAMPS


EFFECTIVE: DECEMBER 2002







PERPENDICULAR PUBLIC SIDEWALK CURB RAMP



SECTION A-A

#### NEW CONSTRUCTION REQUIREMENTS:



1. THE DESIRABLE WIDTH OF THE CURB RAMP (DIMENSION "W" ABOVE) IS 4 FEET OR WIDER. THE MINIMUM WIDTH (W) IS 3 FEET.
2. THE DESIRABLE LENGTH OF THE LANDING AT THE TOP OF THE CURB RAMP (DIMENSION "L" ABOVE) IS 5 FEET OR THE LENGTH OF THE RAMP. THE MINIMUM LENGTH "L" IS 4 FEET.
3. THE DESIRABLE SLOPE FOR THE CURB RAMP IS 1:20 OR FLATTER. THE MAXIMUM CURB RAMP SLOPE IS 1:12.
4. THE DESIRABLE SLOPE FOR THE FLARED SIDE OF THE CURB RAMP IS 1:12 OR FLATTER. THE MAXIMUM FLARED SIDE SLOPE IS 1:10.
5. THE MAXIMUM CROSS SLOPE OF THE SIDEWALK IS 1:50 (2%).
6. THE SURFACE OF THE PERPENDICULAR PUBLIC SIDEWALK CURB RAMP IS TO CONTRAST VISUALLY WITH THE ADJOINING PUBLIC SIDEWALK SURFACES. THIS CAN BE OBTAINED BY USE OF COLORED CONCRETE, PATTERNING THE CONCRETE SURFACE OR OTHER APPROVED METHODS.


#### REQUIREMENTS FOR ALTERATIONS TO EXISTING FACILITIES:

NOTE: WHEREVER POSSIBLE, ALTER EXISTING FACILITIES TO COMPLY WITH THE NEW CONSTRUCTION REQUIREMENTS.


1. THE MINIMUM WIDTH OF THE CURB RAMP (DIMENSION "W" ABOVE) IS 3 FEET.  
NOTE: WHERE THE PUBLIC PEDESTRIAN RIGHT-OF-WAY WIDTH IS LESS THAN 3 FEET, PROVIDE A PARALLEL PUBLIC SIDEWALK CURB RAMP.
2. WHERE PUBLIC PEDESTRIAN RIGHT-OF-WAY WIDTH IS INSUFFICIENT TO ACCOMMODATE A TOP LANDING OF 4 FEET, PROVIDE A TOP LANDING OF 3 FEET.
3. THE MAXIMUM CURB RAMP SLOPE IS 1:10, PROVIDED THE RISE (DIMENSION "Y" ABOVE) IS 6 INCHES OR LESS. A 1:12 OR FLATTER SLOPE IS DESIRABLE.
4. THE MAXIMUM FLARED SIDE SLOPE IS 1:10.
5. THE MAXIMUM CROSS SLOPE OF THE SIDEWALK IS 1:50 (2%).
6. THE SURFACE OF THE PERPENDICULAR PUBLIC SIDEWALK CURB RAMP IS TO CONTRAST VISUALLY WITH THE ADJOINING PUBLIC SIDEWALK SURFACES. THIS CAN BE OBTAINED BY USE OF COLORED CONCRETE, PATTERNING THE CONCRETE SURFACE OR OTHER APPROVED METHODS.
7. WHERE EXISTING SITE DEVELOPMENT CONDITIONS PROHIBIT THE STRICT AND FULL COMPLIANCE OF ALL ADA CRITERIA, PROVIDE ACCESSIBILITY TO THE MAXIMUM EXTENT FEASIBLE.

NOTE:  
COMBINED (PARALLEL/PERPENDICULAR) PUBLIC SIDEWALK CURB RAMPS ARE TO MEET THE CRITERIA FOR BOTH THE PARALLEL AND PERPENDICULAR PUBLIC SIDEWALK CURB RAMPS. (SEE DETAILED DRAWING NUMBER 608-30 AND THIS DRAWING.)

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	608-25
SECTION 608	
PERPENDICULAR PUBLIC SIDEWALK CURB RAMPS	
EFFECTIVE: AUGUST 1999	
 MONTANA DEPARTMENT OF TRANSPORTATION  MONTANA CADD	



SECTION A-A



SECTION B-B

#### NEW CONSTRUCTION REQUIREMENTS:

1. THE MINIMUM LENGTH OF THE LANDING (DIMENSION "L" ABOVE) IS 5 FEET.
2. THE DESIRABLE SLOPE FOR THE CURB RAMPS IS 1:20 OR FLATTER. THE MAXIMUM CURB RAMP SLOPE IS 1:12.
3. THE MAXIMUM CROSS SLOPE OF THE SIDEWALK OR LANDING IS 1:50 (2%).
4. THE SURFACE OF THE RAMP IS TO CONTRAST VISUALLY WITH ADJOINING PUBLIC SIDEWALK SURFACES. THIS CAN BE OBTAINED BY USE OF COLORED CONCRETE, PATTERNING THE CONCRETE SURFACE OR OTHER APPROVED METHODS.

#### REQUIREMENTS FOR ALTERATIONS TO EXISTING FACILITIES:

NOTE: WHEREVER POSSIBLE, ALTER EXISTING FACILITIES TO COMPLY WITH THE NEW CONSTRUCTION REQUIREMENTS.

1. THE DESIRABLE LENGTH OF THE LANDING (DIMENSION "L" ABOVE) IS 5 FEET. THE MINIMUM LANDING LENGTH IS 4 FEET.
2. THE MAXIMUM CURB RAMP SLOPE IS 1:10, PROVIDED THE RISE (DIMENSION "Y" ABOVE) IS 6 INCHES OR LESS. A 1:12 OR FLATTER SLOPE IS DESIRABLE.
3. THE MAXIMUM CROSS SLOPE OF THE SIDEWALK AND LANDING IS 1:50 (2%) SLOPE.
4. THE SURFACE OF THE RAMP IS TO CONTRAST VISUALLY WITH THE ADJOINING PUBLIC SIDEWALK SURFACES. THIS CAN BE OBTAINED BY USE OF COLORED CONCRETE, PATTERNING THE CONCRETE SURFACE OR OTHER APPROVED METHODS.
5. WHERE EXISTING SITE DEVELOPMENT CONDITIONS PROHIBIT THE STRICT AND FULL COMPLIANCE OF ALL ADA CRITERIA, PROVIDE ACCESSIBILITY TO THE MAXIMUM EXTENT FEASIBLE.

#### NOTES:

THE COST OF THE RETAINING WALL IS INCLUDED IN THE UNIT PRICE BID FOR CONCRETE SIDEWALK.

COMBINED (PARALLEL/PERPENDICULAR) PUBLIC SIDEWALK CURB RAMPS ARE TO MEET THE CRITERIA FOR BOTH THE PARALLEL AND PERPENDICULAR PUBLIC SIDEWALK CURB RAMPS. (SEE DETAILED DRAWING NO. 608-25 AND THIS DRAWING.)



DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	608-30
SECTION 608	
PARALLEL PUBLIC SIDEWALK CURB RAMPS	
EFFECTIVE: DECEMBER 2002	
 MONTANA DEPARTMENT OF TRANSPORTATION  MONTANA CADD	



Diagram illustrating the cross-section of a curb and gutter assembly, showing various dimensions and components:

- SIDEWALK (R/W PERMITTING, SEE NOTE 7)**: Indicated by a dashed line and arrow pointing to the sidewalk area.
- B**: Dimension indicating the width of the sidewalk or curb base.
- C**: Dimension indicating the height of the curb or gutter.
- FLARED SIDES**: Indicated by arrows pointing to the sloped sides of the gutter.

A technical diagram of a street corner. On the left is a rectangular sidewalk area divided into four squares by a horizontal and vertical line. An arrow points to this area with the text "SIDEWALK (R/W PERMITTING, SEE NOTE 7)". To the right of the sidewalk is a curved "FLARED SIDE" of a road. Two dimension lines labeled "M" indicate the width of the sidewalk at the top and bottom corners. Two dimension lines labeled "D" indicate the depth of the flared side at the top and bottom corners. A dimension line labeled "W" indicates the width of the flared side at its midpoint. The diagram uses solid lines for the sidewalk and flared side, and dashed lines for the dimension lines.

LOCATION OF LAYDOWN CURB IN CURB RETURNS AT PRIVATE APPROACH OR SIDE STREET WITHOUT SIDEWALK




MAIN STREET

W

A

MAXIMUM 2% SLOPE ON LANDING

PRIVATE APPROACH OR SIDE STREET




SECTION A-A


NOTE: SINGLE DIAGONAL PUBLIC SIDEWALK CURB RAMPS SERVING TWO STREET CROSSING DIRECTIONS ARE NOT PERMITTED IN NEW CONSTRUCTION.

1. THE DESIRABLE WIDTH OF THE CURB RAMP (DIMENSION "W" ABOVE) IS 4 FEET. THE MINIMUM WIDTH IS 3 FEET.
2. THE DESIRABLE CURB RAMP SLOPE IS 1:12 OR FLATTER. THE MAXIMUM CURB RAMP SLOPE IS 1:10, PROVIDED THE RISE (DIMENSION "Y" ABOVE) IS 6 INCHES OR LESS.
3. THE DESIRABLE LANDING LENGTH IS 4 FEET. THE MINIMUM LANDING LENGTH IS 3 FEET.  
NOTE: IF EXISTING RIGHT-OF-WAY OR OTHER OBSTRUCTIONS REDUCE THE LANDING LENGTH TO LESS THAN 4 FEET, THE MAXIMUM FLARED SIDE SLOPE IS 1:12.
4. THE MAXIMUM FLARED SIDE SLOPE IS 1:10.


5. THE MAXIMUM CROSS SLOPE OF THE SIDEWALK IS 1:50 (2%).
6. THE SURFACE OF THE PUBLIC SIDEWALK RAMP IS TO CONTRAST VISUALLY WITH THE ADJOINING PUBLIC SIDEWALK SURFACES. THIS CAN BE OBTAINED BY USE OF COLORED CONCRETE, PATTERNING THE CONCRETE SURFACE OR OTHER APPROVED METHODS.
7. IF R/W DOES NOT PERMIT LANDINGS FOR THESE RAMPs, USE ANOTHER RAMP DESIGN.
8. PEDESTRIAN ACCESS POINTS AT CROSSWALKS ARE TO BE WHOLLY CONTAINED WITHIN THE CROSSWALK LINES.
9. WHERE EXISTING SITE DEVELOPMENT CONDITIONS PROHIBIT THE STRICT AND FULL COMPLIANCE OF ALL ADA CRITERIA, PROVIDE ACCESSIBILITY TO THE MAXIMUM EXTENT FEASIBLE.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	608-35
SECTION 608	
DIAGONAL PUBLIC SIDEWALK CURB RAMPS	
EFFECTIVE: DECEMBER 2002	
	MONTANA DEPARTMENT OF TRANSPORTATION
	MONTANA CADD





PLAN




SECTION A-A

NOTE: THE WIDTH WITH PROPORTIONAL INVERT VARIES TO SATISFY THE DESIGN REQUIREMENTS OF INDIVIDUAL APPLICATIONS.

DETAILED DRAWING	DWG. NO.
REFERENCE STANDARD SPEC. SECTION 609	609-00
CONCRETE VALLEY GUTTER	
EFFECTIVE: AUGUST 1999	
MONTANA DEPARTMENT OF TRANSPORTATION	MONTANA CADD

## CONCRETE CURBS



CURB & GUTTER SECTION  
0.048 C.Y. CONC. PER 1.0' OF CURB FOR 6" GUTTER. \*

### JOINTS:

(A) WHEN INTEGRAL WITH, TIED TO, OR PLACED AGAINST PORTLAND CEMENT CONCRETE PAVEMENT (P.C.C.P.): MATCH TRANSVERSE CONTRACTION AND/OR EXPANSION JOINTS IN THE ADJACENT P.C.C.P. SLAB. IF REQUIRED, EXTEND  $\frac{1}{2}$ " MIN. WIDTH PREFORMED EXPANSION JOINTS COMPLETELY THROUGH CURB AND GUTTER THE SAME WIDTH AS THE P.C.C.P. SLAB JOINT. FILL CURB AND GUTTER EXPANSION JOINTS WITH PREFORMED EXPANSION JOINT FILLER.

(B) ALL OTHER CASES: SPACE CONTRACTION JOINTS IN CURB AND GUTTER AT 10 FT. INTERVALS EXCEPT AS SPECIFIED IN (A) ABOVE. EXTEND  $\frac{1}{2}$ " MIN. WIDTH EXPANSION JOINTS COMPLETELY THROUGH CURB AND GUTTER AT 100 FEET MAXIMUM INTERVALS AND FILL WITH PREFORMED EXPANSION JOINT FILLER.

(C) CONTRACTION JOINTS: CONTRACTION JOINTS ARE  $\frac{1}{8}$ " MIN. AND  $\frac{3}{8}$ " MAX. IN WIDTH. FORM JOINTS BY SAWING OR SCORING TO A MINIMUM DEPTH OF 1". FORM SCORED JOINTS BY A TOOL WHICH WILL LEAVE ROUNDED CORNERS AND DESTROY AGGREGATE INTERLOCK TO A MINIMUM DEPTH OF 1".

(D) OTHER JOINTS: SEPARATE THE CURB AND GUTTER FROM ADJACENT SIDEWALK AT POINTS SHOWN ON DTL. DWG. NO. 608-05 BY  $\frac{1}{2}$ " MIN. WIDTH OF PREFORMED EXPANSION JOINT MATERIAL. PLACE PREFORMED EXPANSION JOINT MATERIAL AT ALL CURB RETURNS, BRIDGES, DROP INLETS, AND WHERE MEETING CURB AND GUTTER IN PLACE.

(E) USE PREFORMED EXPANSION JOINT FILLER MEETING THE REQUIREMENTS OF STD. SPEC. 707.

### RADII:


MINIMUM CURB RETURN RADII = 10'. 15' RADII ARE DESIRABLE FOR STREETS.

### CONCRETE:


UNLESS OTHERWISE SPECIFIED, CONSTRUCT CONCRETE CURBS AND CONCRETE INTEGRAL CURB AND GUTTER WITH CLASS "D" CONCRETE OR APPROVED EQUAL.

\* QUANTITIES FOR ESTIMATING PURPOSES ONLY.

## BITUMINOUS CURBS



CURB SECTION  
1 CUBIC FOOT OF MATERIAL WILL MAKE ABOUT 8 LINEAR FEET OF CURB. \*



GUTTER SECTION  
1 CUBIC FOOT OF MATERIAL WILL MAKE ABOUT 5 LINEAR FEET OF CURB. \*

### NOTES:

WHEN CURB IS USED IN CONJUNCTION WITH GUARDRAIL, USE THE 4" TYPE. OTHERWISE, THE CONTRACTOR MAY USE EITHER SECTION.


CONFORM ALL MATERIALS AND CONSTRUCTION TO THE STANDARD SPECIFICATIONS FOR BITUMINOUS CURB.



CONCRETE MAY BE SUBSTITUTED FOR THE BITUMINOUS MATERIAL. WHEN CONCRETE IS USED, CONSTRUCT CURB IN ACCORDANCE WITH STANDARD SPECIFICATION 609.


GRAVEL BASE IS INCLUDED IN THE SURFACING SECTION.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 609	DWG. NO. 609-05
MISCELLANEOUS CURBS	
EFFECTIVE: JANUARY 2004	
MONTANA DEPARTMENT OF TRANSPORTATION	MONTANA CADD







DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 609	DWG. NO. 609-10
MEDIAN CONCRETE CURBS	
EFFECTIVE: DECEMBER 2002	
 MONTANA DEPARTMENT OF TRANSPORTATION	
 MONTANA CADD	




- ① INSTALL PREFORMED EXPANSION JOINT FILLER, STD. SPEC. 707.01.3, AT ALL EXPANSION JOINTS, FOR THE FULL THICKNESS OF THE CONCRETE MEDIAN CAP.
- ② ALL JOINTS MUST BE STRAIGHT AND PERPENDICULAR TO THE CENTERLINE AND THE SURFACE OF THE MEDIAN CAP. WHERE PRACTICAL, ALIGN ALL JOINTS WITH LIKE JOINTS IN ADJOINING WORK. USE JOINTS TO OUTLINE ALL PANELS IN THE MEDIAN CAP. USE SQUARE PANELS WHEN PRACTICAL. ON NARROW MEDIAN CAPS RECTANGULAR SHAPED PANELS ARE ACCEPTABLE.
- ③ CONTRACTION JOINTS MAY NOT BE MORE THAN  $\frac{1}{8}$ " WIDE AND NOT LESS THAN 1" IN DEPTH AND MAY BE CUT BY A GROOVE FORMING TOOL.
- ④ LOCATE EXPANSION JOINTS AT ALL JOINTS BETWEEN THE MEDIAN CAP AND MEDIAN CURB, AT ALL JOINTS BETWEEN THE MEDIAN CAP AND STRUCTURES IN PLACE, AND AT INTERVALS EQUAL TO THE NEAREST MULTIPLE OF THE CONTRACTION JOINT INTERVAL, BUT NOT GREATER THAN 60 FEET. USE A LONGITUDINAL EXPANSION JOINT IN THE CENTERLINE OF ALL MEDIAN CAPS WIDER THAN 12 FEET.
- ⑤ USE LONGITUDINAL CONTRACTION JOINTS IN MEDIAN CAPS WIDER THAN 6 FEET, WITH SPACING NOT TO EXCEED 6 FEET. SPACE TRANSVERSE CONTRACTION JOINTS EQUAL TO THE LONGITUDINAL SPACING ON MEDIAN CAPS WIDER THAN 6 FEET. FOR MEDIAN CAPS NARROWER THAN 6 FEET, SPACE TRANSVERSE CONTRACTION JOINTS 10 FEET OR LESS.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 609	DWG. NO. 609-12
CONCRETE MEDIAN CAPS	
EFFECTIVE: DECEMBER 2002	
 MONTANA DEPARTMENT OF TRANSPORTATION	
	




This Frame left blank







NOTES:

- ① PLACE TOPSOIL ON THE SURFACING INSLOPE TO A DEPTH OF 4" (±) NOT LESS THAN 2'-0" FROM THE EDGE OF PAVEMENT. FEATHER TOPSOIL TO THE EDGE OF PAVEMENT.
- ② SEED AREAS BEYOND THE CONSTRUCTION LIMITS WITHIN THE RIGHT-OF-WAY OR PERMIT BOUNDARIES THAT HAVE BEEN DISTURBED (i.e. STAGING AREAS, TOPSOIL PILES, EQUIPMENT TRAILS, etc.)
- ③ SALVAGE SUFFICIENT AMOUNTS OF TOPSOIL TO ASSURE QUANTITIES ARE AVAILABLE TO COVER ALL CLEARED AND GRUBBED AREAS WITH 4" OF TOPSOIL. IF QUANTITIES ARE NOT AVAILABLE, RE-SPREAD TOPSOIL TO AN EVEN DEPTH ACROSS ALL DISTURBED GROUND.


SEEDING		
AREA NO.	DEFINITION	TREATMENT
1	3:1 OR FLATTER SLOPES	CONDITION SEEDBED, SEED & FERTILIZE
2	STEEPER THAN 3:1 SLOPES	SEED, FERTILIZE & MULCH
3	15' OR TO THE EDGE OF THE SURFACING INSLOPE, WHICHEVER IS GREATER	CONDITION SEEDBED & SEED

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 610	DWG. NO. 610-00
TOPSOIL AND SEEDING	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION	







NOTE: WELD CROSSBARS TO 2 1/2" x 2 1/2" x 3/8" x 2'-1 1/2" ANGLES HINGED AREA ONLY. SEE HINGE DETAIL.




NOTE: EXTEND END PLATE FROM TOP OF STRINGER TO BOTTOM OF STRINGER WITH 1'-4" OF 1/8" FILLET WELD SYMMETRICALLY DISTRIBUTED TO FLANGE AND WEB OF STRINGER. (SEE SECTION D)




NOTE: LOCK DETAIL SIMILAR EXCEPT USE 3/8" DIA. GALV. MACHINED BOLT WITH GALV. CUT WASHER & GALV. HEX NUTS INSTEAD OF WELDED STUD BOLT.



LIVE LOADING: STANDARD (HS20) LOADING



MAX. FOOTING PRESS = 1.1 TONS/SQ. FT.



NOTES:

C.G. = CATTLE GUARD.

THE CONTRACTOR HAS THE OPTION OF USING PRECAST CONCRETE BASES FOR CATTLE GUARDS. SEE DTL. DWG. NO. 611-15.

FOR CATTLE GUARDS ON FIELD OR PRIVATE APPROACHES, THE PRECAST CONCRETE BASES IN DTL. DWG. NO. 611-10 MAY BE USED.


USE AN EVEN NUMBER OF STEEL CATTLE GUARD GRATES WHEN A CROWNED INSTALLATION IS REQUIRED.

SEE DTL. DWG. NO. 611-05 FOR CAST-IN-PLACE CATTLE GUARD REBAR DETAILS.

STRUCTURAL STEEL IS TO CONFORM TO AASHTO M270 GRADE 36.

ANCHOR BOLTS ARE TO CONFORM TO AASHTO M314 GRADE 36.


ALL NUTS, BOLTS, AND WASHERS ARE TO CONFORM TO ASTM A307 AND BE GALVANIZED PER AASHTO M232.



DETAILED DRAWING	
REFERENCE	DWG. NO.
SECTION 611	611-00
CAST-IN-PLACE CATTLE GUARD	
EFFECTIVE: JANUARY 2004	
MONTANA DEPARTMENT OF TRANSPORTATION	MONTANA CADD



This Frame left blank




16 FT. C. G.					30 FT. C. G.				
MARK	SIZE	NO.	TYPE	LENGTH	MARK	SIZE	NO.	TYPE	LENGTH
B1	#4	12	STR.	16' - 9"	B1	#4	12	STR.	30' - 9"
B2	#4	22	1	6' - 9"	B2	#4	42	1	6' - 9"
B3	#4	6	STR.	7' - 7"	B3	#4	12	STR.	7' - 7"
B4	#4	4	2	5' - 8"	B4	#4	8	2	5' - 8"
B5	#4	6	3	10' - 7"	B5	#4	6	3	10' - 7"
ESTIMATED WT. = 321 LB.					ESTIMATED WT. = 569 LB.				


20 FT. C. G.					32 FT. C. G.				
MARK	SIZE	NO.	TYPE	LENGTH	MARK	SIZE	NO.	TYPE	LENGTH
B1	#4	12	STR.	20' - 9"	B1	#4	12	STR.	32' - 9"
B2	#4	28	1	6' - 9"	B2	#4	44	1	6' - 9"
B3	#4	6	STR.	7' - 7"	B3	#4	18	STR.	7' - 7"
B4	#4	4	2	5' - 8"	B4	#4	12	2	5' - 8"
B5	#4	6	3	10' - 7"	B5	#4	6	3	10' - 7"
ESTIMATED WT. = 381 LB.					ESTIMATED WT. = 640 LB.				

24 FT. C. G.					36 FT. C. G.				
MARK	SIZE	NO.	TYPE	LENGTH	MARK	SIZE	NO.	TYPE	LENGTH
B1	#4	12	STR.	24' - 9"	B1	#4	12	STR.	36' - 9"
B2	#4	34	1	6' - 9"	B2	#4	50	1	6' - 9"
B3	#4	6	STR.	7' - 7"	B3	#4	12	STR.	7' - 7"
B4	#4	4	2	5' - 8"	B4	#4	8	2	5' - 8"
B5	#4	6	3	10' - 7"	B5	#4	6	3	10' - 7"
ESTIMATED WT. = 440 LB.					ESTIMATED WT. = 654 LB.				

40 FT. C. G.				
MARK	SIZE	NO.	TYPE	LENGTH
B1	#4	12	STR.	40' - 9"
B2	#4	54	1	6' - 9"
B3	#4	18	STR.	7' - 7"
B4	#4	12	2	5' - 8"
B5	#4	6	3	10' - 7"
ESTIMATED WT. = 749 LB.				



BENT BARS  
(TYPES 1 AND 2)



B1 AND B3 STRAIGHT BARS

REBAR DETAILS

ESTIMATED CLASS "A" CONC. QUANTITIES		
16' C. G. =	4.76	C. Y.
20' C. G. =	5.69	C. Y.
24' C. G. =	6.61	C. Y.
30' C. G. =	8.51	C. Y.
32' C. G. =	9.48	C. Y.
36' C. G. =	9.90	C. Y.
40' C. G. =	11.33	C. Y.













NOTES:

C. G. = CATTLE GUARD.

CONCRETE QUANTITIES WERE FIGURED WITHOUT A CROWN, INCREASE WHEN A CROWNED INSTALLATION IS USED.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 611	DWG. NO. 611-05
CAST-IN-PLACE CATTLE GUARD REBAR DETAILS	
EFFECTIVE: JANUARY 2004	
MONTANA DEPARTMENT OF TRANSPORTATION	MONTANA CADD





NOTES:

C.G. = CATTLE GUARD.

USE ONLY ON FIELD OR PRIVATE APPROACHES.

PROVIDE CAST-IN ANCHOR BOLTS AS SHOWN IN DTL. DWG. NO. 611-00 AT THE APPROPRIATE LOCATIONS. CAST-IN LAG PLATES, SIMILAR TO THOSE SHOWN IN DTL. DWG. NO. 611-15, MAY ALSO BE USED.

FOR DETAILS OF STEEL GRATES AND STEEL WINGS SEE DTL. DWG. NO. 611-00.












BILL OF REINFORCING STEEL *				
MARK	SIZE	NO.	TYPE	LENGTH
6'-0" SECTION - PANEL A				
B1	#4	4	STRAIGHT	5'-9"
B6	#3	7	2	3'-5"
ESTIMATED WT. = 24 LB.				
8'-0" SECTION - PANEL B				
B1	#4	2	STRAIGHT	7'-9"
B2	#4	2	STRAIGHT	5'-9"
B3	#4	4	STRAIGHT	2'-2"
B4	#3	7	1	3'-7"
B5	#3	4	3	2'-7"
ESTIMATED WT. = 37 LB.				
8'-6" SECTION - PANEL C				
B1	#4	2	STRAIGHT	8'-3"
B2	#4	2	STRAIGHT	6'-3"
B3	#4	4	STRAIGHT	2'-2"
B4	#3	8	1	3'-7"
B5	#3	4	3	2'-7"
ESTIMATED WT. = 40 LB.				
8'-6" SECTION - PANEL D				
B1	#4	4	STRAIGHT	7'-3"
B2	#4	4	STRAIGHT	2'-2"
B4	#3	8	1	3'-7"
B5	#3	4	3	2'-7"
ESTIMATED WT. = 40 LB.				
10'-6" SECTION - PANEL E				
B1	#4	2	STRAIGHT	10'-3"
B2	#4	2	STRAIGHT	8'-3"
B3	#4	4	STRAIGHT	2'-2"
B4	#3	10	1	3'-7"
B5	#3	4	3	2'-7"
ESTIMATED WT. = 48 LB.				
10'-6" SECTION - PANEL F				
B1	#4	4	STRAIGHT	9'-3"
B2	#4	4	STRAIGHT	2'-2"
B4	#3	10	1	3'-7"
B5	#3	4	3	2'-7"
ESTIMATED WT. = 48 LB.				
12'-6" SECTION - PANEL G				
B1	#4	2	STRAIGHT	12'-3"
B2	#4	2	STRAIGHT	10'-3"
B3	#4	4	STRAIGHT	2'-2"
B4	#3	12	1	3'-7"
B5	#3	4	3	2'-7"
ESTIMATED WT. = 56 LB.				
12'-6" SECTION - PANEL H				
B1	#4	4	STRAIGHT	11'-3"
B2	#4	4	STRAIGHT	2'-2"
B4	#3	12	1	3'-7"
B5	#3	4	3	2'-7"
ESTIMATED WT. = 56 LB.				

\* FOR ONE PANEL ONLY

ESTIMATED CLASS "D" CONCRETE QUANTITIES	
6'-0" SECTION - PANEL A	= 0.20 C.Y.
8'-0" SECTION - PANEL B	= 0.26 C.Y.
8'-6" SECTION - PANEL C	= 0.28 C.Y.
8'-6" SECTION - PANEL D	= 0.28 C.Y.
10'-6" SECTION - PANEL E	= 0.35 C.Y.
10'-6" SECTION - PANEL F	= 0.35 C.Y.
12'-6" SECTION - PANEL G	= 0.43 C.Y.
12'-6" SECTION - PANEL H	= 0.43 C.Y.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	611-10
SECTION 611	
PRECAST CONCRETE BASE FOR CATTLE GUARD - APPROACHES	
EFFECTIVE: JANUARY 2004	
MONTANA DEPARTMENT OF TRANSPORTATION	MONTANA CADD





#### NOTES:

C.G. = CATTLE GUARD.

USE SPLICE CONNECTIONS WHEN A CROWNED INSTALLATION IS REQUIRED.

SEE DTL. DWG. NO. 611-20 FOR ADDITIONAL PRE-CAST CONCRETE CATTLE GUARD BASE AND MATERIAL QUANTITY DETAILS.

SEE DTL. DWG. NO. 611-00 FOR DETAILS OF STEEL GRATES AND STEEL WINGS.



#### INSTALLATION PROCEDURE:

EXCAVATE 2'-0" BELOW THE ELEVATION OF THE BOTTOM OF THE CATTLE GUARD BASE. EXTEND THE EXCAVATION HORIZONTALLY AT LEAST 1'-0" IN ALL DIRECTIONS BEYOND THE CATTLE GUARD BASE'S EXTERIOR DIMENSION.

FILL THE EXCAVATION TO THE LEVEL OF THE BOTTOM OF THE CATTLE GUARD BASE WITH FILL MATERIAL OF AASHTO GRADE A-1-a OR BETTER, COMPACTED TO 95% OF PROCTOR DENSITY.


AFTER PLACING THE CATTLE GUARD, FILL THE EXTERIOR PORTION OF THE EXCAVATION TO GRADE WITH THE SAME MATERIAL.

FILL THE INTERIOR OF THE CATTLE GUARD BASE TO A DEPTH OF 1'-6" WITH THE SIMILARLY COMPACTED MATERIAL.


DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	611-15
SECTION 611	
PRECAST CONCRETE BASE FOR CATTLE GUARD	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD




This Frame left blank



LAG PLATE CONNECTION DETAIL



LATERAL SUPPORT REBAR DETAIL



NOTES:

C.G. = CATTLE GUARD.

ALL HARDWARE IS TO BE PRIMER PAINTED.

ALL STEEL HARDWARE IS TO CONFORM TO AASHTO M270 GRADE 36.

ALL NUTS, BOLTS, AND WASHERS ARE TO CONFORM TO ASTM A307 AND BE GALVANIZED PER AASHTO M232.

ESTIMATED CLASS "DD" CONCRETE QUANTITIES
16'-0" C.G. = 5.68 C.Y.
20'-0" C.G. = 6.81 C.Y.
24'-0" C.G. = 7.93 C.Y.
* 24'-0" C.G. = 7.93 C.Y.
30'-0" C.G. = 9.62 C.Y.
32'-0" C.G. = 10.18 C.Y.
36'-0" C.G. = 11.31 C.Y.
40'-0" C.G. = 12.43 C.Y.

---



---

40' - 0" C.G. = 12.

---



---

QUANTITIES AND DIMENSIONS ARE APPROXIMATE ONLY BASED ON ONE COMPLETE CATTLE GUARD.														
NOMINAL C. G. SIZE	REINFORCING STEEL (NO. 4 BARS / GRADE 60)								MISC. STEEL					
	A1		A2		A3		A4		ESTIMATED WT.		LAG PLATES		SPLICE CONNECTION	ESTIMATED WT. LB.
	REQUIRED	LENGTH	REQUIRED	LENGTH	REQUIRED	LENGTH	REQUIRED	LENGTH	LB.		REQUIRED	LENGTH		
16'-0"	18	16'-2"	36	7'-10"	8	9'-1 1/2"	14	4'-10"	477		8	2'-8"	NO	39
20'-0"	18	20'-2"	44	7'-10"	8	9'-1 1/2"	14	4'-10"	567		8	3'-6"	NO	52
24'-0"	18	24'-2"	52	7'-10"	8	9'-1 1/2"	14	4'-10"	657		8	4'-6"	NO	66
* 24'-0"	36	11'-11"	52	7'-10"	8	9'-1 1/2"	14	4'-10"	653		8	4'-6"	YES	323
30'-0"	36	14'-11"	64	7'-10"	8	9'-1 1/2"	14	4'-10"	788		12	3'-6"	YES	334
32'-0"	36	15'-11"	68	7'-10"	8	9'-1 1/2"	14	4'-10"	833		16	2'-8"	YES	335
36'-0"	36	17'-11"	76	7'-10"	8	9'-1 1/2"	14	4'-10"	923		12	4'-6"	YES	356
40'-0"	36	19'-11"	84	7'-10"	8	9'-1 1/2"	14	4'-10"	1013		16	3'-6"	YES	360

\* 24' -0" CATTLE GUARD WITH OPTIONAL SPLICE

REFERENCE STANDARD SPEC. SECTION 611	DETAILED DRAWING	DWG. NO. 611-20
--	------------------	--------------------


## PRECAST CONCRETE CATTLE GUARD BASE DETAILS

EFFECTIVE: JANUARY 2004





ROUND PIPE




SIDE ELEVATION

FRONT ELEVATION

FRONT ELEVATION MULTIPLE PIPES

ARCH PIPE





SIDE ELEVATION


FRONT ELEVATION

FRONT ELEVATION MULTIPLE PIPES


NOTES:  
ALL CONCRETE IS CLASS  
"DD" OR EQUAL.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	613-06
SECTION 613	
CONCRETE EDGE PROTECTION FOR METAL CULVERTS	
EFFECTIVE: DECEMBER 2002	
	MONTANA DEPARTMENT OF TRANSPORTATION
	MONTANA CADD


ARCH PIPE




FRONT ELEVATION



SIDE ELEVATION




FRONT ELEVATION




SIDE ELEVATION

SECTION A-A



FRONT ELEVATION MULTIPLE PIPES



FRONT ELEVATION MULTIPLE PIPES







DETAILED DRAWING  
REFERENCE DWG. NO.  
STANDARD SPEC. 613-08  
SECTION 603.613

CONCRETE EDGE PROTECTION  
FOR CONCRETE CULVERTS

EFFECTIVE: DECEMBER 2002  
 MONTANA DEPARTMENT  
OF TRANSPORTATION

NOTES:  
ALL CONCRETE IS CLASS  
"DD" OR EQUAL.





CAST-IN-PLACE CONCRETE:

LOCATE JOINTS AS INDICATED ON THE PLANS. IF CONSTRUCTION IS STOPPED FOR OVER TWO HOURS, CREATE A CONSTRUCTION JOINT. USE CLASS "D" CONCRETE FOR ALL CAST-IN-PLACE CONCRETE.

USE AN APPROVED 1/2" EXPANSION JOINT FILLER WHENEVER THE CAST-IN-PLACE CONCRETE ABUTS AGAINST ANY PART OF THE BRIDGE STRUCTURE.


CLEAR THE EMBANKMENT SLOPE OF ALL BRUSH, DEBRIS AND RUBBLE. A CUSHION IS NOT REQUIRED FOR GRAVEL EMBANKMENT SLOPES. FINISH ALL SLOPES TO A REASONABLY UNIFORM SURFACE OR TO THE SLOPE INDICATED IN THE BRIDGE PLANS. COMPACT ALL LOOSE MATERIAL TO THE SATISFACTION OF THE ENGINEER. LEAVE THE ADJACENT SLOPE AREA IN A SMOOTH, UNIFORM CONDITION.

REINFORCING STEEL:

(MAY USE EITHER ALTERNATE LISTED BELOW)

1. #3 BARS AT 10" O.C. (HORIZONTAL AND VERTICAL SPACING) MIN. COVER OF 2"
2. 6" x 6" x W2.9 WIRE MESH

12" OVERLAP REQUIRED AT CONSTRUCTION JOINTS FOR REINFORCING STEEL AND WIRE MESH.



### VERTICAL AND HORIZONTAL CONSTRUCTION JOINT



USE AS NEEDED IN PLACING SLAB.  
WHEN REQUIRED, USE IN LIEU OF  
A DIMENSION JOINT AT THE SAME  
SPACING AS A DIMENSION JOINT.

JOINTS MAY BE SAWED, MADE WITH GROOVING TOOLS OR REMOVABLE INSERTS OF AN APPROVED TYPE.


IF JOINTS ARE TO BE SAWED, SAW JOINTS JUST AFTER CONCRETE HAS SET BUT BEFORE UNCONTROLLED CRACKING OCCURS.

### VERTICAL AND HORIZONTAL DIMENSION JOINT

6' VERTICAL SPACING OR AS NOTED.  
8' HORIZONTAL SPACING OR AS NOTED.  
JOINTS MAY BE SAWED, MADE WITH  
GROOVING TOOLS OR REMOVABLE  
INSERTS OF AN APPROVED TYPE.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 613	DWG. NO. 613-10
CONCRETE SLOPE PROTECTION	
EFFECTIVE: AUGUST 1999	
	MONTANA DEPARTMENT OF TRANSPORTATION
	MONTANA CADD





CHAMFER ALL EXPOSED CORNERS 1". REINFORCING STEEL TO BE NOT LESS THAN 1/2" TO NEAREST FACE OF CONCRETE.

INLET AND OUTLET HEADWALLS FOR RCP									
CULVERT		CL. "DD" CONC. OR EQUAL (C. Y.)		DIMENSION TABLE					
DIA. D	AREA (SQ. FT.)	INLET	OUTLET	A	B	H	L	L'	F
18"	1.77	0.80	0.60	1'-3"	1'-3"	2'-6"	2'-6"	1'-9"	6 1/2"
24"	3.14	1.00	0.86	1'-6"	1'-6"	3'-0"	3'-0"	2'-1"	7"
30"	4.91	1.42	1.14	1'-9"	1'-9"	3'-6"	3'-6"	2'-6"	7 1/2"
36"	7.07	1.84	1.43	2'-0"	2'-0"	4'-0"	4'-0"	2'-10"	8"
42"	9.62	2.12	1.73	2'-3"	2'-3"	4'-6"	4'-6"	3'-2"	8 1/2"
48"	12.57	2.34	2.07	2'-6"	2'-6"	5'-0"	5'-0"	3'-6"	9"


INLET AND OUTLET HEADWALLS FOR CMP									
CULVERT		CL. "DD" CONC. OR EQUAL (C. Y.)		DIMENSION TABLE					
DIA. D	AREA (SQ. FT.)	INLET	OUTLET	A	B	H	L	L'	F
18"	1.77	0.73	0.59	1'-3"	1'-3"	2'-6"	2'-6"	1'-9"	6"
24"	3.14	0.91	0.76	1'-6"	1'-6"	3'-0"	3'-0"	2'-1"	6"
30"	4.91	1.06	0.95	1'-9"	1'-9"	3'-6"	3'-6"	2'-6"	6"
36"	7.07	1.68	1.11	2'-0"	2'-0"	4'-0"	4'-0"	2'-10"	6"
42"	9.62	2.10	1.40	2'-3"	2'-3"	4'-6"	4'-6"	3'-2"	6"
48"	12.57	2.32	1.66	2'-6"	2'-6"	5'-0"	5'-0"	3'-6"	6"

DETAILED DRAWING  
REFERENCE DWG. NO.  
STANDARD SPEC. 613-12  
SECTION 613

INLET AND OUTLET  
HEADWALLS FOR  
RCP AND CMP PIPES

EFFECTIVE: AUGUST 1999

MONTANA DEPARTMENT OF TRANSPORTATION



NOTES:

KEY ENDS OF RIPRAP WALLS INTO THE EMBANKMENT SLOPES A MINIMUM OF 2 FEET FROM OUTER FACE OF THE RIPRAP FOR THE FULL HEIGHT OF THE RIPRAP WALL.

SEE SPECIFICATIONS FOR GRADATION, CLASS AND CONSTRUCTION METHODS.


DETAILED DRAWING  
REFERENCE DWG. NO.  
STANDARD SPEC. 613-14  
SECTION 613

CULVERT RIPRAP

EFFECTIVE: DECEMBER 2002

MONTANA DEPARTMENT OF TRANSPORTATION






**EMBANKMENT PROTECTION**

MINIMUM T FOR:  
 CLASS I RIPRAP = 1.5'  
 CLASS II RIPRAP = 2.5'  
 CLASS III RIPRAP = 3.0'

DETAILED DRAWING	
REFERENCE DWG. NO.	613-16
STANDARD SPEC.	SECTION 613, 622
EMBANKMENT PROTECTION	
EFFECTIVE: AUGUST 1999	



**CONCRETE:**


USE CLASS "AC" OR "DC" CONCRETE UNLESS OTHERWISE NOTED, CONFORMING TO SECTION 551 OF THE STANDARD SPECIFICATIONS. CONCRETE MAY BE PNEUMATICALLY APPLIED.

**\* BANK PROTECTION:**


USE TYPE III BANK PROTECTION, CONFORMING TO SUBSECTION 613.03.2 OF THE STANDARD SPECIFICATIONS. THICKNESS IS 12" MIN.

**INLET CONDITIONS:**


DEPRESS THE INLET BELOW THE NATURAL DRAINAGE BASIN TO PREVENT FLOW FROM SIDE CHANNELING OVER THE SLOPE BEFORE REACHING THE CHUTE.



SECTION C-C




SECTION B-B



SECTION A-A


TYPE	DIMENSIONS			QUANTITIES
	A	B	C	
1	2'-0"	4'-0"	0'-4"	0.7 C.Y. + N x 0.051 C.Y./L.F.
2	2'-0"	4'-0"	1'-0"	0.9 C.Y. + N x 0.056 C.Y./L.F.
3	4'-0"	8'-0"	1'-0"	2.2 C.Y. + N x 0.105 C.Y./L.F.
4	4'-0"	8'-0"	1'-6"	2.3 C.Y. + N x 0.111 C.Y./L.F.








DETAILED DRAWING	
REFERENCE DWG. NO.	613-18
STANDARD SPEC.	SECTION 551, 613
CONCRETE DRAINAGE CHUTE	
EFFECTIVE: AUGUST 1999	






This Frame left blank







STOP GROOVE DETAIL



DIMENSIONS AND QUANTITIES							
	B	C	H	L	W	"DD" CONC. OR EQUAL (C.Y.)	REINFORCING STEEL (LB.)
TYPE I	2'-0"	3'-0"	2'-0"	6'-0"	8'-0"	1.5	114.0
	2'-6"	3'-6"	2'-0"	6'-0"	9'-6"	1.7	124.4
	3'-0"	4'-0"	2'-6"	6'-0"	11'-0"	2.2	129.0
TYPE II	2'-0"	3'-0"	2'-0"	9'-6"	8'-0"	2.0	152.0
	2'-6"	3'-6"	2'-0"	11'-0"	9'-6"	2.4	190.0
	3'-0"	4'-0"	2'-6"	12'-6"	11'-0"	3.3	250.8
TYPE III	2'-0"	3'-0"	2'-0"	11'-0"	8'-0"	2.8	212.8
	2'-6"	3'-6"	2'-0"	12'-6"	9'-6"	3.4	258.4
	3'-0"	4'-0"	2'-6"	14'-0"	11'-0"	4.6	349.6
TYPE IV	2'-0"	3'-0"	2'-0"	11'-0"	8'-0"	3.4	266.0
	2'-6"	3'-6"	2'-0"	12'-6"	9'-6"	4.2	319.2
	3'-0"	4'-0"	2'-6"	14'-0"	11'-0"	5.6	425.6


NOTES:

DIVISION BOX MAY BE MODIFIED IF DESIRED WITH DIMENSIONS SHOWN ON THE PLANS.

QUANTITIES ARE FOR ESTIMATING PURPOSES ONLY.


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 552, 615	DWG. NO. 615-04
STANDARD CONCRETE IRRIGATION DIVISION BOXES	
EFFECTIVE: AUGUST 1999	
MONTANA DEPARTMENT OF TRANSPORTATION	MONTANA CADD






ISOMETRIC VIEW OF TRANSITION

PLACE REBAR IN CENTER OF WALLS, SLAB, ETC. UNLESS OTHERWISE SPECIFIED.




SECTION B-B

SPACE REINFORCING BARS APPROX. 12" EACH WAY THROUGHOUT STRUCTURE. USE CONTINUOUS BARS IN FLOORS AND WALLS WHENEVER POSSIBLE. WHEN SPLICES ARE MADE, LAP REINFORCING BAR 1'-6".




ELEVATION




PLAN VIEW

\* WIDTH OF CHANNEL BOTTOM (VARIABLE - SEE TABLE)



SECTION A-A FOR CSP



SECTION A-A FOR RCP

CHAMFER ALL EXPOSED CORNERS TO 1".

INLET AND OUTLET CONCRETE TRANSITIONS FOR CSP																			
CULVERT		DIMENSIONS								QUANTITIES									
										B = D		B = D + 1'-0"		B = D + 2'-0"					
DIA.	D	AREA (SQ. FT.)	J	H	L	T2	W	K	Y	G	B	CL"DD" CONC. (C. Y.)	#4 REBAR (LB.)	B	CL"DD" CONC. (C. Y.)	#4 REBAR (LB.)	B	CL"DD" CONC. (C. Y.)	#4 REBAR (LB.)
18"	1.77	0.45	3'-5"	3'-0"	6"	2'-9"	0.35	1'-3"	2'-0"	1'-6"	0.8	66	2'-6"	0.9	73	3'-6"	1.0	81	
24"	3.14	0.61	4'-0"	4'-0"	6"	3'-3"	0.46	1'-6"	2'-0"	2'-0"	1.2	94	3'-0"	1.3	103	4'-0"	1.4	112	
30"	4.91	0.76	4'-6"	5'-0"	6"	3'-9"	0.58	1'-9"	2'-0"	2'-6"	1.6	124	3'-6"	1.7	134	4'-6"	1.8	144	
36"	7.07	0.91	5'-1"	6'-0"	6"	4'-3"	0.70	2'-0"	2'-6"	3'-0"	2.1	162	4'-0"	2.2	173	5'-0"	2.3	184	
42"	9.62	1.10	5'-8"	7'-0"	6"	4'-9"	0.81	2'-3"	2'-6"	3'-6"	2.6	200	4'-6"	2.7	212	5'-6"	2.9	225	
48"	12.57	1.20	6'-3"	8'-0"	8"	5'-3"	0.93	2'-6"	2'-6"	4'-0"	4.1	245	5'-0"	4.3	259	6'-0"	4.4	272	

INLET AND OUTLET CONCRETE TRANSITIONS FOR RCP																				
CULVERT		DIMENSIONS										QUANTITIES								
												B = D			B = D + 1' - 0"			B = D + 2' - 0"		
DIA.	D	AREA (SQ. FT.)	J	H	L	T	T2	W	K	Y	G	B	CL"DD" CONC. (C. Y.)	#4 REBAR (LB.)	B	CL"DD" CONC. (C. Y.)	#4 REBAR (LB.)	B	CL"DD" CONC. (C. Y.)	#4 REBAR (LB.)
18"	1.77	0.45'	3' - 8"	3' - 0"	2½"	6"	3' - 2"	0.35'	1' - 3"	2' - 0"	1' - 6"	0.9	68	2' - 6"	1.0	76	3' - 6"	83	1.0	
24"	3.14	0.61'	4' - 3"	4' - 0"	3"	6"	3' - 9"	0.46'	1' - 6"	2' - 0"	2' - 0"	1.2	98	3' - 0"	1.3	107	4' - 0"	116	1.4	
30"	4.91	0.76'	4' - 10"	5' - 0"	3½"	6"	4' - 4"	0.58'	1' - 9"	2' - 0"	2' - 6"	1.7	128	3' - 6"	1.8	138	4' - 6"	149	1.9	
36"	7.07	0.91'	5' - 6"	6' - 0"	4"	6"	4' - 11"	0.70'	2' - 0"	2' - 6"	3' - 0"	2.2	168	4' - 0"	2.3	179	5' - 0"	190	2.4	
42"	9.62	1.10'	6' - 1"	7' - 0"	4½"	6"	5' - 6"	0.81'	2' - 3"	2' - 6"	3' - 6"	2.7	212	4' - 6"	2.8	224	5' - 6"	237	2.9	
48"	12.57	1.20'	6' - 8"	8' - 0"	5"	8"	6' - 1"	0.93'	2' - 6"	2' - 6"	4' - 0"	4.2	254	5' - 0"	4.3	267	6' - 0"	287	4.6	

NOTES:  
INSTALL STRUCTURES OUTSIDE THE CLEAR ZONE.  
PROVIDE TRASHRACKS WHEN REQUIRED. SEE DTL. DWG. NO. 615-02.

DETAILED DRAWING

REFERENCE DWG. NO. 615-06


STANDARD SPEC. SECTION 615

CONCRETE IRRIGATION INLET AND OUTLET TRANSITION FOR RCP AND CSP PIPES

EFFECTIVE: AUGUST 1999

MONTANA DEPARTMENT OF TRANSPORTATION



MONTANA CADD



TYPICAL RAISED POSITION

TYPICAL LOWERED POSITION

ELEVATION DIVIDED HIGHWAY INSTALLATION SHOWN



NOTES:  
\* HEIGHT OF GATE ARM GUIDES MAY VARY AS REQUIRED FOR WARNING LIGHT CLEARANCES.  
SEE DTL. DWG. NO. 617-02 FOR ADDITIONAL ROAD CLOSURE GATE DETAILS.

DETAILED DRAWING

REFERENCE DWG. NO. 617-00

STANDARD SPEC. SECTION 617

ROAD CLOSURE GATE

EFFECTIVE: AUGUST 1999



MONTANA DEPARTMENT OF TRANSPORTATION

MONTANA CADD





TYPICAL TWO-WAY, TWO-LANE INSTALLATION (1 GATE REQUIRED)

TYPICAL DIVIDED HIGHWAY INSTALLATION (2 GATES REQUIRED)











 MONTANA DEPARTMENT OF TRANSPORTATION
 









INSTALLATION REQUIREMENTS FOR TOP NUTS OF ANCHOR BOLTS  
FIELD LUBRICATE BEARING FACE AND THREADS OF TOP ANCHOR  
BOLT NUTS WITH A STICK WAX. TIGHTEN TOP NUTS TO SNUG-  
TIGHT. SNUG-TIGHT IS DEFINED AS THE TIGHTNESS THAT EXISTS  
WHEN THE GROUND BASE PLATE IS IN FIRM CONTACT WITH THE  
BOTTOM NUT. TIGHTNESS IS ATTAINED BY THE FULL EFFORT  
OF A MAN USING AN ORDINARY SPUID WRENCH. AFTER THE SNUG-  
TIGHT CONDITION IS ATTAINED, ROTATE THE TOP NUTS AN  
ADDITIONAL 45° (+20°, -0°).




DO NOT ENCLOSE ANY SLIP BOLT HEADS OR WASHERS IN GROUT AND KEEP THEM COMPLETELY MECHANICALLY ACCESSIBLE, ALLOWING BOLTS TO BE FREELY PUSHED OUT DURING VEHICLE IMPACT.

 MONTANA DEPARTMENT  
OF TRANSPORTATION





DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 617	DWG. NO. 617-10
FOUR BOLT SLIP BASE DETAILS	
EFFECTIVE: AUGUST 1999	
MONTANA DEPARTMENT OF TRANSPORTATION	MONTANA CADD




NOTES:

- RAIL STRIPES ARE 6" IN WIDTH FOR BARRICADES 3' OR GREATER IN LENGTH. FOR BARRICADES LESS THAN 3' IN LENGTH, 4" STRIPES MAY BE USED.
- THE PREDOMINANT COLOR FOR OTHER BARRICADE COMPONENTS IS WHITE, BUT UNPAINTED GALVANIZED METAL OR ALUMINUM COMPONENTS MAY BE USED.
- WHERE B(III) BARRICADES ARE TO FACE TRAFFIC FROM TWO DIRECTIONS, STRIPING ON BOTH THE FRONT AND REAR SIDES IS REQUIRED.

- USE MATERIALS FOR BARRICADE FRAMEWORK AND ASSEMBLY, INCLUDING ANY SIGNS AND MEANS OF ATTACHMENT, THAT MEET THE REQUIREMENTS FOR NCHRP 350 FOR WORK ZONE DEVICES.
- USE SANDBAGS OF SUFFICIENT WEIGHT TO HOLD THE BARRICADES IN PLACE. WATERPROOF SANDBAGS DURING PERIODS OF FREEZING WEATHER.


#### PORTABLE BARRICADES

- USE VERTICAL PANELS TO DELINEATE ROADSIDE CONSTRUCTIONS OF THE CLEAR ZONE. VERTICAL PANELS ARE NOT INTENDED TO BE USED TO DELINEATE THE TRAVELED PATH.



#### VERTICAL PANEL

(VP-1R SHOWN, REVERSE FOR VP-1L.)




ADD BALLAST ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS TO HOLD THE DRUM IN PLACE.


DRUMS HAVE CLOSED TOPS.

NOTES:

- BARRICADES OR VERTICAL PANELS DESIGNATED "R" ARE PLACED TO THE RIGHT SIDE OF APPROACHING TRAFFIC. THOSE DESIGNATED "L" ARE PLACED TO THE LEFT SIDE.
- SEE THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) PART 6 FOR ADDITIONAL INFORMATION.
- USE ASTM TYPE III REFLECTIVE SHEETING ON ALL BARRICADES AND CHANNELIZING DEVICES.





#### FLEXIBLE GUIDE POST




#### HINGED FLEXIBLE GUIDE POST

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 618	DWG. NO. 618-00
BARRICADES AND CHANNELIZING DEVICES	
EFFECTIVE: JANUARY 2004	
MONTANA DEPARTMENT OF TRANSPORTATION	MONTANA CADD







TYPICAL MULTIPLE POST INSTALLATIONS  
(FOR CONSTRUCTION SIGNING ONLY)





TYPICAL SIGN MOUNTINGS  
(FOR CONSTRUCTION SIGNING ONLY)




NOTES:


- FURNISH AND INSTALL POSTS OR POLES MEETING NCHRP 350 REQUIREMENTS.
- FURNISH POST OR POLE LENGTHS TO ACCOMMODATE THE FOUNDATION DEPTH, THE MOUNTING HEIGHT AND THE MOUNTINGS
- BACKFILL FOUNDATION HOLES IN 8" LIFTS, THOROUGHLY TAMPING EACH LIFT.
- IN HIGH WIND AREAS INSTALL LARGER POSTS OR POLES COMPLYING WITH THE FOUNDATION AND BREAKAWAY REQUIREMENTS OF DTL. DWG. NO. 619-20. THE MINIMUM POST SPACING FOR MULTIPLE POSTS LARGER THAN 4" IS 7'-0".
- VERTICAL ALIGNMENT OF SIGNS IS TO BE WITHIN 5" OF PLUMB (1" IN 1').
- USE THE URBAN MOUNTING HEIGHTS IN BUSINESS, COMMERCIAL, AND RESIDENTIAL DISTRICTS WHERE PARKING AND/OR PEDESTRIAN MOVEMENT IS LIKELY TO OCCUR, OR WHERE THERE ARE OTHER OBSTRUCTIONS TO VIEW. URBAN MOUNTING HEIGHTS MAY ALSO BE USED IN RURAL AREAS FOR INCREASED VISIBILITY.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	618-01
SECTION 618	
CONSTRUCTION SIGN DETAILS	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD






- NOTES:
- ① THE MAXIMUM WEIGHT OF THE ASSEMBLY IS 250 POUNDS.
  - ② USE A 14" WHEEL AND TIRE.
  - ③ AUTOMOTIVE AND EQUIPMENT AXLE ASSEMBLIES MAY NOT BE USED FOR TRAILER-MOUNTED SIGN SUPPORTS.
  - ④ OTHER NCHRP 350 CRASH TESTED ASSEMBLIES ARE ACCEPTABLE.




FRONT RIGHT


SIGN SUPPORT



FRONT




RIGHT




TOP

TRAILER

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	618-02
SECTION 618.715	
PORTABLE SIGN SUPPORT ASSEMBLY	
EFFECTIVE: DECEMBER 2002	




- NOTES:
- ① THIS SIGN LAYOUT IS INTENDED TO BE A PERMANENT INSTALLATION FOR THE DURATION OF THE CONSTRUCTION PROJECT, AS APPROVED BY THE ENGINEER. COVER OR REMOVE ANY SIGNS WHEN NOT IN USE, INCLUDING SPEED LIMIT SIGNS NOT WARRANTED. REMOVE ANY SIGN SUPPORTS IF THEY WILL NOT BE NEEDED WITHIN 90 DAYS.
  - ② XX = SPEED DETERMINED BY THE ENGINEER.
  - ③ INCLUDE REGULATORY SIGNING ONLY IF THE CONSTRUCTION PROJECT CONTAINS A WORK ZONE OR HAS ROADWAY CONDITIONS THAT WARRANT SPEED RESTRICTIONS. MODIFY REGULATORY SIGNS TO MATCH ADJACENT REGULATIONS.
  - ④ THE WORK ZONE REFERS TO THE AREA WITHIN THE CONSTRUCTION PROJECT WHERE WORK IS ACTUALLY TAKING PLACE.
  - ⑤ IN ADDITION TO THE SIGNS SHOWN, INCLUDE THE APPROPRIATE TWO-LANE WORK ZONE SIGNS (DTL. DWG. NO. 618-08) WHEN A WORK ZONE IS LOCATED AT THE BEGINNING OR END OF THE CONSTRUCTION PROJECT.
  - ⑥ SET UP THIS SIGN LAYOUT IN EACH TRAFFIC DIRECTION.
- \* DENOTES SIGNS THAT ARE UNIQUE TO MONTANA.



DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	618-04
SECTION 618	
TWO-LANE CONSTRUCTION PROJECT	
EFFECTIVE: JANUARY 2004	





WORK ZONE WITH NO FLAGGER


NOTES:

- ① THESE SIGN LAYOUTS WORK IN CONJUNCTION WITH THE PERMANENT LAYOUT ILLUSTRATED ON DTL. DWG. NO. 618-04 FOR WORK ZONES LOCATED AT THE BEGIN AND END OF THE CONSTRUCTION PROJECT.
- ② XX = SPEED DETERMINED BY THE ENGINEER.
- ③ INCLUDE REGULATORY SIGNING ONLY IF THERE IS REASON TO RESTRICT SPEED WITHIN THE WORK ZONE. MODIFY REGULATORY SIGNS TO MATCH ADJACENT REGULATIONS.
- ④ SET UP THIS SIGN LAYOUT IN EACH TRAFFIC DIRECTION. COMBINE SUCCESSIVE WORK ZONES WHEN LESS THAN 1.0 MILE APART.


- ⑤ THE WORK ZONE REFERS TO THE AREA WITHIN THE CONSTRUCTION PROJECT WHERE WORK IS ACTUALLY TAKING PLACE.
- ⑥ THE BUFFER SPACE MAY BE INCREASED FOR DOWNGRADES AND OTHER CONDITIONS THAT AFFECT STOPPING DISTANCE.
- ⑦ USE MORE SPECIFIC SIGNS, WHERE APPLICABLE, SUCH AS W8-3 "PAVEMENT ENDS."
- ⑧ PROVIDE A SECOND FLAGGER WHEN MORE THAN 10 VEHICLES ARE STOPPED AT THE FLAGGER STATION MORE THAN 50% OF THE TIME.

\* DENOTES SIGNS THAT ARE UNIQUE TO MONTANA.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	618-08
SECTION 618	
TWO-LANE CONSTRUCTION PROJECT WORK ZONES	
EFFECTIVE: DECEMBER 2002	



WORK ZONE WITH FLAGGER



NOTES:


- ① THIS SIGN LAYOUT WORKS IN CONJUNCTION WITH THE PERMANENT LAYOUT ILLUSTRATED ON DTL. DWG. NO. 618-04. COVER OR REMOVE SIGNS WHEN NOT IN USE, INCLUDING SPEED LIMIT SIGNS NOT WARRANTED.
- ② INCLUDE REGULATORY SIGNING ONLY IF THERE IS REASON TO RESTRICT SPEED WITHIN THE CONSTRUCTION PROJECT. MODIFY REGULATORY SIGNS TO MATCH ADJACENT REGULATIONS.
- ③ THE WORK ZONE REFERS TO THE AREA WITHIN THE CONSTRUCTION PROJECT WHERE WORK IS ACTUALLY TAKING PLACE.
- ④ FOR SEAL COAT WORK ZONE ACTIVITIES, USE THE FLAGGER APPLICATION OF THE WORK ZONE LAYOUT FROM DTL. DWG. NO. 618-08.
- ⑤ IN ADDITION TO THE SIGNS SHOWN, INCLUDE THE APPROPRIATE TWO-LANE WORK ZONE SIGNS WHEN A WORK ZONE IS LOCATED AT THE BEGINNING OR END OF THE CONSTRUCTION PROJECT.
- ⑥ SET UP THIS SIGN LAYOUT IN EACH TRAFFIC DIRECTION.
- ⑦ PLACE THE W8-7 AND W13-1 SIGNS AT EACH END OF EACH WORK ZONE AND AT 2.0 MILE INTERVALS WITHIN THE WORK ZONES FOR EACH DIRECTION OF TRAVEL.

\* DENOTES SIGNS THAT ARE UNIQUE TO MONTANA.



DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	618-10
SECTION 618	
TWO-LANE CONSTRUCTION PROJECT SEAL COAT	
EFFECTIVE: JANUARY 2004	




This Frame left blank





- NOTES:
- ① MODIFY REGULATORY SIGNS TO MATCH ADJACENT REGULATIONS.
  - ② SET UP THIS SIGN LAYOUT IN EACH TRAFFIC DIRECTION.
  - ③ THE WORK ZONE REFERS TO THE AREA WITHIN THE CONSTRUCTION PROJECT WHERE WORK IS ACTUALLY TAKING PLACE.
  - ④ THE BUFFER SPACE MAY BE INCREASED FOR DOWNGRADES AND OTHER CONDITIONS THAT AFFECT STOPPING DISTANCE.
  - ⑤ PROVIDE A SECOND FLAGGER WHEN MORE THAN 10 VEHICLES ARE STOPPED AT THE FLAGGER STATION MORE THAN 50% OF THE TIME.
- \* DENOTES SIGNS THAT ARE UNIQUE TO MONTANA.


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 618	DWG. NO. 618-12
TWO-LANE CONSTRUCTION PROJECT LANE CLOSURE	
EFFECTIVE: DECEMBER 2002	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD







- NOTES:
- ① USE THIS SIGN LAYOUT ON LOW VOLUME ROADS, WHEN APPROPRIATE. OTHERWISE REFER TO DTL. DWG. NO. 618-16 WHEN A REDUCTION IN SPEED OR A FLAGGER IS NEEDED.
  - ② LOW VOLUME ROADS ARE DEFINED AS ROADS WITH LESS THAN 400 CURRENT AADT AND ARE OUTSIDE OF BUILT-UP AREAS OF TOWNS AND COMMUNITIES.
  - ③ SET UP THIS SIGN LAYOUT IN EACH TRAFFIC DIRECTION, AS NEEDED.
- \*DENOTES SIGNS THAT ARE UNIQUE TO MONTANA.


DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	618-14
SECTION 618	
TWO-LANE EQUIPMENT ENTRANCES ON LOW VOLUME ROADS	
EFFECTIVE: DECEMBER 2002	
	MONTANA DEPARTMENT OF TRANSPORTATION
	MONTANA CADD



EQUIPMENT ENTRANCE WITH NO FLAGGER



- NOTES:
- ① INCLUDE REGULATORY SIGNING ONLY IF THERE IS REASON TO RESTRICT SPEED. MODIFY REGULATORY SIGNS TO MATCH ADJACENT REGULATIONS.
  - ② SET UP THIS SIGN LAYOUT IN EACH TRAFFIC DIRECTION, AS NEEDED.
  - ③ THE BUFFER SPACE MAY BE INCREASED FOR DOWNGRADES AND OTHER CONDITIONS THAT AFFECT STOPPING DISTANCE.
  - ④ XX = SPEED DETERMINED BY THE ENGINEER.
  - ⑤ THE WORK ZONE REFERS TO THE AREA WHERE WORK IS ACTUALLY TAKING PLACE. WHEN THIS OCCURS OUTSIDE OF A CONSTRUCTION PROJECT INCLUDE THE W20-1 AND R2-15\* SIGNS.
  - ⑥ REFER TO DTL. DWG. NO. 618-14 FOR LOW VOLUME ROADS (LESS THAN 400 CURRENT AADT AND OUTSIDE OF BUILT-UP AREAS OF TOWNS AND COMMUNITIES).
- \*DENOTES SIGNS THAT ARE UNIQUE TO MONTANA.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	618-16
SECTION 618	
TWO-LANE EQUIPMENT ENTRANCES	
EFFECTIVE: DECEMBER 2002	
	MONTANA DEPARTMENT OF TRANSPORTATION
	MONTANA CADD




EQUIPMENT ENTRANCE WITH FLAGGER



<p align="center"><b>DETAILED DRAWING</b></p>	
<p>REFERENCE STANDARD SPEC. SECTION 618</p>	<p>DWG. NO. 618-18</p>
<p align="center"><b>TWO-LANE CONSTRUCTION PROJECT DETOUR</b></p>	
<p align="center">EFFECTIVE: DECEMBER 2002</p>	
<p align="center">  <b>MONTANA DEPARTMENT OF TRANSPORTATION</b>  </p>	





This Frame left blank





- NOTES:
- THIS SIGN LAYOUT IS INTENDED TO BE A PERMANENT INSTALLATION FOR THE DURATION OF THE CONSTRUCTION PROJECT, AS APPROVED BY THE ENGINEER. COVER OR REMOVE SIGNS WHEN NOT IN USE, INCLUDING SPEED LIMIT SIGNS NOT WARRANTED. REMOVE ANY SIGN SUPPORTS IF THEY WILL NOT BE NEEDED WITHIN 90 DAYS.
  - XX = SPEED DETERMINED BY THE ENGINEER.
  - INCLUDE REGULATORY SIGNING ONLY IF THE CONSTRUCTION PROJECT CONTAINS A WORK ZONE OR HAS ROADWAY CONDITIONS THAT WARRANT SPEED RESTRICTIONS. MODIFY REGULATORY SIGNS TO MATCH ADJACENT REGULATIONS.
  - THE WORK ZONE REFERS TO THE AREA WITHIN THE CONSTRUCTION PROJECT WHERE WORK IS ACTUALLY TAKING PLACE.
  - SET UP THIS SIGN LAYOUT IN EACH TRAFFIC DIRECTION.
  - IN ADDITION TO THE SIGNS SHOWN, INCLUDE THE APPROPRIATE FOUR-LANE WORK ZONE SIGNS (DTL. DWG. NO. 618-24) WHEN A WORK ZONE FALLS AT THE BEGIN OR END OF THE CONSTRUCTION PROJECT.
  - DIVIDED FOUR-LANE IS SHOWN. FOR UN-DIVIDED FOUR-LANE, PLACE SIGNS ON RIGHT SIDE ONLY.
- \* DENOTES SIGNS THAT ARE UNIQUE TO MONTANA.

FOUR-LANE WORK  
ZONE SIGN LAYOUT  
(WHEN APPLICABLE,  
SEE DTL. DWG. 618-24) ⑥

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	618-20
SECTION 618	
FOUR-LANE CONSTRUCTION PROJECT	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD










NOTE:

THIS SEQUENCE OF SIGNS IS IDENTICAL FOR BOTH WORK ZONES SHOWN ON THIS DETAIL.



WORK ZONE WITH NO FLAGGER





WORK ZONE WITH FLAGGER



NOTES:

- ① THESE SIGN LAYOUTS WORK IN CONJUNCTION WITH THE PERMANENT LAYOUT ILLUSTRATED ON DTL. DWG. NO. 618-20 FOR WORK ZONES LOCATED AT THE BEGIN AND END OF THE CONSTRUCTION PROJECT.
- ② INCLUDE REGULATORY SIGNING ONLY IF THERE IS REASON TO RESTRICT SPEED WITHIN THE WORK ZONE. MODIFY REGULATORY SIGNS TO MATCH ADJACENT REGULATIONS.
- ③ THE WORK ZONE REFERS TO THE AREA WITHIN THE CONSTRUCTION PROJECT WHERE WORK IS ACTUALLY TAKING PLACE.
- ④ THE BUFFER SPACE MAY BE INCREASED FOR DOWNGRADES AND OTHER CONDITIONS THAT AFFECT STOPPING DISTANCE.
- ⑤ USE MORE SPECIFIC SIGNS, WHERE APPLICABLE, SUCH AS W8-3 "PAVEMENT ENDS."
- ⑥ XX = SPEED DETERMINED BY THE ENGINEER.
- ⑦ PROVIDE A SECOND FLAGGER WHEN MORE THAN 10 VEHICLES ARE STOPPED AT THE FLAGGER STATION MORE THAN 50% OF THE TIME.
- ⑧ SPACE FLEXIBLE GUIDE POSTS ON TANGENTS AT INTERVALS IN FEET OF NO MORE THAN TWO TIMES THE SPEED LIMIT IN M.P.H. SPACE PLASTIC DRUMS IN ALL TAPER SECTIONS AT INTERVALS IN FEET OF NO MORE THAN ONE TIMES THE SPEED LIMIT IN M.P.H. FOR SPEED LIMITS LESS THAN 35 M.P.H., SPACE CHANNELIZING DEVICES AS DIRECTED BY THE ENGINEER.
- ⑨ WHEN PORTABLE SIGNS ARE USED, PLACE AS DIRECTED BY THE ENGINEER.


\* DENOTES SIGNS THAT ARE UNIQUE TO MONTANA.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	618-24
SECTION 618	
FOUR-LANE CONSTRUCTION PROJECT WORK ZONES	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD







WORK ZONE WITH NO FLAGGER




WORK ZONE WITH FLAGGER

- NOTES:
- ① INCLUDE REGULATORY SIGNING ONLY IF THERE IS REASON TO RESTRICT SPEED WITHIN THE WORK ZONE. MODIFY REGULATORY SIGNS TO MATCH ADJACENT REGULATIONS.
  - ② THE BUFFER SPACE MAY BE INCREASED FOR DOWNGRADES AND OTHER CONDITIONS THAT AFFECT STOPPING DISTANCE.
  - ③ XX = SPEED DETERMINED BY THE ENGINEER.
  - ④ THE WORK ZONE REFERS TO THE AREA WHERE WORK IS ACTUALLY TAKING PLACE. WHEN THIS OCCURS OUTSIDE OF A CONSTRUCTION PROJECT, INCLUDE THE W20-1 AND R2-15\* SIGNS.
  - ⑤ SPACE FLEXIBLE GUIDE POSTS ON TANGENTS AT INTERVALS IN FEET OF NO MORE THAN TWO TIMES THE SPEED LIMIT IN M.P.H. SPACE PLASTIC DRUMS IN ALL TAPER SECTIONS AT INTERVALS IN FEET OF NO MORE THAN ONE TIMES THE SPEED LIMIT IN M.P.H. FOR SPEED LIMITS LESS THAN 35 M.P.H., SPACE CHANNELIZING DEVICES AS DIRECTED BY THE ENGINEER.
- \* DENOTES SIGNS THAT ARE UNIQUE TO MONTANA.





WORK ZONE WITH NO FLAGGER  
(USE WITH WIDE MEDIANS)





WORK ZONE WITH FLAGGER  
(USE WITH NARROW MEDIANS)


NOTES:

- ① INCLUDE REGULATORY SIGNING ONLY IF THERE IS REASON TO RESTRICT SPEED WITHIN THE WORK ZONE. MODIFY REGULATORY SIGNS TO MATCH ADJACENT REGULATIONS.
- ② THE BUFFER SPACE MAY BE INCREASED FOR DOWNGRADES AND OTHER CONDITIONS THAT AFFECT STOPPING DISTANCE.
- ③ XX = SPEED DETERMINED BY THE ENGINEER.
- ④ THE WORK ZONE REFERS TO THE AREA WHERE WORK IS ACTUALLY TAKING PLACE. WHEN THIS OCCURS OUTSIDE OF A CONSTRUCTION PROJECT, INCLUDE THE W20-1 AND R2-15\* SIGNS.
- ⑤ SPACE FLEXIBLE GUIDE POSTS ON TANGENTS AT INTERVALS IN FEET OF NO MORE THAN TWO TIMES THE SPEED LIMIT IN M.P.H. SPACE PLASTIC DRUMS IN ALL TAPER SECTIONS AT INTERVALS IN FEET OF NO MORE THAN ONE TIMES THE SPEED LIMIT IN M.P.H. FOR SPEED LIMITS LESS THAN 35 M.P.H., SPACE CHANNELIZING DEVICES AS DIRECTED BY THE ENGINEER.



\* DENOTES SIGNS THAT ARE UNIQUE TO MONTANA.



DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	618-28
SECTION 618	
FOUR-LANE MEDIAN CROSSINGS	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD





- ① INCLUDE REGULATORY SIGNING ONLY AS REQUIRED. MODIFY REGULATORY SIGNS TO MATCH ADJACENT REGULATIONS.
- ② THE WORK ZONE REFERS TO THE AREA WITHIN THE CONSTRUCTION PROJECT WHERE WORK IS ACTUALLY TAKING PLACE.
- ③ INDICATED SPACINGS ARE INTENDED TO BE A MAXIMUM AND MAY BE REDUCED IF CONDITIONS WARRANT.
- ④ XX = SPEED DETERMINED BY THE MEDIAN CROSSING DESIGN SPEED OR THE ENGINEER.
- ⑤ SPACE CHANNELIZING DEVICES ON TANGENTS AT INTERVALS IN FEET OF NO MORE THAN TWO TIMES THE SPEED LIMIT IN M. P. H. AND ON ALL TAPER SECTIONS AT INTERVALS IN FEET OF NO MORE THAN ONE TIME THE SPEED LIMIT IN M. P. H. FOR SPEED LIMITS LESS THAN 35 M. P. H. SPACE CHANNELIZING DEVICES AS DIRECTED BY THE ENGINEER.
- ⑥ OBLITERATE ALL PAVEMENT MARKINGS THAT CONFLICT AT ANY TIME DURING OR AFTER MEDIAN CROSSING USE.




DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	618-30
SECTION 618	
TEMPORARY	
FOUR-LANE TO TWO-LANE	
MEDIAN CROSSING	
EFFECTIVE: DECEMBER 2002	
 MONTANA DEPARTMENT OF TRANSPORTATION 	












NOTES:



- ① SHORT DURATION ACTIVITIES ARE DEFINED AS THOSE LASTING UP TO ONE HOUR.
- ② USE THIS SIGN LAYOUT WHEN WORK IS TO TAKE PLACE ON THE TRAVELED WAY. SIGNING FOR WORK ON OR NEAR THE SHOULDER MAY BE LIMITED TO THE USE OF ONE 48" WARNING SIGN FOR EACH TRAVEL DIRECTION. SIGNING FOR WORK OUTSIDE THE SHOULDER MAY BE LIMITED TO THE USE OF ONE 48" WARNING SIGN FOR THE TRAVEL DIRECTION ADJACENT TO THE WORK.
- ③ SIGN BOTH TRAVEL DIRECTIONS ON TWO-LANE, TWO-WAY ROADWAYS OR BOTH SHOULDERS ON TWO-LANE, ONE-WAY ROADWAYS.
- ④ PROVIDE AT LEAST THE DISTANCE SHOWN FOR DELINEATOR MOUNTED SIGNS.
- ⑤ SEE DTL, DWG. NO. 618-36 "SHORT-TERM STATIONARY CREW SIGNING" IF THE DOUBLE PENALTY REGULATION IS TO BE UTILIZED.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 618	DWG. NO. 618-34
SHORT DURATION CREW SIGNING	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD




NOTES:



- ① SHORT-TERM STATIONARY ACTIVITIES ARE DEFINED AS THOSE LASTING GREATER THAN ONE HOUR, UP TO A FULL SHIFT.
  - ② USE THIS SIGN LAYOUT WHEN WORK IS TO TAKE PLACE ON THE TRAVELED WAY. SIGNING FOR WORK ON OR NEAR THE SHOULDER MAY BE LIMITED TO THE USE OF ONE 48" WARNING SIGN FOR EACH TRAVEL DIRECTION. SIGNING FOR WORK OUTSIDE THE SHOULDER MAY BE LIMITED TO THE USE OF ONE 48" WARNING SIGN FOR THE TRAVEL DIRECTION ADJACENT TO THE WORK.
  - ③ THE CONSTRUCTION ZONE REFERS TO THE GENERAL AREA THAT REQUIRES TEMPORARY WORK ZONE TRAFFIC CONTROL. IT SHOULD NOT EXCEED THREE MILES IN LENGTH.
  - ④ THE TWO SIGNS MARKING THE WORK ZONE BOUNDARIES AND THE REGULATORY SPEED SIGN MUST MOVE AS NEEDED WITHIN THE CONSTRUCTION ZONE TO REMAIN WITHIN 500 FEET OF THE WORK ACTIVITY.
  - ⑤ SIGN BOTH TRAVEL DIRECTIONS ON TWO-LANE, TWO-WAY ROADWAYS OR BOTH SHOULDERS ON TWO-LANE, ONE-WAY ROADWAYS.
  - ⑥ PROVIDE AT LEAST THE DISTANCE SHOWN FOR DELINEATOR MOUNTED SIGNS.
  - ⑦ USE REFLECTIVE DEVICES.
- \* DENOTES SIGNS THAT ARE UNIQUE TO MONTANA.


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 618	DWG. NO. 618-36
SHORT-TERM STATIONARY CREW SIGNING	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD







- NOTES:
- ① MINIMUM REGULATORY SIGN SIZE IS 24" X 30" ON TWO LANE ROADS.
  - ② ON ROADWAYS WITH HIGH TRAFFIC VOLUMES OR VISIBILITY RESTRICTIONS, A 500' SPACING FOR ALL SIGNS IS RECOMMENDED.
  - ③ SPACE CHANNELIZING DEVICES AT INTERVALS IN FEET OF TWICE THE SPEED LIMIT IN M.P.H. THROUGH THE BUFFER AND WORK AREA.
  - ④ IF A NEED ARISES TO INCREASE VEHICLE STORAGE, ADD AN ADDITIONAL W20-7a "FLAGGER AHEAD" SIGN BETWEEN THE R2-1 AND THE ORIGINAL W20-7a AND/OR CONSIDER AN ADDITIONAL ADVANCE FLAGGER.
  - ⑤ A MIRROR IMAGE OF THIS SIGN SEQUENCE IS REQUIRED FOR THE TRAFFIC FROM THE OPPOSITE DIRECTION.
  - ⑥ FOR MORE INFORMATION OR CLARIFICATION CONTACT THE DISTRICT TRAFFIC ENGINEER. FOR EXAMPLE, IF WORK ZONE IS CLOSE TO A HORIZONTAL CURVE, A VERTICAL CURVE, A BRIDGE, INTERCHANGE, POOR SIGHT DISTANCE, OR OTHER SPECIAL CONDITION.
  - ⑦ COVER ANY CONFLICTING SIGNS IN THE WORK ZONE.
  - ⑧ SHORT-TERM WORK ZONE SIGNING IS NOT REQUIRED TO BE POST MOUNTED.
  - ⑨ THE BUFFER SPACE CAN BE LATERAL AND LOGITUDINAL AND MAY BE INCREASED FOR DOWNGRADES AND OTHER CONDITIONS THAT AFFECT STOPPING DISTANCE.
  - ⑩ TYPICALLY 2 MILES IS THE MAX. WORK AREA. HOWEVER, WHEN SIGHT DISTANCE, BUFFER ZONES OR ACCOMPLISHMENT RATES FOR EQUIPMENT ARE CONSIDERED, SOME MINOR ADJUSTMENTS TO THIS MAX. MAY BE CONSIDERED.
- \* DENOTES SIGNS THAT ARE UNIQUE TO MONTANA.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	618-M1
SECTION 618	
MAINTENANCE GUIDELINE FOR SHORT-TERM TWO-LANE CRACK SEALING WORK ZONE	
EFFECTIVE: JANUARY 2004	
	MONTANA DEPARTMENT OF TRANSPORTATION
	MONTANA CADD




- NOTE:
- TO BE POSTED AT THE START OF THE WORK AND REPEATED AT TWO MILE INTERVALS UNTIL THE SURFACE IS SWEEP AND STRIPED.

- NOTES:
- ① MINIMUM REGULATORY SIGN SIZE IS 24" X 30" ON TWO LANE ROADS.
  - ② ON ROADWAYS WITH HIGH TRAFFIC VOLUMES OR VISIBILITY RESTRICTIONS, A 500' SPACING FOR ALL SIGNS IS RECOMMENDED.
  - ③ IF A NEED ARISES TO INCREASE VEHICLE STORAGE, ADD AN ADDITIONAL W20-7a "FLAGGER AHEAD" SIGN BETWEEN THE R2-1 AND THE ORIGINAL W20-7a AND/OR CONSIDER AN ADDITIONAL ADVANCE FLAGGER.
  - ④ A MIRROR IMAGE OF THIS SIGN SEQUENCE IS REQUIRED FOR THE TRAFFIC FROM THE OPPOSITE DIRECTION.
  - ⑤ FOR MORE INFORMATION OR CLARIFICATION CONTACT THE DISTRICT TRAFFIC ENGINEER. FOR EXAMPLE, IF WORK ZONE IS CLOSE TO A HORIZONTAL CURVE, A VERTICAL CURVE, A BRIDGE, INTERCHANGE, POOR SIGHT DISTANCE OR OTHER SPECIAL CONDITION.
  - ⑥ COVER ANY CONFLICTING SIGNS IN THE WORK ZONE.
  - ⑦ SHORT-TERM WORK ZONE SIGNING IS NOT REQUIRED TO BE POST MOUNTED.
  - ⑧ THE BUFFER SPACE CAN BE LATERAL AND LONGITUDINAL AND MAY BE INCREASED FOR DOWNGRADES AND OTHER CONDITIONS THAT AFFECT STOPPING DISTANCE.
- \* DENOTES SIGNS THAT ARE UNIQUE TO MONTANA.



DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	618-M2
SECTION 618	
MAINT. GUIDELINE FOR SHORT-TERM TWO-LANE CHIP SEAL & OVERLAY (PILOTTED TRAFFIC)	
EFFECTIVE: JANUARY 2004	
	MONTANA DEPARTMENT OF TRANSPORTATION
	MONTANA CADD



This Frame left blank



- NOTES:
- ① USE A MINIMUM 210' SHOULDER TAPER.
  - ② USE THIRTEEN APPROVED CHANNELIZING DEVICES FOR A 12' LANE CLOSURE TAPER (75 M.P.H. SPACED AT 75'.) ASSURE THAT THE TAPER IS A MINIMUM LENGTH OF 900'.
  - ③ SPACE CHANNELIZING DEVICES AT INTERVALS IN FEET OF TWICE THE SPEED LIMIT IN M.P.H. THROUGH THE BUFFER AND WORK AREA.
  - ④ PLACE THE ARROW BOARD (IF USED) ON THE SHOULDER AT THE START OF THE TRAVEL LANE CLOSURE TAPER.
  - ⑤ THE BUFFER SPACE CAN BE LATERAL AND LONGITUDINAL. KEEP THE BUFFER SPACE CLEAR OF EQUIPMENT AND PERSONNEL.
  - ⑥ FOR MORE INFORMATION OR CLARIFICATION CONTACT THE DISTRICT TRAFFIC ENGINEER. FOR EXAMPLE, IF WORK AREA IS CLOSE TO A HORIZONTAL CURVE, A VERTICAL CURVE, A BRIDGE, INTERCHANGE, POOR SIGHT DISTANCE OR OTHER SPECIAL CONDITION.
  - ⑦ COVER ANY CONFLICTING SIGNS IN THE WORK AREA.
  - ⑧ SHORT-TERM WORK ZONE SIGNING IS NOT REQUIRED TO BE POST MOUNTED.
  - ⑨ WHEN THE WORK ZONE CHANGES WITHIN THE CONSTRUCTION ZONE THESE SIGNS SHOULD BE MOVED TO REFLECT THE ACTUAL WORK ZONE.
  - ⑩ TYPICALLY 2 MILE IS THE MAX. WORK AREA. HOWEVER, WHEN SIGHT DISTANCE, BUFFER ZONES OR ACCOMPLISHMENT RATES FOR EQUIPMENT ARE CONSIDERED, SOME MINOR ADJUSTMENTS TO THIS MAX. MAY BE CONSIDERED.
- \* DENOTES SIGNS THAT ARE UNIQUE TO MONTANA.


DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	618-M3
SECTION 618	
MAINTENANCE GUIDELINE FOR SHORT-TERM LANE CLOSURE ON INTERSTATE	
EFFECTIVE: JANUARY 2004	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD








This Frame left blank





NOTES:  
\* 6' MINIMUM; 50' MAXIMUM.  
PLACE R1-1 SIGN AT THE BEGINNING OF CURB RADIUS OR SHOULDER RADIUS, OR 4 FEET MIN. IN ADVANCE OF THE MARKED OR UNMARKED CROSSWALK.  
SEE PLANS FOR FINAL SIGNING AND PAVEMENT MARKING LOCATIONS.


RURAL




URBAN

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 619	DWG. NO. 619-02
TYPICAL RURAL AND URBAN APPROACHES	
EFFECTIVE: AUGUST 1999	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD






BACKBRACE DETAIL



BACKBRACING TABLE - ALUMINUM SIGNS		
MAXIMUM BACKBRACE SPACING "A"	MAXIMUM WIDTH "B"	
	2 POST	3 POST
1' - 8"	18' - 0"	27' - 0"
1' - 10"	17' - 0"	25' - 8"
2' - 0"	16' - 6"	24' - 8"
2' - 6"	14' - 9"	22' - 0"
3' - 0"	13' - 6"	20' - 0"
3' - 6"	12' - 6"	18' - 6"

FOR ALUMINUM PLATE THICKNESS INFORMATION SEE SECTION 704.01 OF THE STANDARD SPECIFICATIONS.




RIVET SPACING DETAIL

LOCATE RIVETS AT 6" ALTERNATE CENTERS ON HORIZONTAL EXTRUDED "T"-SECTION.

DOUBLE RIVETS (TOP AND BOTTOM OR LEFT AND RIGHT OF EXTRUDED "T"-SECTION) AT HORIZONTAL AND VERTICAL JOINTS IN SHEET ALUMINUM FACE AND AT ENDS OF EXTRUDED "T"-SECTION.

COLOR RIVET HEADS TO MATCH ADJACENT SHEETING.



EXTRUDED "T"-SECTION BACKBRACE

#### NOTES:

CONFORM ALL ALUMINUM SIGNS TO SECTIONS 619, 704.01.1 AND 704.01.2 OF THE STANDARD SPECIFICATIONS.

FOR SIGNS 4'-0" HIGH BY 6'-0" LONG OR LESS USE A SINGLE SHEET OF ALUMINUM.

DO NOT USE HORIZONTAL JOINTS ON SIGNS 6'-0" IN HEIGHT AND SMALLER. THE MINIMUM SHEET WIDTH IS 1'-6".

SIGNS OVER 6'-0" HIGH MAY HAVE HORIZONTAL AND VERTICAL JOINTS. THE MINIMUM SHEET SIZE IS 1'-6" WIDE BY 1'-6" HIGH.

CLEAN AND DRY POST CLIP NUTS, THEN TORQUE TO 225 INCH POUNDS.

LOCATE ALL HORIZONTAL JOINTS AT A "T"-SECTION.



NO SPLICES ARE ALLOWED IN EXTRUDED "T"-SECTIONS.

USE SCREWS, BOLTS AND LOCKWASHERS THAT ARE ALUMINUM ALLOY MEETING ASTM B 211 FOR ALLOY 2024-T4, STAINLESS STEEL, OR CADMIUM PLATED STEEL MEETING ASTM B 766.



USE ONLY ALUMINUM RIVETS.

THE MAXIMUM GAP BETWEEN INDIVIDUAL SIGN PANELS AT JOINTS IS 1/16" AT ANY POINT.


THE ENGINEER MAY APPROVE ADDITIONAL METHODS TO PREVENT LIGHT LEAKAGE THROUGH SIGN PANEL SEAMS.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	619-04
SECTION 619, 704	
ALUMINUM SHEET INCREMENT SIGN CONSTRUCTION DETAILS	
EFFECTIVE: AUGUST 1999	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD







ALUMINUM CLIP PLACEMENT



BACKBRACING TABLE - PLYWOOD SIGNS		
MAXIMUM BACKBRACE SPACING "A"	MAXIMUM WIDTH "B"	
	2 POST	3 POST
1' - 8"	18' - 0"	27' - 0"
1' - 10"	17' - 0"	25' - 8"
2' - 0"	16' - 6"	24' - 8"
2' - 6"	14' - 9"	22' - 0"
3' - 0"	13' - 6"	20' - 0"
3' - 6"	12' - 6"	18' - 6"



DETAIL A  
VERTICAL JOINT



DETAIL B  
HORIZONTAL JOINT

NOTES:

CONFORM ALL PLYWOOD SIGNS TO SECTIONS 619, 704.01.3 AND 704.02.2 OF THE STANDARD SPECIFICATIONS.

ON SIGNS 4'-0" HIGH AND GREATER, DO NOT USE ANY PANELS LESS THAN 4'-0" IN HEIGHT.

DO NOT USE HORIZONTAL JOINTS ON SIGNS LESS THAN 4'-0" IN HEIGHT.

FOR SIGNS WITH WIDTHS THAT ARE NOT IN MULTIPLES OF 4'-0", PLACE THE ODD LENGTH PANEL ON THE INSIDE EDGE.


FOR SIGNS OVER 10'-0" IN HEIGHT, THE FULL HEIGHT MAY BE OBTAINED WITH PANELS HAVING A FACTORY SCARFED JOINT IN LIEU OF USING STANDARD LENGTH PANEL AS SHOWN.

THE MINIMUM SIZE PANEL IS 1'-6" WIDE BY 4'-0" HIGH.

CONSTRUCT PLYWOOD SIGNS OF ONE PIECE OF PLYWOOD UNLESS THE PLANS SPECIFY OTHERWISE FOR SPECIAL DESIGN SIGNS.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	619-06
SECTION 619, 704	
PLYWOOD SHEET INCREMENT GUIDE SIGN CONSTRUCTION DETAILS	
EFFECTIVE: AUGUST 1999	
MONTANA DEPARTMENT OF TRANSPORTATION	MONTANA CADD





⊗ POST SPACING WIDTH:

= 0.60 x B FOR 2 POSTS

= 0.35 x B FOR 3 POSTS

WHERE 3 POSTS ARE REQUIRED, THE CENTER POST IS DESIGNATED Z POST

#### NOTES:

MOUNTING SYSTEMS SHOWN ARE TYPICAL. OTHER SYSTEMS MAY BE APPROVED BY THE ENGINEER.

ALL STEEL HARDWARE MUST BE GALVANIZED, STAINLESS, OR CADMIUM PLATED.

GAIN THE TOP HALF OF WOOD POLES ACCORDING TO THE TABLE ON DTL. DWG. NO. 619-20.

SEE THE SIGNING QUANTITIES FOR THE TYPES OF POSTS AND FOUNDATIONS.

MOUNT ONE-PANEL PLYWOOD SIGNS DIRECTLY TO WOOD POLES OR POSTS, WHEN SPECIFIED IN THE PLANS, BY BOLTING THROUGH THE SIGN PLATE AND THE POLE WITH CADMIUM PLATED BOLTS AS REQUIRED BY THE DETAILED DRAWINGS, SPECIFICATIONS AND DESIGN. USE "T"-SECTION WIND BEAMS WHEN REQUIRED BY DTL. DWG. NO. 619-06.





⑦ SUSPEND LARGE SUPPLEMENTAL SIGNS, ADDED AFTER INITIAL SIGN INSTALLATION, FROM MAJOR SIGN PANEL OR BACKBRACING. ATTACHMENT TO MULTIPLE POSTS/POLES IS NOT ALLOWED.

USE POST SPACING, POST SIZE AND BREAKAWAY DEVICES SPECIFIED IN THE PLANS AND IN THE SPECIFICATIONS. FOR INFORMATION REGARDING APPROPRIATE BREAKAWAY DEVICES FOR NEW INSTALLATIONS NOT SUPPORTED BY THE PLANS, CONTACT THE TRAFFIC UNIT.

IN LOCATING SIGNS, AVOID PLACING POSTS IN DITCH BOTTOMS WHERE THEY WOULD IMPEDE DRAINAGE.

⊗ DIMENSIONS ARE SPECIFIED IN THE SIGNING PLANS.

#### MOUNTING DETAILS




DOUBLE POLE MOUNT

TREATED POLE  
SINGLE OR DOUBLE  
(USED WHEN "T"-BAR WIND  
BEAMS NOT REQUIRED)

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	619-08
SECTION 619, 704	
GUIDE SIGN CLEARANCE AND MOUNTING DETAILS	
EFFECTIVE: DECEMBER 2002	
MONTANA DEPARTMENT OF TRANSPORTATION	




This Frame left blank



EXISTING PLYWOOD SIGNS

EXISTING ALUMINUM SIGNS





FASTENER PATTERN



NOTES:

- REMOVE ALL RAISED LETTERS, NUMERALS, SYMBOLS, BORDERS AND PREVIOUS SIGN OVERLAYS TO BE REPLACED, AND CLEAN SIGN FACE TO A SMOOTH SURFACE BEFORE OVERLAYING.
- ALL LETTERS, NUMERALS, SYMBOLS AND BORDERS ARE TYPE "C" CUTOUT UNLESS OTHERWISE SPECIFIED, AND APPLIED TO THE BACK-GROUND SHEETING PRIOR TO FIELD APPLICATION OF THE SIGN.
- THE SIZE OF ALL GUIDE SIGN OVERLAYS AND LEGENDS MUST BE VERIFIED BY THE ENGINEER PRIOR TO FABRICATION.
- ⑩ AN ADHESIVE-BACKED SHEETING MAY BE USED AS AN ALTERNATIVE ON SIGN WIDTHS OF 6'-0" OR LESS IF IT IS PREFABRICATED TO A MINIMUM THICKNESS OF 0.005 INCHES AND CONSTRUCTED OF PREAPPLIED REFLECTIVE SHEETING ON ADHESIVE-BACKED ALUMINUM. APPLY ADHESIVE-BACKED OVERLAY SHEETING WHEN AIR AND SURFACE TEMPERATURES ARE ABOVE 50°F (10°C). DO NOT USE THIS TYPE OF OVERLAY MATERIAL ON OVERHEAD SIGNS.
- PROVIDE A MINIMUM REFLECTIVE SHEETING INTENSITY OF ENGINEERING GRADE, MEETING THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS, UNLESS SPECIFIED OTHERWISE.
- APPLY ALL MATERIALS IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS.
- SEE THE STANDARD SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.


- USE ALUMINUM ALLOY TYPE 6061-T6 OR AA5052-H38. CONVERSION COAT ALL ALUMINUM WITH A PROCESS SUCH AS ALODINE 1200 (OR EQUAL), AND RINSE AND DRY THOROUGHLY. PROTECT IT FROM SOIL BY ACCEPTABLE METHODS.
- SIGN OVERLAYS MAY REQUIRE REMOVAL OF THE SIGN FROM THE POSTS TO AVOID PROJECTING BOLT HEADS. DO NOT LEAVE WARNING AND REGULATORY SIGNS TO BE OVERLAYED UNDISPLAYED FOR MORE THAN ONE (1) HOUR DURING DAYLIGHT. DO NOT LEAVE GUIDE SIGNS UNDISPLAYED FOR MORE THAN TEN (10) HOURS DURING DAYLIGHT. INSURE SIGNS TO BE OVERLAYED ARE OPERATIONAL PRIOR TO DARKNESS.
- OVERLAY SIGNS SMALLER THAN 4'-0" x 6'-0" WITH ONE PANEL OF MATERIAL. FOR SEAMS IN LARGE OVERLAYS, USE RIVETS OR BOLTS SPACED AS SHOWN ON THIS DRAWING AND PLACE PARALLEL TO AND NO MORE THAN 3" Laterally FROM THE SEAM.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	619-10
SECTION 619	
SHEET ALUMINUM OVERLAY	
EFFECTIVE: AUGUST 1999	
 MONTANA DEPARTMENT OF TRANSPORTATION	



 MONTANA DEPARTMENT  
OF TRANSPORTATION  MONTANA  
CADD






BASE CONNECTION DATA											FUSE PLATE DATA										FOUNDATION DATA				
POST SIZE	BOLT SIZE	BOLT TORQUE	DIMENSIONS							BREAKAWAY DEVICE (LB.)	DIMENSIONS								BOLT DIA.	FUSE DEVICE (LB.)	FTG. DEPTH	STUB LENGTH	FTG. DIA.	BAR C SIZE	STUB POST (LB.)
			A	B	C	D	E	t <sub>1</sub>	W		F	G	H	J	K	L	N	t <sub>3</sub>							
W4 x 13 M4 x 13	5/8" DIA. x 2 3/4"	40 FT. LB.	8 1/2"	5"	3/4"	2 3/4"	1 1/8"	3/4"	5/16"	21.58	3 3/4"	2"	1 1/8"	4"	2 1/4"	7/8"	5/8"	3/8"	5/8"	1.60	3'-6"	2'-0"	1'-6"	#5	26.00
W8 x 18			12 1/2"	6 1/4"	3/4"	4"	1 1/8"	3/4"	5/16"	37.00	4 1/2"	2 1/2"	1 1/4"	5 1/4"	2 3/4"	1 1/4"	3/4"	1/2"	3/4"	3.27	5'-6"	2'-6"	2'-0"	#7	45.00
W8 x 24	3/4" DIA. x 3 1/2"	65 FT. LB.	13"	7 1/2"	3/4"	5"	1 1/4"	1"	5/16"	60.86	4 3/4"	2 1/2"	1 1/2"	6"	3 1/2"	1 1/4"	3/4"	9/16"	3/4"	4.66	7'-0"	3'-0"	2'-0"	#9	72.00
W12 x 30			17"	7 1/2"	7/8"	5"	1 1/4"	1"	5/16"	78.54	5 3/8"	3"	1 1/2"	6 1/2"	3 1/2"	1 1/2"	7/8"	9/16"	7/8"	5.42	8'-0"	3'-0"	2'-6"	#9	90.00
S3 x 5.7	1/2" DIA. x 2 1/2"	20 FT. LB.	8"	3"	3/4"	1 1/2"	3/4"	5/8"	1/4"	10.37	3 1/8"	1 1/2"	1 1/8"	2 5/8"	1 1/2"	9/16"	1/2"	1/4"	1/2"	0.64	3'-6"	1'-6"	1'-6"	#4	8.55
S4 x 7.7			8"	3"	3/4"	1 1/2"	3/4"	5/8"	1/4"	10.45	3 1/8"	1 1/2"	1 1/8"	2 5/8"	1 1/2"	9/16"	1/2"	1/4"	1/2"	0.64	3'-6"	1'-6"	1'-6"	#4	11.55
S5 x 10.0	5/8" DIA. x 2 3/4"	40 FT. LB.	9 1/2"	4"	3/4"	2"	1"	3/4"	1/4"	19.08	3 1/8"	1 1/2"	1 1/8"	3"	1 7/8"	9/16"	1/2"	1/4"	1/2"	0.66	3'-6"	1'-6"	1'-6"	#5	15.00

#### PROCEDURE FOR BASE CONNECTION ASSEMBLY



1. ASSEMBLE POST TO STUB WITH BOLTS AND ONE FLAT WASHER BETWEEN PLATES.
2. SHIM AS REQUIRED TO PLUMB POST.
3. TIGHTEN BOLTS IN A SYSTEMATIC ORDER TO THE PRESCRIBED TORQUE (SEE TABLE).

4. LOOSEN EACH BOLT AND RETIGHTEN TO PRESCRIBED TORQUE IN THE SAME ORDER AS ORIGINAL TIGHTENING. DO NOT OVERTIGHTEN.
5. BURR THREADS AT JUNCTION WITH NUT USING A CENTER PUNCH TO PREVENT NUT LOOSENING.


NOTE:  
ALL BOLTS MUST BE ASTM A 325 AND BE TIGHTENED BY USE OF A DIRECT TENSION INDICATING DEVICE (LOAD INDICATING WASHER) IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS.






SIGN POST AND STUB POST DETAIL "A"



SIGN POST AND STUB POST DETAIL "B"  
USE ONLY WITH SINGLE POST SIGNS



NOTE:  
SECTIONS SHOWN ARE FOR INSTALLATIONS ON RIGHT SHOULDER AND IN GORE. PLATE SLOT BEVELS ARE OPPOSITE HAND FROM THAT SHOWN FOR INSTALLATIONS ON LEFT SHOULDER.



FURNISH TWO 0.012" ± THICK AND TWO 0.032" ± THICK SHIMS PER POST. USE SHIMS FABRICATED FROM BRASS SHIM STOCK OR STRIP CONFORMING TO ASTM B 36.

#### NOTES:

USE CLASS "A" OR "D" CONCRETE WITH A WOOD FLOAT FINISH ON TOP. FORM TOP 12 INCHES OF FOUNDATION.


SEE THE STANDARD SPECIFICATIONS FOR REQUIREMENTS GOVERNING STRUCTURAL STEELS AND THEIR FABRICATIONS. TO AVOID OVERSIGHT, NOTE THESE REQUIREMENTS ON THE SHOP DRAWINGS.

SUBMIT SHOP PLANS FOR APPROVAL BEFORE FABRICATION IS BEGUN.

THE WEIGHT OF STEEL POSTS IS COMPUTED BY TAKING THE LENGTH OF THE POST TIMES THE NOMINAL WEIGHT PER FOOT PLUS THE WEIGHT OF THE BREAKAWAY DEVICE, FUSE DEVICE AND STUB POST AS SHOWN IN THE TABLE.

FOR GUIDE SIGN PLACEMENT AND DETAILS, SEE SIGNING DTL. DWG. NO. 619-08.

FRANGIBLE BOLT BREAKAWAY SYSTEMS APPROVED BY FHWA ARE ALLOWED TO BE USED IN PLACE OF THE DESIGN SHOWN HERE AS AN EQUAL OPTION (PER ENGINEER'S APPROVAL).





PAINT:  
EXCEPT AS OTHERWISE APPROVED BY THE ENGINEER, PAINT STRUCTURAL STEEL WITH ONE SHOP COAT AND ONE FIELD COAT OF ZINC RICH BASED PAINT AND ONE FIELD COAT OF ALUMINUM PAINT, AS SPECIFIED IN THE STANDARD SPECIFICATIONS, ON ALL SURFACES NOT IN CONTACT WITH CONCRETE.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	619-13
SECTION 619	
BREAKAWAY AND FOUNDATION DETAILS FOR MULTIPLE GUIDE SIGN SUPPORTS	
EFFECTIVE: AUGUST 1999	





## SIGNS WITHOUT BACKBRACING



THE COST FOR MOUNTING D-3 SIGNS  
IS ABSORBED IN OTHER BID ITEMS OF  
THE CONTRACT.

REFER TO FHWA'S "STANDARD HIGHWAY  
SIGNS" FOR D-3 STREET NAME SIGN  
TYPICAL LAYOUT.

## SIGNS WITH BACKBRACING



PLAN VIEW

VERTICAL DIMENSIONS SHOWN ARE FROM TOP TO TOP  
OF ALL POST CLIP PLATES.


PLACE A SUITABLE WATERTIGHT CAP ON TOP OF ALL PIPE POSTS.

BREAKAWAY DEVICES FOR SQUARE TUBING ARE SHOWN  
ON DTL. DWG. NO. 619-14.






CONFORM MATERIAL USED IN FABRICATION OF POST  
CLIPS AND ANGLE BRACKETS TO SECTION 556 OF  
THE STANDARD SPECIFICATIONS.

THE LENGTH OF EACH ANGLE BRACKET DEPENDS ON THE MOUNTING ASSEMBLY AND HOLE SPACING OF EACH SIGN. THE ASSEMBLIES SHOWN ARE TYPICAL INSTALLATIONS. ERECT SIMILAR ASSEMBLIES IN A LIKE MANNER.





REFER TO FHWA'S "STANDARD HIGHWAY SIGNS" FOR  
STANDARD HOLE SPACING IN SIGNS.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	
SECTION 556, 619, 704	619-16
TYPICAL STEEL POST MOUNTING DETAILS	
EFFECTIVE: AUGUST 1999	
 MONTANA DEPARTMENT OF TRANSPORTATION	MONTANA CADD





NOTE:  
ALTERNATE MOUNTING MUST BE  
APPROVED BY THE ENGINEER.




#### NOTES:

REFER TO FHWA'S MANUAL "STANDARD HIGHWAY SIGNS" FOR STANDARD HOLE SPACING IN SIGNS.

USE POST CLIPS AS SHOWN IN SIGNING DETAILED DRAWING NO. 619-12 WHEN CANTILEVER MOUNTING IS NECESSARY.

USE POSTS ONE SIZE LARGER THAN THOSE REQUIRED FOR STANDARD MOUNTINGS.


DIMENSIONS FOR POST CLIP SPACING ARE SHOWN TO THE TOP OF EACH CLIP.



#### ALTERNATE A

USE THE STANDARD TYPE MOUNTING BEHIND SIDEWALKS IF R/W LIMITS PERMIT. IF R/W DOES NOT PERMIT, THEN ALTERNATE A SHOULD BE USED BEHIND SIDEWALKS OR IN THE SIDEWALK NEXT TO A BUILDING. IF CONDITIONS ARE SUCH THAT THE SIGN CANNOT BE MOUNTED ON THE BACKSIDE OF THE SIDEWALK THEN USE ALTERNATE B.

#### ALTERNATE B





#### DETAIL C



DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	619-18
SECTION 556, 619, 704	
CANTILEVER TYPE SIGN SUPPORT DETAILS FOR SIDEWALK AREAS	
EFFECTIVE: AUGUST 1999	




This Frame left blank




NOTE:  
SEE THE PLANS  
FOR BACKBRACING  
REQUIREMENTS.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	619-19
SECTION 619, 704	
STRUCTURAL STEEL POST SIGN MOUNTING DETAILS	
EFFECTIVE: AUGUST 1999	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD





BREAKAWAY AND FOOTING DETAILS



5/16" DIA. HEX HEAD BOLT, PLATE WASHER, LOCKWASHER AND NUT

5/16" DIA. HEX HEAD BOLT, PLATE WASHER, LOCKWASHER AND NUT

5/16" DIA. HEX HEAD BOLT, PLATE WASHER, LOCKWASHER AND NUT

SIGN FACE 36" x 36" MAX. SIZE


SIGN FACE 30" x 36" MAX. SIZE

SIGN FACE 36" x 36" MAX. SIZE

REGULATORY SIGNS

WARNING SIGNS

TYPICAL SIGN MOUNTINGS  
(NO BACKBRACING)




NOTES:


THE COST FOR MOUNTING D-3 SIGNS IS ABSORBED IN OTHER BID ITEMS OF THE CONTRACT.

REFER TO FHWA'S "STANDARD HIGHWAY SIGNS" FOR D-3 STREET NAME SIGN TYPICAL LAYOUT.


STREET NAME SIGN INSTALLATION



TOP END TREATMENT



GAIN DETAIL



SIGN MOUNTING DETAIL

NOTES:

CONFORM ALL WOOD POLES TO THE REQUIREMENTS OF SECTION 704 OF THE STANDARD SPECIFICATIONS.

GAIN ALL POLES ON THE SIGN SIDE THE MINIMUM WIDTH SHOWN IN THE TABLE, FOR HALF THE LENGTH OF EACH POLE.

BREAKAWAY DETAILS ARE STANDARD FOR ALL WOOD POLES LISTED IN THE TABLE, ON SINGLE AND MULTIPLE SIGN SUPPORTS.

ALL BOLTS, NUTS AND WASHERS MUST CONSIST OF ALUMINUM, STAINLESS STEEL OR CADMIUM PLATED STEEL MATERIAL.

ATTACH A 2" x 4" x 12" BOARD 12" FROM THE BOTTOM OF THE POLE TO PREVENT SPINNING. ATTACH THIS CLEAT BY DRIVING TWO 16d NAILS THROUGH THE CLEAT AND INTO THE POLE. TREAT THE 2" x 4" CLEAT ACCORDING TO THE STANDARD SPECIFICATIONS.



⊗ THE MAXIMUM CROSS-SECTIONAL AREA AT A POINT 4" ABOVE GROUND LEVEL MAY NOT EXCEED 24 SQUARE INCHES EXCLUSIVE OF DRILLED BREAKAWAY HOLES FOR UNPROTECTED POST INSTALLATIONS. THE HOLE DIAMETER MAY BE ENLARGED IF NECESSARY TO INSURE THIS REQUIREMENT IS MET.

USE SOIL CEMENT FOR THE FOUNDATION - SEE SECTION 619.03.3 OF THE STANDARD SPECIFICATIONS.


FOR SIGNS REQUIRING BACKBRACING, CONSULT DTL. DWG. NO. 619-21 AND 619-22 FOR BACKBRACING OPTIONS AND DETAILS.

POLE SIZE	A	B	C	HOLE DIA. (SEE NOTE ⊗)	EMBEDMENT	GAIN
3" TOP DIA.	~	~	~	~	3'-0"	2 3/4"
4" TOP DIA.	~	~	~	~	3'-0"	3 1/2"
5" TOP DIA.	~	12"	4"	2"	3'-6"	4"
6" TOP DIA.	~	12"	4"	2 1/2"	4'-6"	4"
CLASS 4	~	12"	4"	2"	5'-0"	4"
CLASS 3	~	12"	4"	2 1/2"	5'-6"	4"
CLASS 2	6"	6"	4"	2"	6'-0"	4"
CLASS 1	6"	6"	4"	2 1/2"	6'-6"	4"

MUST BE PROTECTED OR OUT OF CLEAR ZONE

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	619-20
SECTION 619, 704	
TREATED WOOD POLE SIGN MOUNTING AND SUPPORT DETAILS	
EFFECTIVE: AUGUST 1999	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD







NOTE:  
SIGNS OF THESE SIZES AND LARGER REQUIRE WOOD BACKBRACING.

WOOD BACKBRACE INSTALLATIONS

SMALLER SIGNS MAY REQUIRE BACKBRACING IF THE CONDITIONS WARRANT (SEE SIGNING PLANS). IN THIS CASE, THE CONTRACTOR HAS THE OPTION OF USING WOOD OR STEEL BACKBRACING (SEE DTL. DWG. NO. 619-22).



SIGN MOUNTING DETAIL




GAIN DETAIL

TOP END TREATMENT

NOTES:  
CONFORM ALL WOOD POLES TO THE REQUIREMENTS OF SECTION 704 OF THE STANDARD SPECIFICATIONS.  
GAIN ALL POLES ON THE SIGN SIDE THE MINIMUM WIDTH SHOWN IN THE TABLE ON DTL. DWG. NO. 619-20, FOR HALF THE LENGTH OF EACH POLE.  
USE 2" x 4" S4S LUMBER FOR ALL WOOD BACKBRACING, CONFORMING TO THE REQUIREMENTS OF SECTION 704 OF THE STANDARD SPECIFICATIONS.  
ALL BOLTS, NUTS AND WASHERS MUST CONSIST OF ALUMINUM, STAINLESS STEEL OR CADMIUM PLATED STEEL MATERIAL.  
SEE DTL. DWG. NO. 619-20 FOR BREAKAWAY AND SUPPORT DETAILS.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	619-21
SECTION 619, 704	
TREATED WOOD POLE SIGN MOUNTING DETAILS	
EFFECTIVE: AUGUST 1999	
MONTANA DEPARTMENT OF TRANSPORTATION	




NO PASSING PENNANTS

WARNING SIGNS

REGULATORY SIGNS

STEEL BACKBRACE INSTALLATIONS




NO PASSING PENNANTS

REGULATORY AND WARNING SIGNS

STEEL BACKBRACE DETAILS

POLE DIA.	A	B	C
3"	2 1/8"	2 1/8"	3 3/4"
4"	3"	3"	3 3/4"
5"	-	4"	4 1/4"
6"	-	5 1/4"	4 1/4"




SIGN MOUNTING DETAIL

NOTES:  
USE COMMERCIAL QUALITY, MILD STEEL, HOT-DIPPED AFTER FABRICATION. GALVANIZE ACCORDING TO THE SPECIFICATIONS OF AASHTO M 111.  
SEE DTL. DWG. NO. 619-21 FOR APPLICATIONS OF THIS TYPE OF BRACE AND ADDITIONAL SIGN MOUNTING REQUIREMENTS.  
SEE DTL. DWG. NO. 619-20 FOR BREAKAWAY AND SUPPORT DETAILS.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	619-22
SECTION 619	
TREATED WOOD POLE OPTIONAL BACKBRACE	
EFFECTIVE: AUGUST 1999	
MONTANA DEPARTMENT OF TRANSPORTATION	



This Frame left blank




SIGN SIZE	DIMENSIONS				
	A	B	C	D	E
18" x 24"	1/4" x 2" x 1'-11"	15"	9"	18"	18"
24" x 30"	1/4" x 2" x 2'-2"	18"	12"	24"	24"
30" x 36"	1/4" x 2" x 2'-5"	21"	15"	30"	30"
36" x 48"	1/4" x 2" x 2'-8"	24"	18"	36"	36"



**WOOD POST MOUNTING**  
MOUNT 2 CHEVRON SIGNS ON EACH POST WITH EACH PANEL ADJUSTED TO APPROXIMATE RIGHT ANGLE TO ROADWAY CENTERLINE. EXACT LOCATION AND ANGLE TO BE DETERMINED BY ENGINEER.



W1-8 CHEVRON ALIGNMENT SIGNS MAY BE USED AS AN ALTERNATE OR AS A SUPPLEMENT TO DELINEATION TO PROVIDE ADDITIONAL EMPHASIS AND GUIDANCE WHEN A CHANGE IN HORIZONTAL ALIGNMENT EXISTS IN THE ROADWAY.




**NOTES:**  
INSTALL CHEVRONS WITH A MINIMUM 10'-0" HORIZONTAL CLEARANCE AND A 5'-0" VERTICAL MOUNTING HEIGHT.  
SPACING FOR DESIGN PURPOSES IS DOUBLE THE SPACING SHOWN IN THE TABLE ON DTL. DWG. NO. 619-36, UP TO A MAXIMUM CHEVRON SPACING OF 200'. A MINIMUM OF 3 VISIBLE CHEVRONS ARE REQUIRED THROUGH A CURVE.  
FIELD INSPECT THE CHEVRONS AT NIGHT AND ADJUST THEIR LOCATIONS TO ACHIEVE 500' OF VISIBILITY.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 619	DWG. NO. 619-24
CHEVRON MOUNTING DETAILS	
EFFECTIVE: AUGUST 1999	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD



PANELS  
FOR USE ON ROUTE MARKER ASSEMBLIES



MI-5


24" x 24"

MARGIN = NONE

BORDER = 1/2"

CORNER RADIUS = 1/2"

BLACK LEGEND AND BORDER ON  
A RETRO-REFLECTORIZED WHITE  
BACKGROUND.



MI-5


30" x 24"

MARGIN = NONE

BORDER = 1/2"

CORNER RADIUS = 1/2"

BLACK LEGEND AND BORDER ON  
A RETRO-REFLECTORIZED WHITE  
BACKGROUND.



MI-10

24" x 24"


MARGIN = NONE

BORDER = SEE DESIGN ABOVE


CORNER RADIUS = 1/2"

BLACK LEGEND AND BORDER ON  
A RETRO-REFLECTORIZED WHITE  
BACKGROUND.

SHIELDS  
FOR USE ON GUIDE SIGNS



SERIES "D" NUMERALS



SERIES "C" NUMERALS

	10" NUMERALS		12" NUMERALS		18" NUMERALS	
	2 DIGIT	3 DIGIT	2 DIGIT	3 DIGIT	2 DIGIT	3 DIGIT
A	21"	21"	24"	24"	36"	36"
B	24"	30"	24"	30"	36"	45"
J	6"	6"	6 1/2"	6 1/2"	9 1/2"	9 1/2"
R	1 1/2"	1 1/2"	2"	2"	2 1/2"	2 1/2"

BLACK LEGEND ON A RETRO-REFLECTORIZED  
WHITE BACKGROUND WITH NO BORDER.

													RADII			
		A	B	C	D	E	F	G	H	J	K	L	R 1	R 2	R 3	R 4
*	8" NUMERALS	26"	28"	18½"	2⅝"	3"	⅝"	2"	5½"	11"	17"	2¼"	32"	1¾"	⅝"	⅝"
**	10" NUMERALS	32"	34"	22½"	3¼"	3⅞"	⅞"	2½"	6¾"	13¾"	20½"	2"	38½"	2"	¾"	⅜"
***	12" NUMERALS	40"	42"	28"	4"	4½"	½"	3"	8⅞"	17"	25"	2⅞"	48"	2½"	1"	½"

BLACK LEGEND ON A RETRO-REFLECTORIZED WHITE BACKGROUND.

\* USE WITH STANDARD 24" U.S. SHIELD.



\*\* USE WITH STANDARD 30" AND 36" U.S. SHIELD.

\*\*\* USE WITH STANDARD 42" U.S. SHIELD AND ALL INDEPENDENT USE.





NOTES:

CENTER ALL NUMERALS USED ON PANELS AND  
SHIELDS OPTICALLY ABOUT VERTICAL CENTERLINE.

SEE SIGNS AND SIGNING MATERIALS CATALOG  
FOR COMPLETE LISTING OF SIGNS AND SIGN SIZES.  
DESIGNS ARE AVAILABLE FROM THE TRAFFIC UNIT  
FOR SIGNS UNIQUE TO MONTANA.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	619-26
SECTION 619	
SPECIAL DESIGN ROUTE MARKER PANELS AND SHIELDS	
EFFECTIVE: AUGUST 1999	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD





NOTES:

SEE SIGNS AND SIGNING MATERIALS CATALOG FOR COMPLETE LISTING OF SIGNS AND SIGN SIZES. DESIGNS ARE AVAILABLE FROM THE TRAFFIC UNIT FOR SIGNS UNIQUE TO MONTANA.



THE SIGN PANEL CONSISTS OF 3/4" HIGH DENSITY PLYWOOD OR 0.125" ALUMINUM SHEET INCREMENT AS SPECIFIED ON THE PLANS. THE HINGED PANEL CONSISTS OF 0.100" SHEET ALUMINUM.

PAINT ALL HARDWARE VISIBLE ON THE SIGN FACE OR COVER WITH RETRO-REFLECTIVE SHEETING, THE SAME COLOR AS THE SIGN.





SUBMIT SHOP DRAWINGS FOR APPROVAL PRIOR TO FABRICATION.

SUPPLEMENTAL SIGN PANEL BELOW MAJOR SIGN PANEL MUST HAVE RETRO-REFLECTORIZED LEGEND AND BACKGROUND MATCHING COLORS OF MAJOR PANEL.

THE MINIMUM MOUNTING HEIGHT TO THE BOTTOM OF THE SECONDARY PANEL IS 5'-0".

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 619, 704	DWG. NO. 619-30
SIGN HINGE DETAILS	
EFFECTIVE: AUGUST 1999	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD





DIMENSION	INTERSTATE	NON-INTERSTATE
M	4'	4'
N	6'	2' TO 6' *
O	2' MIN.	2' MIN.

\* NORMALLY IN LINE WITH DELINEATORS


#### TYPICAL PLACEMENT

#### PANEL DIMENSION INFORMATION


INTERSTATE			
DIMENSION	D10-4 (1 DIGIT)	D10-5 (2 DIGIT)	D10-6 (3 DIGIT)
A	12.0"	12.0"	12.0"
B	24.0"	36.0"	48.0"
C	0.5"	0.5"	0.5"
D	3.5"	3.0"	3.0"
E	4.0" SERIES "C"	4.0" SERIES "C"	4.0" SERIES "C"
F	3.0"	3.0"	3.0"
G	10.0" SERIES "C"	10.0" SERIES "C"	10.0" SERIES "C"
H	~	3.0"	2.5"
J	4.6"	4.6"	4.6"
K	4.8"	4.8"	4.8"
P	2.0"	2.0"	2.0"
Q	~	13.0"	12.0"
R	~	~	13.0"

NON-INTERSTATE			
DIMENSION	D10-1 (1 DIGIT)	D10-2 (2 DIGIT)	D10-3 (3 DIGIT)
A	10.0"	10.0"	10.0"
B	18.0"	27.0"	36.0"
C	0.5"	0.5"	0.5"
D	2.0"	2.0"	2.0"
E	4.0" SERIES "B"	4.0" SERIES "B"	4.0" SERIES "B"
F	2.0"	2.0"	2.0"
G	6.0" SERIES "C"	6.0" SERIES "C"	6.0" SERIES "C"
H	~	3.0"	3.0"
J	3.6"	3.6"	3.6"
K	3.8"	3.8"	3.8"
P	1.5"	1.5"	1.5"
Q	~	10.0"	10.0"
R	~	~	9.0"

⊗ OPTICALLY CENTER DIGITS ON VERTICAL C OF PANEL.



#### TYPICAL PANEL MOUNTING



#### ROUTE IDENTIFICATION STICKERS

ON NEW SIGNING PROJECTS, FURNISH AND PLACE ROUTE NUMBER IDENTIFICATION STICKERS UPON BACKS OF ALL SIGNS BEFORE FINAL ACCEPTANCE OF THE PROJECT.

PLACE THE STICKER DISPLAYING THE FEDERAL AID ROUTE NUMBER IN THE LOWER LEFT CORNER OF THE MILEPOST SIGN, NEAREST THE EDGE OF THE ROADWAY.

#### NOTES:

MILEPOST PANELS CONSIST OF A RETRO-REFLECTORIZED WHITE LEGEND AND BORDER ON A RETRO-REFLECTORIZED GREEN BACKGROUND.

MOUNT ALL MILEPOSTS ON STEEL U-POSTS (MIN. 2 LB./FT.) EXCEPT THE D10-6, WHICH IS MOUNTED ON A STEEL U-POST (MIN. 3 LB./FT.) AS NOTED IN THE SIGNING PLANS.

USE GALVANIZED OR CADMIUM PLATED 5/16" DIA. BOLT, NUT AND WASHER, AND JAM THREADS AFTER TIGHTENING. USE 5/16" DIA. ALUMINUM OR CADMIUM PLATED BOLT RIVETS OR PAINT RIVET HEADS WITH BRILLIANT GREEN SIGN ENAMEL.

DO NOT RELOCATE OR MOVE A MILEPOST ONCE IT HAS BEEN PROPERLY PLACED.


DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	619-32
SECTION 619	
MILEPOST DETAILS	
EFFECTIVE: AUGUST 1999	
MONTANA DEPARTMENT OF TRANSPORTATION	

#### DESIGN A USAGE:

USE FOR CONTINUOUS DELINEATION AND RT. SHOULDER OF ALL ROUTES.

#### DESIGN H USAGE:

USE ON LT. SHOULDER OF INTERSTATE ROUTES.



DESIGN A (WHITE)  
DESIGN H (YELLOW)

#### DESIGN B USAGE:


USE ON LT. SHOULDER OF INTERSTATE RAMPS.

#### DESIGN G USAGE:

USE ON RT. SHOULDER OF INTERSTATE RAMPS.

#### DESIGN J USAGE:


USE FOR TRUCK ESCAPE RAMPS ONLY.



DESIGN B (YELLOW)  
DESIGN G (WHITE)  
DESIGN J (RED)

#### DESIGN C USAGE:


USE FOR 10' CURVES AND GREATER, BOTH OUTSIDE AND INSIDE OF CURVE.



DESIGN C (WHITE)

#### DESIGN D USAGE:


NON-INTERSTATE ROUTES:  
USE AT APPROACHES WITH STOP OR YIELD SIGNS.  
INTERSTATE ROUTES:  
USE FOR RAMP TERMINATION AT CROSS ROAD.



DESIGN D (YELLOW)

#### DESIGN E USAGE:


SPECIAL USE ONLY.  
FORMERLY USED AT GORES AND ISLAND NOSES.



DESIGN E (YELLOW)

#### DESIGN F USAGE:

USE FOR CURVES LESS THAN 10'; 4' TO 7' 29'; OUTSIDE OF CURVE ONLY.  
7' 30' TO 10'; OUTSIDE AND INSIDE OF CURVE.



DESIGN F (WHITE)


DELINEATOR LEGEND	
DESIGN "A"	—
DESIGN "B"	—
DESIGN "C"	—V—V
DESIGN "D"	—  —
DESIGN "E"	—
DESIGN "F"	— —
DESIGN "G"	—<
DESIGN "H"	—>
DESIGN "J"	—x

NOTE:  
SOME TYPICAL USES ARE SHOWN FOR EACH DESIGN. REFER TO THE MUTCD FOR SPECIFIC GUIDANCE.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	619-34
SECTION 619	
DELINEATOR DETAILS	
EFFECTIVE: AUGUST 1999	
MONTANA DEPARTMENT OF TRANSPORTATION	



This Frame left blank



HORIZONTAL CURVE SPACING TABLE					
DEGREE OF CURVE	SPACING ON CURVE	SPACING ON BOTH APPROACH TANGENTS			
	A	B	C	D	E
0° + TO 30'	300'	400'	400'	400'	400'
30' + TO 1°	300'	400'	400'	400'	400'
1° + TO 2°	225'	400'	400'	400'	400'
2° + TO 3°	160'	320'	400'	400'	400'
3° + TO 4°	130'	260'	400'	400'	400'
4° + TO 6°	110'	220'	330'	400'	400'
6° + TO 8°	90'	185'	275'	400'	400'
8° + TO 12°	75'	150'	230'	300'	400'
12° + TO 20°	60'	125'	185'	300'	400'
20° PLUS	45'	90'	140'	275'	400'

NOTES:

FURNISH RETRO-REFLECTIVE SHEETING ACCORDING TO THE STANDARD SPECIFICATIONS FOR RETRO-REFLECTIVE SHEETING B (HIGH INTENSITY). POSITION DELINEATOR FACES PERPENDICULAR TO TANGENT TO CENTERLINE OF CURVE AS SHOWN IN FIGURE B.

MOUNT DELINEATORS ON METAL U-POSTS (MIN. 1.12 LB./FT.) WITH 3/16" DIA. CADMIUM PLATED BOLT(S). DRILL OR PUNCH A MINIMUM OF TWELVE 3/16" MAXIMUM DIAMETER HOLES ON 1 INCH CENTERS FROM THE TOP OF THE POST. 1/4" SQUARE HOLES MAY BE USED. IF SQUARE HOLES ARE USED, USE A LARGE HEADED BOLT OR AN APPROPRIATE WASHER. JAM THREADS AFTER TIGHTENING THE NUT TO PREVENT REMOVAL.

PLACE DELINEATORS AT A CONSTANT CLEARANCE DISTANCE FROM THE EDGE OF THE PAVEMENT EXCEPT WHERE GUARDRAIL OR OTHER OBSTRUCTIONS INTERFERE. ALIGN THE DELINEATORS WITH THE INSIDE EDGE OF THE OBSTRUCTION. CLEARANCE FOR DELINEATORS IS 6'-0" ON INTERSTATE HIGHWAYS, 2'-0" TO 6'-0" ON PRIMARY AND SECONDARY HIGHWAYS OR AS DETERMINED BY THE ENGINEER. THE STANDARD MOUNTING HEIGHT IS 4'-0" TO THE TOP OF THE POST. SUPPLY POST LENGTHS TO MAINTAIN THE PROPER MOUNTING HEIGHT AND A MINIMUM OF 18" EMBEDMENT.

SPACE DELINEATORS ACCORDING TO THE DISTANCES FOUND IN THE TABLE ABOVE OR AS SPECIFIED IN THE PLANS. IN FIGURE A, IF "F" IS GREATER THAN 20' ADD ONE REGULAR DELINEATOR IN AT "A" SPACING. UNDER NORMAL SPACING, SHOULD A DELINEATOR FALL WITHIN A CROSSROAD OR APPROACH, IT MAY BE MOVED IN EITHER DIRECTION A DISTANCE NOT TO EXCEED ONE QUARTER OF THE NORMAL SPACING. ELIMINATE DELINEATORS STILL FALLING IN SUCH AREAS.

ALL DELINEATOR REFLECTORS HAVE 3/4" CORNER RADIi EXCEPT DESIGN "E".

MOUNT THE DELINEATOR REFLECTOR 1" BELOW THE TOP OF THE METAL U-POST.

WHEN THE ROADWAY ADT IS LESS THAN 900, DELINEATE ALL CURVES WITH DEGREE OF CURVATURE OF 4° OR GREATER.



CONTINUOUSLY DELINEATE ROADWAYS WHEN THE ADT IS 900 AND GREATER, OR BY ENGINEERING JUDGEMENT.

DETAILED DRAWING

REFERENCE DWG. NO.  
STANDARD SPEC. 619-36  
SECTION 619, 704


DELINEATOR PLACEMENT  
DETAILS

EFFECTIVE: AUGUST 1999


 MONTANA DEPARTMENT  
OF TRANSPORTATION  MONTANA  
CADD



TYPE 1  
X3-2




NOTE:  
TYPE 1 OBJECT MARKERS HAVE YELLOW REFLECTORS ON A YELLOW OR BLACK BACKGROUND OR AN ALL YELLOW RETRO-REFLECTORIZED PANEL OF THE SAME SIZE. IF USED AS END OF ROAD MARKERS, TYPE 1 MARKERS ARE RETRO-REFLECTORIZED RED OR HAVE RED REFLECTORS ON A RED OR BLACK BACKGROUND.




TYPICAL USE AND PLACEMENT  
PLACEMENT OF X3-2 IS USED ONLY AS OPTIONAL TO ENHANCE TARGET VALUE WHEN NEEDED.

TYPE 2  
X3-3





ALTERNATE DESIGN FOR TYPE 2 OBJECT MARKERS IS A YELLOW RETRO-REFLECTORIZED PANEL OF THE SAME SIZE.



PLACE POST AND PANEL(S) SO THAT PANEL(S) ARE DIRECTLY ADJACENT TO INNER-MOST EDGE OF OBJECT NEAREST TRAVELED WAY.

TYPICAL USE AND PLACEMENT

TYPE 3  
OM-3  
(OM-3L SHOWN)




TYPICAL USE AND PLACEMENT

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	619-38
SECTION 619	
OBJECT MARKER DESIGN AND PLACEMENT DETAILS FOR OBSTRUCTIONS ADJACENT TO OR WITHIN HIGHWAYS	
EFFECTIVE: AUGUST 1999	



This Frame left blank




NOTES:



USE FLEXIBLE DELINEATORS SIMILAR TO THE DESIGN AND SPECIFICATIONS SHOWN ON THIS SHEET OR IN THE SIGNING PLANS OF THE CONTRACT.

MOUNT OR EMBED FLEXIBLE DELINEATORS TO THE MANUFACTURER'S SPECIFICATIONS.

RETRO-REFLECTORIZE FLEXIBLE DELINEATORS, IF REQUIRED IN PLAN SPECIFICATIONS, BY THE ADDITION OF DELINEATOR CRYSTALS, EITHER 1 1/2" x 7" OR 3" DIAMETER, OR BY ADDING TWO 3" MINIMUM WIDTH BANDS OF RETRO-REFLECTIVE SHEETING TYPE HI, 360° AROUND THE TOP OF THE DELINEATOR. USE THE COLOR OF THE DELINEATOR CRYSTALS OR RETRO-REFLECTORIZED MATERIAL AS SHOWN IN THE SIGNING PLANS OF THE CONTRACT OR THE MUTCD.


THE EXACT LOCATION AND PLACEMENT OF THE FLEXIBLE DELINEATORS ARE SHOWN IN THE SIGNING PLANS.




DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	619-40
SECTION 619	
FLEXIBLE DELINEATORS	
EFFECTIVE: AUGUST 1999	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD



# B I BARRICADE B (I)-L SHOWN




FRONT VIEW




RIGHT  
SIDE VIEW

BARRICADE DETAILS



REAR VIEW



LEFT  
SIDE VIEW

SIGN MOUNTING DETAILS

## NOTES:

CONSTRUCT ALL BARRICADES OF COMMERCIAL GRADE S4S LUMBER. USE 3/8" DIA. GALVANIZED CARRIAGE OR CADMIUM PLATED BOLTS, WASHERS AND NUTS FOR ALL CONNECTIONS.

PAINT ALL BARRICADES WITH TWO COATS OF WHITE PAINT IN ACCORDANCE WITH SECTION 710 OF THE STANDARD SPECIFICATIONS.


ALL BARRICADES HAVE ALTERNATING RETRO-REFLECTIVE RED AND WHITE STRIPES, 6" IN WIDTH AT AN ANGLE OF 45° TO THE VERTICAL, SLANTING DOWNWARD TOWARD THE SIDE OR SIDES ON WHICH TRAFFIC IS TO FLOW. NOMINAL DIMENSIONS OF ROLL MATERIAL FOR STRIPES IS ACCEPTABLE.

BARRICADES DESIGNATED "L" ARE PLACED ON THE LEFT SIDE OF APPROACHING TRAFFIC. BARRICADES DESIGNATED "R" ARE PLACED ON THE RIGHT SIDE OF APPROACHING TRAFFIC.


RETRO-REFLECTORIZE ALL BARRICADES WITH THE SHEETING MOUNTED ON A SHEET ALUMINUM BACKING AT LEAST 0.019" THICK. USE ALUMINUM ALLOY 6061-T6 OR AA5052-H38 CONFORMING TO ASTM DESIGNATION B 209. SECURE RETRO-REFLECTIVE ALUMINUM SHEETING WITH ALUMINUM NAILS.

DETERMINE THE POST LENGTHS IN THE FIELD, COMPLYING WITH THE MOUNTING HEIGHTS AND FOUNDATION DEPTHS LISTED ON THIS SHEET.

# B III BARRICADE B (III)-L & R SHOWN




FRONT VIEW




RIGHT  
SIDE VIEW

BARRICADE DETAILS



REAR VIEW




LEFT  
SIDE VIEW

SIGN MOUNTING DETAILS


DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	619-42
SECTION 619	
PERMANENT BARRICADE DESIGN DETAILS	
EFFECTIVE: AUGUST 1999	
MONTANA DEPARTMENT OF TRANSPORTATION	



This Frame left blank



PLACEMENT DETAILS



NOTES:

FURNISH AND PLACE INSTALLATION DATE TAGS ON ALL SIGNS PRIOR TO FINAL ACCEPTANCE OF THE PROJECT.


THE TAGS DISPLAY THE YEARS IN WHICH THE SIGNS WERE INSTALLED. SEE THE COLOR SEQUENCE TABLE SHOWN ON THIS DRAWING FOR THE APPROPRIATE COLORS. DATE TAGS ARE TO BE RETRO-REFLECTIVE.

PLACE A TAG ON THE BACK OF EACH SIGN, LOCATED NEAR THE LOWER CORNER OF THE SIGN NEAREST THE EDGE OF ROADWAY, TO BE VISIBLE FROM THE ROADWAY AS SHOWN IN THE EXAMPLES ABOVE.


PLACE TAGS ON ANY NEW SIGN INSTALLED IN THE FIELD AS ROUTINE MAINTENANCE BY MDT FORCES. MAINTENANCE DESIGN DATE TAGS CAN BE ORDERED FROM THE SIGN SHOP IN HELENA.

DATE TAG DETAIL

DATE TAG COLOR SEQUENCE	
DATE TAG COLOR CORRESPONDS TO THE LAST DIGIT OF THE INSTALLATION YEAR AS FOLLOWS:	
0 - YELLOW	5 - RED
1 - WHITE	6 - PURPLE
2 - LIGHT BLUE	7 - ORANGE
3 - GOLD	8 - BLUE
4 - LIGHT GREEN	9 - GREEN

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 619	DWG. NO. 619-44
INSTALLATION DATE TAGS	
EFFECTIVE: AUGUST 1999	
 MONTANA DEPARTMENT OF TRANSPORTATION	





NOTES:


ADJUST MANHOLES UPWARD WITH ADJUSTING RINGS UNDER FRAME.

ADJUST MANHOLES DOWNWARD BY REMOVING CONE AND BARREL SECTIONS AS NECESSARY AND REPLACING WITH SECTIONS OF LENGTH REQUIRED TO MATCH GRADE.

SLOPE MANHOLE FRAME AS REQUIRED TO MATCH SLOPE OF STREET.

MAKE FINAL MANHOLE ADJUSTMENTS BEFORE PAVING.

MANHOLE ADJUSTMENT DETAIL






NOTES:

ADJUST WATER VALVES UPWARD OR DOWNWARD AS REQUIRED.

MAKE FINAL ADJUSTMENT BEFORE PAVING.

VALVE BOX ADJUSTMENT DETAIL

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	621-00
SECTION 604, 621	
MANHOLE AND VALVE BOX ADJUSTMENT DETAILS	
EFFECTIVE: AUGUST 1999	
 MONTANA DEPARTMENT OF TRANSPORTATION  MONTANA CADD	



NOTES:


ADJUST MANHOLES UPWARD WITH ADJUSTING RINGS UNDER FRAME.

ADJUST MANHOLES DOWNWARD BY REMOVING CONE AND BARREL SECTIONS AS NECESSARY AND REPLACING WITH SECTIONS OF LENGTH REQUIRED TO MATCH GRADE.

SLOPE MANHOLE FRAME AS REQUIRED TO MATCH SLOPE OF STREET.

MAKE FINAL MANHOLE ADJUSTMENTS BEFORE PAVING.

MANHOLE ADJUSTMENT DETAIL





NOTES:

ADJUST WATER VALVES UPWARD OR DOWNWARD AS REQUIRED.


MAKE FINAL ADJUSTMENT BEFORE PAVING.

VALVE BOX ADJUSTMENT DETAIL


DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	621-05
SECTION 604, 621	
OPTIONAL MANHOLE AND VALVE BOX ADJUSTMENT DETAILS	
EFFECTIVE: DECEMBER 2002	
 MONTANA DEPARTMENT OF TRANSPORTATION  MONTANA CADD	



This Frame left blank




PLAN



PROFILE



MEDIAN WIDTHS 36' TO 76'

LOCATE AND CONSTRUCT TURNOUTS ABOVE IN CONJUNCTION WITH DITCH BLOCKS IF AT ALL POSSIBLE. PROVIDE DRAINAGE WHEN NECESSARY.




STANDARD U-TURN FOR NARROW MEDIANS


NOTES:  
NARROW MEDIANS, MEDIAN WIDTHS GREATER THAN 76 FT. AND INDEPENDENT ROADWAYS REQUIRE SPECIAL DESIGN.  
GRADES: UNIFORM BETWEEN INSIDE SHOULDERS OF MAIN TRAVELED WAY EXCEPT FOR SPECIAL DESIGN.  
SURFACING: SEE PLANS FOR QUANTITIES.  
DRAINAGE: USE 18" OR 24" CULVERTS IF REQUIRED.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	900-00
SECTION	
U-TURN MEDIAN OPENINGS ON CONTROLLED ACCESS HIGHWAYS	
EFFECTIVE: AUGUST 1999	
 MONTANA DEPARTMENT OF TRANSPORTATION	 MONTANA CADD






SINGLE MAILBOX ASSEMBLY \*



PLATFORM



BRACKET

NOTES:

GALVANIZE ALL MATERIALS PER AASHTO M 111.

STAKE MAILBOX LOCATIONS BEFORE INSTALLATION FOR PROPER HEIGHT AND DISTANCE FROM THE ROADWAY. ONCE STAKED, NOTIFY THE ENGINEER AND THE POST OFFICE. THE ENGINEER AND POSTMASTER/MAILCARRIER ARE ALLOWED 48 HOURS TO REVIEW AND MODIFY THE STAKED LOCATIONS PRIOR TO FINAL INSTALLATION.


\* OTHER CRASH TESTED MAILBOX SUPPORTS AND ASSEMBLIES MAY ALSO BE USED.

LOCATE THE MAILBOX 8 TO 12 INCHES OUTSIDE THE EDGE OF THE SHOULDER OR 6 TO 12 INCHES FROM THE FACE OF CURB.


USE MAILBOXES MEETING THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS.

SEE "A GUIDE TO MAILBOX SAFETY IN MONTANA", 1996 EDITION, FOR ADDITIONAL INFORMATION.


DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	900-05
SECTION	
MAILBOX DETAIL	
EFFECTIVE: AUGUST 1999	
MONTANA DEPARTMENT OF TRANSPORTATION          MONTANA CADD	



PIPE/POST CONNECTION  
ROADWAY VIEW



TAIL PIPE CLAMP



SECTION A-A

NOTES:

GALVANIZE ALL MATERIALS PER AASHTO M 111.


STAKE MAILBOX LOCATIONS BEFORE INSTALLATION FOR PROPER HEIGHT AND DISTANCE FROM THE ROADWAY. ONCE STAKED, NOTIFY THE ENGINEER AND THE POST OFFICE. THE ENGINEER AND POSTMASTER/MAILCARRIER ARE ALLOWED 48 HOURS TO REVIEW AND MODIFY THE STAKED LOCATIONS PRIOR TO FINAL INSTALLATION.

OTHER CRASH TESTED MAILBOX SUPPORTS AND ASSEMBLIES MAY ALSO BE USED.

LOCATE THE MAILBOX 8 TO 12 INCHES OUTSIDE THE EDGE OF THE SHOULDER OR 6 TO 12 INCHES FROM THE FACE OF CURB.

USE MAILBOXES MEETING THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS.

SEE "A GUIDE TO MAILBOX SAFETY IN MONTANA", 1996 EDITION, FOR ADDITIONAL INFORMATION.



MAILBOX SUPPORT  
STEEL PIPE WITH FITTINGS AND STEEL FENCE POST

NOTES:

GALVANIZE ALL MATERIALS PER AASHTO M 111.

STAKE MAILBOX LOCATIONS BEFORE INSTALLATION FOR PROPER HEIGHT AND DISTANCE FROM THE ROADWAY. ONCE STAKED, NOTIFY THE ENGINEER AND THE POST OFFICE. THE ENGINEER AND POSTMASTER/MAILCARRIER ARE ALLOWED 48 HOURS TO REVIEW AND MODIFY THE STAKED LOCATIONS PRIOR TO FINAL INSTALLATION.

OTHER CRASH TESTED MAILBOX SUPPORTS AND ASSEMBLIES MAY ALSO BE USED.

LOCATE THE MAILBOX 8 TO 12 INCHES OUTSIDE THE EDGE OF THE SHOULDER OR 6 TO 12 INCHES FROM THE FACE OF CURB.

USE MAILBOXES MEETING THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS.

SEE "A GUIDE TO MAILBOX SAFETY IN MONTANA", 1996 EDITION, FOR ADDITIONAL INFORMATION.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	900-10
SECTION	
OPTIONAL MAILBOX DETAIL	
EFFECTIVE: AUGUST 1999	
MONTANA DEPARTMENT OF TRANSPORTATION          MONTANA CADD	